

INDUSTRIAL FILTRATION

BY

ARTHUR WRIGHT, M.E.

VOLUME I

*THE MODERN LIBRARY OF
CHEMICAL ENGINEERING*

BOOK DEPARTMENT

The CHEMICAL CATALOG COMPANY, Inc.

19 EAST 24TH STREET, NEW YORK, U. S. A.


1923

1076


660.28424

N2.2.1

COPYRIGHT, 1923, BY
The CHEMICAL CATALOG COMPANY, Inc.
All Rights Reserved



Printed at
J. J. Little & Ives Company
New York, U. S. A.



The MODERN LIBRARY of, CHEMICAL ENGINEERING

So rapid has been the development of the technology of chemical processes during the past decade it is only natural that literature on the subject has failed to keep pace.

Those in a position to write authoritative books have been too busy solving practical problems to chronicle their experiences for others, and the feeling that chemical engineering data were still coming in at a rapid rate caused many to hesitate to publish data which might soon be rendered out of date by further advances in practice.

During the past two years, however, it has become generally recognized that the best interests of the industry and the profession demand a literature dealing with the fundamental processes of chemical engineering, not only as a basis for future progress but as an economical factor in current operation, as well as for the instruction of the younger men entering the profession.

Such a literature Germany has long had, and any American who has worked or studied in Germany knows what a great factor it has been in Germany's chemical development. It is not believed, however, that any good purpose could be served by a general translation of the German books, as much of the equipment discussed therein never has been and never will be used in this country. As a matter of fact, much of this German literature is now out of date, not only in this country but abroad, and in many instances our technical knowledge of chemical processes outstrips the world.

In view of these conditions, The Chetnical Catalog Company has undertaken the work of interesting experts of indisputable standing in their several lines, in writing a series of technological works dealing with such fundamental processes in chemical engineering as Evaporation, Filtration, Distillation, Heat Transfer, Drying, Transportation of Liquids, Compression of Gases, Mechanical Handling of Materials, Grinding, Pulverizing, etc.

The scope of this Series naturally cannot be fixed at this time, but

4 MODERN LIBRARY OF CHEMICAL ENGINEERING

books in this group, to be known as the "Modern Library of Chemical Engineering," will develop as chemical engineering knowledge develops. An effort will be made to drag forth facts and little tricks of the trade from their hiding places so that the current status of all the fundamental subdivisions of chemical engineering can be presented without reserve. Where this is not possible through the agency of a single author or group of authors, the co-operation of all the owners of facts will be sought to that end, and an editor or board of editors will be appointed to handle existing data with fairness to all.

The Modern Library of Chemical Engineering series will be uniform in format and binding. Some of the subjects with their authors, in addition to this volume on "Industrial Filtration" by Arthur Wright, that have thus far been definitely decided upon are as follows:—

Heat Transfer and Evaporation

By W. L. Badger,

Theory and Practice of Evaporation

By A. L. Webre and C. S. Robinson,

Fractional Distillation

By E. H. Leslie and E. M. Baker.

Announcements regarding the progress of the Modern Library of Chemical Engineering will be made from time to time, and of course more detailed information will be furnished at any time upon request. The publishers will welcome suggestions that will help improve the service these books on the technology of chemical processes are expected to render to chemical engineers, plant operatives, research men and students.

The CHEMICAL CATALOG COMPANY, Inc.

PREFACE

In chemical engineering, the industrial practice of filtration occurs so frequently that it must be considered a distinct department, and the subject of a volume by itself in any series attempting to cover chemical engineering at all completely.

This has been written as that volume in such a series, in an endeavor to make it a handbook useful to plant chemists and engineers, to superintendents, foremen and operators. It may also act as a textbook for students and cadet engineers, comparing for them the various designs of filters. Lay language has been used so that plant managers and purchasing agents, reading it as laymen, may better understand how to select the special filter for their particular duty.

This book sets on record some results of the author's own twelve years' filter experience, and there is therefore no bibliography to append.

Every effort has been made to keep the book practical, so that even Part I, "Theory of Filtration," is largely an accumulation of "tricks of the trade." Some new ideas are presented so that there is novelty in the work, which otherwise is made up of an exposition of standard practice. Such an idea, for instance, as the use of "muddied" wash-water ought alone to better many installations. Elimination of deep technical discussion has been premeditated in the belief that special papers before societies, or even a separate work, is a better means of treating this phase of filtration.

A brief explanation of the general plan of the book may be welcome here so that the reader can quickly get a bird's-eye view of the contents of the whole volume before entering its details.

To make the mass of technical data easy to read and understand, outline form is adhered to as far as practicable throughout. The Table of Contents gives at a glance the general arrangement of the entire subject matter, showing classification of subordinate material. Each chapter then follows definite outline form in turn, so that, in review, a summary and digest can be readily made.

In Part I, "Theory of Filtration," it is shown that as step follows step

in plant practice, certain laws of filtration become apparent. Application of these laws through certain mechanics, as set down in Part II, "Mechanics of Filtration" leads to the development of better "Filter Practice" which is the subject of Part III and the theme of the whole book. Concisely, the book's aim is to add a step to filter progress, and this is attempted in two ways:

- (1) primarily by emphasizing the importance of mastering the fundamental laws underlying filtration and applying them in various ways.
- (2) by analysis of filter development through criticism of representative types of machines as a key to future progress.

For purposes of ready comparison, each filter description in turn is reduced to a similar outline showing its development, operation, and drawbacks, and the advantages which explain its basis of application to certain work. Discussion of the drawbacks of each filter is included, not in the spirit of commercial criticism of patent features, but because it is plain that no one filter is applicable to all fields, and unless the limitations of each are understood, wrong selections may be made. In filters applicable to the same field, it is only by impartially balancing the merits and defects of each that decision as to the particular machine best adapted for the particular duty can be determined. By knowing the weakness of each, better appreciation of the advantages is gained.

Acknowledgment is made to the filter manufacturers for help in furnishing data, cuts, etc., which made the assembling of this material easier for the writer and more valuable to the reader.

Criticisms from filter manufacturers and filter purchasers are invited in the hope that their suggestions can improve future editions of this book and further the cause of better filtration.

Effort has been made here to help in the advance from rule of thumb methods, in the conviction that progress in the art would have been faster if the fundamental laws of filtration had been more firmly impressed long ago. This, then, is first emphasized; and, secondly, stress is laid on the need for wider filter knowledge among operators. Advance must be made through an educational campaign, since filtration generally has remained a little appreciated art. It is desirable that the young graduate engineer be acquainted with present-day filter practice, and it is still more desirable that practical plant men understand what can be achieved so that they will not too easily rest content with the operation of their own filters.

That they may find this profitable reading, and from it gain an appreciation of the art that will make them more critical of filters and filter operation, is the wish of the writer,

ARTHUR WRIGHT, M.E.

April, 1923.

The MODERN LIBRARY of **CHEMICAL ENGINEERING**

In addition to the present volume on "Industrial Filtration" by Arthur Wright, the following books are included in this Series :—

Heat Transfer and Evaporation
By W. L. Badger,

Theory and Practice of Evaporation
By A. L. Webre and C. S. Robinson,

Fractional Distillation
By E. H. Leslie and E. M. Baker.

Other books to be included in the Series, which is briefly described in the preceding pages, will be announced from time to time. Among the subjects to be treated are Drying, Transportation of Liquids, Mechanical Handling of Materials, Compression of Gases, Electric Heat (Its Application to Industrial Processes), Grinding and Pulverizing.

LIBRARY

BANGALORE

CONTENTS

	PAGE
FUNCTIONS OF INDUSTRIAL FILTERS	13

PART I

Theory of Filtration

CHAPTER		PAGE
I	CLARIFICATION	21
II	CAKE BUILDING	31
III	CAKE WASHING	47
IV	CAKE DRYING	59
V	CAKE DISCHARGING	66
VI	FILTER MEDIA	79
VII	THEORY OF FILTER APPLICATION	87
VIII	AUXILIARY EQUIPMENT	91

PART II

Mechanics of Filtration


I	THEORY AND MECHANICS AS RELATED TO PRACTICE	101
II	BAG FILTERS	103
III	PLATE AND FRAME PRESSES	108
IV	SUCTION LEAF FILTERS	123
V	PRESSURE LEAF FILTERS	137
	Section 1 The Kelly Filter	139
	2 The Sweetland Filter	160
	3 The Vallez Filter	188
VI	ROTARY VACUUM FILTERS	199
	Section 1 Oliver Filter	201
	2 American Continuous Filter	221
	3 FEinc Apparatus	230

CHAPTER		PAGE
VII	SPECIAL FILTERS AND CLARIFIERS	245
Section I Dorr Apparatus		247
2 Merrill Filter		260
3 Atkins-Shriver Press		264
4 Burt Filter		269
5 Zenith Rotary Hopper Dewaterer		275
6 Oliver Rotary Sand Table		278
7 FEinc Acid Sand Filter		282

PART III

Filter Practice

I	APPLICATION OF DIFFERENT TYPES OF FILTERS	289
II	RELATION OF FILTRATION TO OTHER PLANT OPERATIONS	298
Section I Drying, Evaporation, Etc.		299
2 Combination Filtering and Drying		302
III	PLANT PRACTICE	314



FUNCTIONS OF INDUSTRIAL FILTERS.



FEB 21 1923

FUNCTIONS OF INDUSTRIAL FILTERS.

Filtration Defined.

Filtration, i.e., "separation of solids in suspensions from a liquid vehicle," has an important industrial function, for clarification plays a part in the majority of chemical operations, and the uses to which filters can be applied are increasing at a high rate.

To begin with, the difference must be defined here between *industrial filters* and other filters (such as: municipal water filters; boiler feed-water filters; filters for recovery of machine oil and the separation of water from gasoline; household drinking water filters, etc.) for it is the *industrial filter* only that is our particular subject. This is the filter that is used for chemical engineering. The chief difference between industrial and other filters is this: the industrial filter handles a large volume of solids in a relatively small volume of liquid, and is equipped to recover the solid and discharge it in a semi-dry state. Other filters generally handle large volumes of liquid with small solid content, these solids being measured in grains per gallon as against the industrial's pounds per gallon and tons per hour. The solids in these other filters are disposed of as mere muddy back-wash.

The function of the industrial filter is to put laboratory precipitate-filtering into large-scale commercial practice. In the laboratory, precipitates are filtered through filter paper in funnels. In industry, the filtering is done by various types of machines which will be discussed later. In laboratory work, pure reagents are used and the precipitates to be filtered are formed according to chemical formulae. In commercial practice, however, the reagents, purchased in bulk, are often far from pure and must themselves be clarified of extraneous matter before they can be used to throw down the precipitate which is to be recovered as a commercial product. The industrial filter may thus play two parts in one process.

An idea of the extensive use of the industrial filter may be realized by running over only a few of the industries in which the filter functions, as for instance:

chemical and dye works,
food product plants (i.e., corn syrup, starch, cane and beet sugar manufacture, etc.),
paper manufacture,
pottery works,
oil refineries,
mining and metallurgical mills,
municipal sewage disposal plants,
etc., etc.

There are, of course, obvious applications for industrial filters, but the advance made in filter design and operation has opened up new uses such as:

- leaching solubles from ores, organic matter, etc.,
- conditioning solids to be dried,
- agglomerating dusting materials,

and other work not essentially filtration in the sense of its popular definition as "separating solids from liquids."

Industrial filtration is "a lowly art," for many years governed only by rule-of-thumb methods. But, with the introduction of the modern filter, we are beginning to recognize that there are fundamental principles underlying their best operation. Filtration is no longer summed up in the old adage "get a good hard cake," but comprises, in addition to clarification of the liquor, the complete washing of the soluble from the deposited solids; the drying of the cake; thorough discharge of the cake so that the filter medium is maintained in a free-filtering condition for recurring runs, and a consideration of pumps, filter cloths and other auxiliaries. It is only when these principles are understood and applied that the filter station reaches its true economy and efficiency. These underlying principles, therefore, will be discussed in detail under these separate headings:

1. Clarification
2. Cake Building
3. Cake Washing
4. Cake Drying
5. Cake Discharge
6. Filter Media
7. Theory of Filter Application
8. Auxiliary Equipment.

The different makes of machines will be described fully and individually under the heading "Mechanics of Filters" but it is well to have clearly defined at the beginning the general types of filters in order to avoid confusion by references thereto in earlier discussions. Filters may be divided into classes as follows:

1. Plate and Frame (or "chamber") filter presses
2. Leaf filters (both vacuum and pressure)
3. Continuous filters (both rotary drum and rotary leaf)
4. Special filters (bed filters, etc.)

To illustrate the difference between chamber and leaf filters, "suppose that we have to clarify a muddy liquid with no other means than a bag, a piece of pipe and a string. We may then proceed, after inserting the pipe into the bag and fastening the bag to the pipe, in either of two ways:

- (1). We may pour the muddy liquid into the bag, catch the mud *inside* the bag and the clarified liquid in a receptacle below, or—

- (2). We may distend the bag with any convenient means to prevent it from collapsing, submerge the bag into the muddy liquid and draw the filtrate from the pipe. In this case the mud deposits on the *outside* of the bag."

The first case illustrates the principle of the chamber press, the chamber being the bag. The second illustrates the principle of the leaf filter, the bag in this instance being the leaf.

Plate and Frame Filter Presses.

These consist of a series of enclosed chambers into which the muddy liquid is pumped. The walls of these chambers are made of filter cloth hung on solid corrugated plates and the liquid, filtering through this cloth, is drained off while the solids are deposited inside the chambers. These chambers are made up of alternate cloth-covered plates and spacers (or "frames") clamped together.

Leaf Filters.

These consist of a series of non-collapsible bags (called leaves) inserted in a tank which is open for vacuum leaf filters and closed for pressure leaf filters. In vacuum leaf filters the liquid is sucked into the leaf; in the pressure type it is forced into the leaf by pump pressure. In either case, the solids are deposited upon the *outside* of the leaf.

A mark of distinction between leaf and chamber presses is their difference in discharge. In chamber presses, the chambers are opened and the deposit, or cake, is removed by hand. In leaf filters a reverse current of steam or compressed air blows the cake loose from the leaf automatically and hand labor is eliminated. Leaf filters may be discharged when the cake is of any thickness, but plate and frame presses are discharged only when each chamber is built up solid with cake.

Continuous Filters.


Continuous filters are developments of leaf filters and are of two types, —(1) drum, and (2) sectionated rotatable leaf.

Continuous Rotary Drum Filters.—A rotating drum covered on its periphery with filter cloth is partly submerged in a tank of muddy liquor. The filter cloth is divided into parallel sections. On each section a separate cake is formed by separate vacuum pipes which draw off the filtrate while the drum revolves through the liquor. As the drum rotates, the cake is lifted from the tank and before it turns over to a point where it would again enter the liquor, the vacuum is shut off, section by section, allowing the cake to be removed from the drum and leaving the cloth clear for a new cake to be built upon it by return of vacuum. This filter is therefore clarifying the liquid by building up and discharging the cake in a continuous cycle.

Continuous Rotary Leaf Filters.—This type of filter consists of a series of circular leaves rotating on a central shaft. Each leaf is divided

Courtesy Oliver Continuous Filter Company

FIG. I.—A Most Popular Modern Filter
Oliver Continuous Filter—Rotary Drum Type.



into perhaps 10 sectors and each sector acts as an individual leaf in itself, being equipped with its own vacuum outlet at the center. As these leaves rotate in the tank they are partly submerged in a tank of muddy liquor and the cakes, formed by the vacuum, are deposited upon the face of the leaves. The cakes are discharged by reverse air current supplanting the vacuum just prior to the point of submergence in the cycle.


The marked difference between rotary drum filters and rotary disk filters is that the filter area in the first is distributed *around* the shaft on the periphery of the drum, while in the other it is the surface of the disk on both sides of each leaf, at *right angles* to the shaft. The principle of operation and discharge is identical in both.

Bed Filters.

Bed filters are horizontal filtering surfaces consisting of crushed stone or gravel topped with sand or filter cloths laid on false bottoms. These filters are largely confined to work with acids and are operated either by gravity or suction. Discharge is effected by removing a screen or other stripping member which lifts the cake from the bed.

The art of filtration is chiefly a summary of "tricks of the trade," but industrial filtration is a branch of chemical engineering unique in the number and importance of small factors, or constants. This fact has been borne out many times when failure to make a filter develop desired capacity has been changed to complete success by so small a factor as ten degrees difference in temperature, or 15 per cent added solids of suspension. Emphasis on this is made here as a caution against hoping that we may develop formulae of general value. Any formulae for practical use cannot be overladen with constants, and without these constants no filtration formula is applicable, except in a few isolated cases. Obviously, such formulae are not worth the work necessary for their development.

Machines and methods herein described are those developed in the United States, since our subject is *American Industrial Filtration*.



PART I.
THEORY OF FILTRATION.

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000

1000


1000

1000

1000

1000

1000



LIBRARY

MANGALORE *

Chapter I.

Clarification.

In all chemical engineering there is probably no branch that combines so intimately the functions of the chemist and the engineer as does filtration.

The quantities to be filtered in most cases are measured in tons, so that the *engineer* has much for his attention in respect to handling these materials. The filter is the main unit in filtration practice, but tanks equipped with agitators for mixing the material for the filter; pipe lines and pumps for introducing the mixed material into the filter; pumps for developing filtering force, whether it be pressure or vacuum; receivers for clarified material and its conduction to the next process, etc., are all strictly in the engineer's domain.

Proper precipitation of the solids of suspension; control of the temperature at which the precipitation takes place; specifying the density at which the material must be handled; prescribing the corrosive content and nature of the liquid, together with the allowable materials of construction and other similar points, are all distinctly in the *chemist's* province.

Of these two divisions, *the part played by the chemist is the most important*. It is for this reason that the following chapters on the Theory of Filtration appear before those on the Mechanics of Filtration, in order to give the control chemist a better insight into the peculiarities of filtration so that he can handle his material most economically.

By utilizing a combination of the various phases of filtration (for example: combining uniform-cake-building with displacement-washing; or, limited-cake-building with drying) filters are applicable today where hitherto they could not be considered. In this it is seen how application of the theory of filtration results in progress and development of its mechanical features. It is therefore hoped that better acquaintance with the Theory of Filtration will develop more field of applications for these machines.

Definition.

Clarity of filtrate is, in the vast majority of cases, the primary object of the filter, but, as will be shown later, it is too often over-emphasized. When absolute clarity is not required, a different attack than that which will be outlined here is often possible.

The number of cases where capillary attraction and adsorptive action

are real factors in clarification are relatively so few and far between that this general law can be defined:

Clarity of filtration is due to superlative straining of the particles of suspension from the liquid in which they are suspended.

This statement will doubtless call for criticism from some quarters, but it is held to be basic by reason of success obtained in handling a large number of problems completely ignoring capillary and adsorptive actions and concentrating solely on straining.

Open Woven Fabrics.

The choice of straining or filter mediums determines the nature of the straining or filtering. It is the popular belief that woven fabrics effect clarification by surface filtration, i.e., that the solids are caught on the surface of the fabric and build up to form a cake. Such a belief is rational when comparing a woven fabric with a granular bed filter medium. It is obvious that any particle penetrating the surface of a sand bed has opportunity to be caught in the interior of the bed before issuing from the false bottom as a cloudy filtrate. Both theories are, however, subject to liberal interpretation, for we have only to witness the number of times the filter cloth is clogged and not opened even though the surface be hand-cleaned with vigorous scrubbing and the cloth given reverse washings. Or, again, to watch the working of boiler feed-water filters wherein the initial flow is not clear and after running clear can be run for a period only before the filter must be cleaned.

The answers are obvious. In the former, solids penetrate the cloth and are held firmly in the meshes of the cloth,—surely not true surface filtration. In the second case, clarification begins only when the retained solids form of themselves a filter medium on the top of the sand bed. The reason that the rate of flow is approximately constant in sand filters is because the deposit on the bed, as it builds up, has the effect of building up a resistance to the flow which increases the filter pressure. At some point this pressure builds up sufficiently to force the deposit through the surface of the sand bed and to work into the interior. Manifestly, if the filter is run long enough, the solids will issue through with the filtrate. In point of fact, therefore, the initial filtration through fabrics approximates filtration through-a-depth and with sand beds true clarification commences with surface filtration.

Until recently, the practice was to choose a densely woven filter cloth so that none of the solids could pass through it. This disregarded the principle that *the initial coating or film, not the fabric itself, is the true filter medium.*

With the above principle in mind, we have ground for the contention that too many industrial filters are still equipped with too dense a filter cloth. Mechanical wear will often dictate the choice of a heavy cloth,

but this should not be the signal to use a dense cloth. It cannot be expected that with the use of open cloths the initial clarity will be satisfactory, but it will be found that there is no hardship in refiltering the first runnings. Usually the filtrate brightens up readily and the amount to be returned can be added to the feed of the filter or else run through a separate filter which is used as a "polisher." Local conditions will govern the best means of handling this cloudy filtrate. It is not practical to equip filters with a more open cloth or a thinner fabric and not provide for the handling of cloudy filtrate. Absolute clarity can sometimes be obtained with such cloths by working with a low initial pressure, as for instance, gravity feed. There are cases where this is good practice, but as a general rule it is precarious, for it is required only that an insufficient deposit be made on the cloth when the pressure line is opened and the solids will be pushed through into the filtrate. The basic idea is that clarification shall be effected by virtue of the deposit of the solids on the filter cloth rather than that the cloth shall be the real medium. If this be carried out, it will be found that those particles that clog the dense cloth pass through into the filtrate so that the open cloth is maintained in a free filtering condition for recurring runs. This, of course, is obvious and need not be elaborated upon save to consider further the kind of cloth to use.

What is true about providing for cloudy filtrate when using cotton filter cloths is even more important when using metallic cloths. These fabrics are designed as permanent mediums, and their initial cost is justified only by their long life. Consequently, how much more fatal it is to allow these cloths to clog up! Users are the best judges of the delays and trials when caustic, acid, and heat treatments are resorted to in order to regain their porosity. So much of this is needless if only provision be made to take care of cloudy filtrate and *an open weave of uniform mesh be used.*


Unsatisfactory Use of Double Plies.

It must be borne in mind that cotton is a cellulose product and with very few exceptions swells when immersed in liquids. Consequently, weaves that seem quite porous before wetting are quite dense afterward, and, similarly, loosely woven fabrics that often seem flimsy when cut upon the table will prove quite substantial in practice. Many investigators have been impressed with the excellence of thin muslins, but have been deterred in their use by reason of their frailty. Such mediums are, indeed, very efficient, for they effect the nearest approach to instant surface filtration and, by reason of the thin yarn from which they are woven, do not clog up if their surface be cleaned,—for they have not enough thickness to hold solids.

The writer has seen installations of thin cloths strengthened by using two layers. This is usually a poor expedient, for the idea that the inner cloth backs up any rent or tear in the outer cloth is not well founded. To obtain this result, the two layers should be made integral one with

Courtesy United Filters Corporation

FIG. 2.—A Long Popular Modern Filter.
Sweetland Filter—Pressure Leaf Type.



the other by close lateral stitching or by spot pinning, etc. Then the possibility of a wrinkle occurring in the inner cloth at a point where the outer cloth is torn, is decreased, but this procedure has the same effect as the use of heavy cloth to begin with, and there is certainly no advantage in the scheme worth the effort. To prove the futility of double thickness of thin muslin, one has but to inspect a filter so equipped that has been in operation a few days and note the accumulation of cake that occurs at the bottom of the leaves or plates. This increases with every run and is accounted for by the fact that the outer cloths are ripped or have "pin" holes, so that the under cloth must do the filtering at such points. More cake builds up than can clear through the hole when the filter is discharged, and this excess works down to the low point of the leaves.

Satisfactory Fabric Reinforcement.

The idea of reinforcing the muslin, to strengthen it, is good, but the under cloth must be of an excessively open weave such as a "hose duck," burlap, cocoa matting, or the like. Then, any solids penetrating the muslin will issue from the leaves as cloudy filtrate. It is amazing to see the extent to which muslin can be torn and still give good service under such conditions. The length of life of muslin is then made positively practical even when using those machines that require the cloths to be sewn to the leaf. Diverse opinions have been rendered on this subject, but the writer was much impressed with the working of a battery of Sweetland filters having an aggregate filter area of over 7,000 sq. ft., where, after a thorough investigation was made of this point by several months' experimentation, muslin backed up by burlap was used. The life of this muslin was doubled, the output increased and material economies were effected.

Importance of Agitation of Liquor in the Filter.

Use of open weaves is less necessary in filtering crystalline solids because these particles are large, and, as there are no fine particles to be caught in the meshes, a dense cloth used for crystals can easily be kept in a free filtering condition. This holds true except when such liquors also contain fine impurities in suspension, the nature of which is not crystalline. In such cases the above is of positive importance.

A case occurred in a plant where calcium sulphate was thrown down from an acid liquor, but a considerable percentage of flocculent precipitates were present as well. The superintendent and chemist were advised of the advantage of using open cloths, and tried them. They reported utter failure: the clarity never did become brilliant. One glance at their cakes, as discharged from the filter, told the whole story. As every filter manufacturer warns against the formation of tapering cakes, they were informed on this point. They were not troubled with poor washing; had no difficulty in discharging; and the leaves were not warped excessively. But,—they were not equipped for *thorough agitation of the*

liquor in the filter. Consequently, the heavy solids sank to the bottom and, with their open cloths, the upper part of the leaves received only the lighter solids which were fine enough to penetrate the filter cloth without coating the surface with a substantial deposit. The solution of the problem lay in maintaining a steady agitation of the liquor in the filter to prevent settling of the heavier solids and thus assure uniform cake thickness. This resulted in clarity of filtrate. This instance shows the relation of agitation to clarity and also illustrates what small factors can often be the deciding point between success and failure in the art of filtration.

Filter-Aids.

It has been explained that initial coating or film of the deposited solid, not the fabric itself, is the true filter medium. To aid in this coating, some additional coating material is often added to the liquor, the material being termed "filter-aid." A filter-aid, whether it be waste industrial matter (such as sawdust flour; calcium sulphate; calcium carbonate; pulverized bone-black) or some specific filter-aid product on the market such as "filter-cel," must have three main properties: (1) its specific gravity must be such that when mixed in water, or in the liquid being filtered, it will stay in suspension without settling or floating; (2) it must be of a free filtering character; and (3) its chemical composition must be inert or harmless to the liquid. Filter-acids as *clarification agents* will be discussed here, and their use in increasing capacity, facilitating discharge, etc., will be taken up later.

Pre-Coating the Cloths.

The fundamental use of a filter-aid as a clarification agent is in producing an auxiliary filter medium upon the filter cloth by means of "pre-coating." Pre-coating is the term used to define the initial filtration of a filter-aid before opening the main liquor line. This filtration is generally only for a minute or so, and it is sufficient when the effluent issuing from the filter is brilliant. Too often, the impression seems to be that this coating must be of some sensible thickness,— $\frac{1}{8}$ in. or $\frac{1}{16}$ in.,—where, in fact, a mere film is sufficient. On raw sugar liquors it is practical to pre-coat the cloths, using 1 lb. of "filter-cel" per 100 sq. ft. of filter surface, and on examination of a filter leaf after coating it will seem to be without any deposit, but the clarity of the filtrate will be found to be brilliant when filtering the sugar liquor, and a white surface will be noted on the inner face of the cake when discharged. This is probably the minimum amount to use and safer results are obtained by doubling this amount, but even this will give a coating difficult to measure and no liquors have been encountered to date that will not give a brilliant filtrate through it. Obviously, more than this is an extravagant use of the material and unnecessarily increases the initial resistance of the medium. Pre-coating is an automatic operation in the sense that the uniformity of the coating takes care of itself and the time required is

seldom more than a small fraction safely put at 10 per cent of the total cycle. Therefore, a filter with anything over 11 per cent excess capacity is sufficiently large to meet production. This amount, however, may be called the maximum, for the time required depends on the method used for pre-coating.

Methods of Pre-Coating.

The vehicle to use for this pre-coating is a matter for local decision; but there are three methods in practical use giving eminent satisfaction.

(1) A slurry is made up of filter-aid and water (or, when handling varnishes, etc., some solvent), and this is filtered in the usual manner, shutting off when the filtrate is brilliant. In most machines the amount of unfiltered slurry demands its withdrawal from the filter before admitting the sludge. Best practice, therefore, is to locate the slurry mixing-tank below the filter so that the excess unfiltered in the machine may be drained back, using the minimum air pressure to hold the coating on the cloths.

(2) To obviate this draining back, some plants use the second method, where clarified effluent is used instead of water or the solvent and sufficient filter-aid is added to insure a pre-coat when the following operation is carried out: the pre-coating liquor is admitted to the filter until full, when the regular liquor is fed to the machine. The lay-out for this method is usually to locate the pre-coating tank above the filter so that no pump is necessary to feed the pre-coating slurry to the filter, gravity-feed, with large pipe lines being sufficient. In this case the excess slurry is not withdrawn, but filters through the machine more quickly than the time required to drain the excess and refill the filter. This is probably the most fool-proof method of pre-coating. The deposit is a clean coating of the filter-aid, and there is required no such nicety of control in maintaining positive pressure within the filter as in the case of the first method, and, further, the drainage members and outlets of the filter are not filled with a water liquor but with a high strength filtrate. The one canal for the return of cloudy filtrate (which must be provided even if pre-coating were not used) takes care of the first filtrate.

(3) The third method is that used extensively in sugar refineries of the United States and Canada, and is considered by many as the most practical. Here the solids of suspension in the liquors to be clarified are present in relatively low percentages and it is found quite practical simply to add sufficient filter-aid to the unfiltered material so that the volume of the filter-aid far exceeds the original solids. This liquor may then be fed as in the second method. The coating will be found to be such a close approximation to straight filter-aid that the practical results are the same. Theoretically there is much to commend this system, but the human element in its control is its weakness, for too often an operator, falling behind in his schedule, will prolong the time of pre-coating and thereby increase his output of clear filtrate at the expense of excess use of filter-aid. Wherever the quantity of filter-aid used is an item of operating expense, the second method of pre-coating proves to be the

most economical, for there the operator has no incentive to prolong the pre-coating cycle and obtain a filtrate which he has previously clarified.

Modifications in these methods of pre-coating are found in special instances. An example is seen in the handling of cachazza, or the settled solids in raw cane sugar manufacture, where the semi-clear supernatant liquor from the settling tanks is a practical vehicle for the filter-aid in the pre-coating operation. Some chemical plants use the wash filtrate for this purpose, and when the quantity of wash-water is small, permit its entire evaporation. This is good practice, especially when the strong liquor is a viscous material.

Considerable educational work was necessary at first to popularize the use of pre-coating, but industrial plants now generally accept the principle as a part of their routine. It is now held that the scheme is applicable even to municipal work with sand filters, as the following experiment would seem to indicate.

During the war, when sulphuric acid was at a premium, a celluloid works contracted for a quantity of 98% sulphuric acid. This had to be crystal clear, and in the mixing of oleum and 66° Baumé acid to get this strength, fine colloidal lead and iron sulphate precipitated. It required an average of thirty days for a batch to settle so that a clear supernatant liquid could be drawn off. This delay of course increased the cost, and efforts were made to filter the liquid. The filter medium practical for acid of such strength was limited practically to silica as sand, "filtros," carborundum, alundum, etc. It was hoped that one of these materials could be made dense enough to clarify the colloids from the acid and not clog up after a couple of runs. The manufacturers of these media worked hard to meet the requirements, but without success. Pre-coating was suggested and a sample of acid secured for a laboratory test. It was planned to run this on a Buchner funnel using an alundum plate as the medium. The right size plate was not at hand so a sand filter was approximated by filling the bottom of the Buchner with gravel and then covering with ordinary beach sand. A mixture of clear 66° acid and calcined filter-cel was poured on the sand and a small suction filtered off the acid. The filter-cel most effectively clarified the 98% acid then poured on the bed. The thing of most interest was that the filtration was a close approximation to true surface filtration, for the sand bed, after the coating was removed, was to all appearances as clean as when laid in the filter. This is significant, for in sand filters true clarification starts when a deposit coats the surface of the bed. Hastening this coating is a move toward progress in sand filtration.

Pre-coating has already increased the fields of application to include those liquors hitherto thought inapplicable, and has played a big part in advancing the use of open filter cloths. With the principle of pre-coating defined and endorsed, it is a matter of local consideration and research to determine the best material to be used. Standard filter-aids (such as filter-cel) are almost universal media, but often a better medium can be obtained free from the property of imparting taste to food-product liquors, or free from sliming up (as silicates in handling caustics). Wood

pulp is a substitute in the first case, and waste calcium sulphate from phosphoric, tartaric acid, or similar manufacture answers well in the second case.

Colloidal Clarification.

The most interesting of the more difficult clarification problems is the filtering of colloidal solids of suspension. Filter men use the term "colloid" very comprehensively and often extravagantly, to make it include solids whose size and behavior are not those of true colloids, but whose filtering characteristics are. From a filtering standpoint, any solid so fine, or any flocculent precipitate so weak in structure as to make true clarity difficult to obtain (or, when obtained, difficult to maintain economically its rate of flow), is put in the colloid class. Examples are, roughly: cane sugar liquors as found in plantation and refinery practice; raw sewage; soaps in the neutralization of free fatty acids in vegetable oils; and aluminum hydrates precipitated from the introduction of alum as in municipal water clarification.

Obviously, the prime difficulty in colloidal clarification rises from the delayed arching effect of the fine solids in deposit, and their easy breakdown under pressure. Any filter fabric must be perfectly and *tightly woven* to obtain clear filtrate from these materials. But we have previously pointed out that use of tightly woven fabrics is objectionable practice, not to be resorted to when it is possible to handle the filtrate through open weaves. Then, how can open media be used for colloids? The answer is: By the addition of filter-aid.

In most industrial liquors containing colloidal suspensions, the filtrate is of far greater value than the solids. When the solids have by-product value, there is enough gained to warrant the recovery of the solids to be considered as a separate problem apart from the work of filtering the liquors. An example of this is seen in vegetable oil refining. In this, the neutralized free fatty acids were formerly recovered as soap stocks by the process of *sedimentation*. They are now recovered more advantageously by the Baskerville Process through *filtration*. In this process, cotton linters are added to facilitate filtration of the neutralized acids, and the recovered solids, spoiled by the linters for use as soap stocks, are recovered as baser material. These filtered solids are then taken and the free fatty acids reformed by acidulation which makes the recovery of the grease a simple process, since the grease floats on top of the acidulating liquor making it easily recoverable by skimming or by high speed centrifuges of the cream-separator type. Thus, the soap stock is finally recovered. This process clarifies by filtration instead of by the old method of sedimentation and has these advantages: it saves time, as sedimentation is slow; it assures positive clarification in place of uncertain clarity, it leaves less of the valuable refined oil behind in the waste product, and it requires far less tankage. Plainly, then, filtering here is a better method than sedimentation. The secret of filter success in this process lies in the addition of the cotton linters, which is, in effect, the addition of filter-aid.

1076

660-28424

Formerly, filter paper and paper pulp filters (the first consisting of sheets laid upon filter cloth in plate and frame presses; the second being made of circular blocks with internal drainage) were used because these media were denser than any cloth and so insured complete clarification. These were particularly used in breweries, in gum and varnish works, fruit juice plants, etc., because here the solids are so fine that they pass through cloth. Today, pre-coating the cloth with paper pulp or other filter-aid accomplishes the same end and does away with their use. This marks an advance in simplicity and economy of filter operation, for the use of filter paper and pulp blocks was difficult indeed. The sheets of paper had to be laid with extreme care to get them smoothly adjusted without tearing. The paper pulp blocks had to be washed after each run and then compressed back into shape under hydraulic presses. Today, the filter-aid is simply added to the liquor and filtered, forming its own filter medium.

To sum up: Clarification is the department of industrial filtration which meets the popular definition of filtration,—*the separation of solids from liquids.*

Chapter II.

Cake Building.

In industrial filtration, the point of liveliest interest to the plant superintendent is the *capacity* of his filters.

Capacity is the amount of cake discharged or amount of filtrate obtained. It is directly proportional to the time required for the whole cycle of operation including cake forming, cake washing, cake drying and discharging, but it is primarily based upon the *Rate of Flow*. The term "Rate of Flow" covers not only the flow obtained per unit of time (as, for instance, the gallons per sq. ft. per minute), but, what is the same thing on a larger scale, the total flow per cycle.

Many ingenious efforts to increase capacity have been made which have failed because of incomplete comprehension of the principles that underlie cake-building. The importance of understanding these principles is strikingly shown in the experience of one superintendent who was not getting sufficient output from his three filters and was planning to install a fourth machine. By modifying his method of operation, however, two of his filters were made to deliver the quantity he expected of four, saving this extra installation altogether, and, moreover, leaving his third machine for extra output.

The factors which underlie cake-building and govern capacity may be outlined thus:

- (1) cake density
 - (a) initial pressure
 - (b) concentration of solids
- (2) steady, increasing pressure
- (3) critical pressure
- (4) economical limit
- (5) homogeneity of feed
- (6) temperature, viscosity and density of feed
- (7) flocculation
- (8) filter-aids
- (9) maintenance of cloth porosity
- (10) design of drainage member

i. Cake Density.

The Rate of Flow is proportional to the porosity of the medium for the passage of the filtrate. Anything that tends to reduce the openings tends to reduce the rate of flow. The depositing cake does this auto-

matically, and our consideration must center on those agents which unduly hasten this decrease in flow, i.e., (a) too high initial pressure, and (b) insufficient concentration of solids in the feed.


a. High Initial Pressure.—As a particle is deposited on the filter medium, liquid has passed through the medium. The solid particle has come to rest, the liquid maintains its motion, although possibly at a slower gait. The solid, prior to its deposit, was in motion, being carried by the liquid as its vehicle. Therefore, having been in motion and then coming to rest, it has an impact force and a compacting action upon the deposit already formed, or, if it is the initial flow, a forcing action trying to penetrate the pores of the filter cloth itself. By the law of mechanics for momentum, this force is in proportion to the mass weight of the particle (including its entrained liquid) and to the velocity of movement. The velocity is the factor for our consideration. The velocity is proportional to the pressure, according to the familiar law of hydraulics. Any filter, when first starting up, has its maximum velocity of flow, the decrease from which varies with the material in hand. In some cases this is gradual, in others the decrease in velocity is rapid. Rapid decrease defeats high production. The momentum of the first coating-solids is of prime importance. This rapid decrease is nothing more than the creation of high resistance to the continued flow, and a tightly packed cake is always more resistant than one loosely packed. Here, then, we see the importance of cake density. Decreasing the initial flow and consequently the velocity of the particles prior to their deposit, is the answer here. This is accomplished by low initial pressure. This substantiates the old adage: "Start the press with a low pressure." It must be pointed out that while this rule does not apply to free-filtering liquors (such as caustic soda carrying calcium carbonate in suspension, or calcium sulphate in phosphoric acid, etc.), it is vital in handling average liquors.

b. Concentration of Solids.—Cake density also depends upon concentration of solids in the liquor. If the liquor is high in solids, the cake deposited is more porous than a cake formed from a thinly concentrated liquor. This is because the rate of flow of thin liquor is greater and deposits the solids with more velocity, producing a denser cake. A tightly packed cake, as we have seen, is plainly more resistant than one loosely packed. The liquor should, therefore, be concentrated as much as possible in order to form a loose, porous cake which prolongs the period of good flow.

Decantation prior to filtration, to concentrate the solids, increases the capacity of the filter. This is universally true in regard to capacity of cake discharged, and there are instances where the rate of flow is also increased. Rate of flow is increased because the cake deposited from concentrated liquor is more porous, and thus allows freer passage for the liquid. There are a great many installations of Dorr Thickeners feeding the underflow discharge to continuous filters where continuous filters could not have been used on the original unthickened slurry. The reason for this is that the accumulation of solids enables a cake that can

be discharged to be built on the filter whereas from a thin liquor so thin a cake is formed that discharge is impractical.

There are numerous cases where this procedure is especially economical and advantageous, but in the main it is confined to those materials that settle readily with a satisfactorily clear supernatant liquor. If, however, the supernatant liquor needs further clarification, then this pro-



Courtesy The Dorr Company

FIG. 3.—Widely Used Modern Clarifier.
Dorr Thickener—Continuous Settling Type.

cedure is really "two bites at a cherry" and has no advantage, for clarification of such decanted liquor, with its fine particles, is more difficult than filtering the original liquor, especially if the solids are waste products so that filter-aid may be added to the concentrate without chemically affecting the filtrate.

2. Steady, Increasing Pressure.

To increase capacity, the attack most often pursued is to increase the filtering pressure. This is logical, for the filter medium and the cake

can be considered multiple orifices, so that the law applies that: "the flow of liquid through an orifice is proportional to the pressure." It is becoming better recognized that a constant, or *steady* pressure is the most desirable for obtaining best rate of flow. Fluctuations in pressure produce an effect similar to that of tamping wet ground. The cakes are made denser and more resistant by this action. If efforts are made to form porous cakes at the start of operation, similar efforts must be made to maintain this porosity. One of the agents best calculated to defeat this endeavor is the hammer-like action of pulsating pumps. For this reason, slide valve and plunger type pumps are never supplied as new equipment, being supplanted by even-pressure machines. Fluctuating pressure produces irregular flow for the resistance produced by the high pressure is too great for the lower pressure to force the liquid through rapidly. This point is one of the favorable factors in the use of montejus and pneumatic eggs, gravity feed and vacuum receivers, etc.

Use of centrifugal pumps automatically insures low initial pressure, steady, and increasing pressure. Centrifugal pumps with rotors easily accessible and with sufficient clearance to allow the pumping of gritty and coarse materials are admirable in that the amount of pressure is in reverse proportion to the amount of filtrate flowing.

Increased *pressure* is identical with increased *suction* when operating vacuum filters. There have been misconceptions on the difference of pressure and vacuum filtration. Much discussion has arisen over the merit of "pushing" the liquid through the filter, as in pressure type machines, and "drawing" it through with vacuum filters. The action here is *not* analogous to the familiar law of mechanics that a cane can be *drawn* along a pavement more easily than it can be *pushed* along. The action in pressure and suction filters is identical: *the filtrate is pushed through in both instances*, the pump being the agent in one case, and atmospheric pressure the agent in the other. In other words, the filtering force in either case is the difference of pressure on the two sides of the medium, in the one case it being the pressure due to a pump or head greater than atmospheric pressure; in the other, that of the atmosphere compared to a pressure lower than atmospheric. In consequence, laws pertaining to pressure filtration apply also to vacuum filters. What is of advantage in vacuum filtration is its evenness and ease of control. The only fundamental difference in vacuum and pressure filtration is that the former is limited to atmospheric pressure as the maximum, while the limit of the latter is only the strength of the materials of construction. The range of difference in pressure is limited to 14.7 lb. per sq. in. as the theoretical maximum with the vacuum type.

3. Critical Pressure.

That an increase of pressure increases the quantity of filtrate is not universally true. It is practical with almost theoretical accuracy when handling solids of a crystalline or granular texture. It is true to a certain extent with every material, but with some only through a small

range of pressure. Those with the smallest limits are flocculent precipitates with which a few feet increased head of gravity feed is all that will increase the flow before a contrary result is obtained.

The reason that, in practice, the law of increased pressure does not always increase the flow, is found in the fact that in filtration the orifice (i.e., cake porosity) becomes a variable under pressure. For every material there is a pressure above which an increased flow is not obtained, but a decreased flow is had instead. This is known in filtration parlance as the *critical pressure* for that material.

Confusion sometimes occurs on this point, for an operator will, after filtering at a given pressure, jump his pressure up and point to the larger stream issuing from the filtrate outlet. Unfortunately for him, the flow does not last long. It is occasioned by the fact that the increased force compacts the cakes on the leaves and forces the entrained liquid out through the filter cloth. After this momentary rush, however, the rate is lower.

It is difficult to estimate the critical pressure for the various materials handled in industrial filtration, or even for one material. What is a low pressure for one, may be a maximum pressure for another. Determining correct pressure for the material in hand leads to the questions, "Why are not the same pressures uniformly applicable to any material?" and, "Is there a critical pressure above which harm instead of good results?" Experience answers this last with a positive "yes," and if we might mount the scale high enough we could include in this even hard crystalline solids which are so freely filtered. The theory of an increased pressure,—based on the law for flow of liquid through orifices,—holds true only so long as the pressure employed does not change the form of the particles deposited. If we filter a wax as the solid of suspension, it is apparent that we can put sufficient pressure upon the deposited wax to cement the particles to form a homogeneous mass that would be impenetrable. When we handle gelatinous flocculent precipitates like calcium phosphate, iron hydrate, etc., we closely emulate the wax condition if we go beyond the critical pressure for these materials. Unfortunately, it is impossible to tabulate the limiting pressures critical for any material by reason of the variation of filtering characteristics of the material when precipitated under varying conditions; when suspended in different liquids; when handled under varying temperatures, densities of liquids, concentration of solids, etc. Therefore, each installation must determine for itself the critical pressure and by no other means than by empirical tests of actual operations. It is not difficult to ascertain the critical pressure in any plant if experimental runs at different pressures be made with periodic readings of the filtrate flow taken while all other factors that affect the rate of flow be maintained constant. With these readings, it is simple arithmetic to figure the rate of flow per unit area for the successive periods at which the readings were taken. A graph can then be plotted, the abscissae being the time of filtration and the ordinates the rate of flow. It is interesting to find how completely experimental observation is corroborated by such a plot.

If a low pressure is advisable in forming the first deposit in order to obtain a loose, porous cake, and if a limiting pressure is necessary in order to maintain this cake formation, we have some appreciation of the importance of the pressure employed. Save where the critical pressure is measured in feet of head rather than in pounds per square inch, the mechanics of the feeding device to the filter is extremely simple. A centrifugal pump with throw equal to the average output of the filter automatically regulates the pressure, since it cannot develop beyond a certain maximum. In filling Sweetland and other pressure leaf filters, this size pump will be too small, but the work can be done best by gravity feed through larger pipe lines. No objection should be encountered on the score that this means elevating the supply to a needless level, for this filling supply tank can be charged by the by-pass line when the safety valve throws. The use of the safety-valve on filters fed by centrifugal pumps is a new and recent procedure, although its function is purely that of preventing churning action of the impeller on the liquor when the flow falls below the throw of the pump. Naturally, the safety valve is set at a pressure less than the maximum head of the pump. This feed tank must be provided with an overflow dropping back into the main supply tank so as to prevent flooding the filling tank.

When handling materials of low critical pressure, vacuum or gravity fed filters are rightfully popular. It is a simple matter to control the vacuum pressure to 5 inches of mercury, which is, so far as the filtering force is concerned, the approximate equivalent of 5 feet gravity head. A gravity feed tank, when operating pressure-filters, can be placed at any height above the filter and consequently low pressure control on this type of filter is a simple matter. If a plant layout is made from experimental data it must not be forgotten that valves, elbows and fittings set up frictional resistance, decreasing the actual head on the filter medium and the measured height of the mean level of the liquor in the tank above the center of the filter must be in excess to the extent of this resistance, measured in feet. Gravity feed tanks will always be found a far better feeding arrangement than throttling discharge from pumps, using slow-speed centrifugal pumps, injectors, etc. In a layout it will often be necessary to elevate the liquor to be filtered into the gravity feed, and in this case a pump of approximate, but with slight excess capacity, continuously delivers into the gravity tank, with an overflow back to the source of supply.

4. Economical Limit.

In practically all phases of filtration discussion the *rate of flow is synonymous with cake building*. It is apparent that if a dry, hard cake is desired from a plate and frame filter press, the frames should be designed so that the cakes on the two sides of each frame shall join together before the rate of flow has fallen off too greatly. If the time required to build the frame solidly full is too prolonged, the cycle is bound to be uneconomical. This is best shown by a graphical analysis of rates of flow.

Representative curves are shown in Fig. 4. AB is that of a liquor containing crystalline solids, or materials of similar texture, which are free filtering products. This is practically a straight line slowly breaking into a hyperbola, and the interpretation is that the rate of flow falls off at equal increments, each increase in thickness of cake causing a corresponding increase in the resistance to the flow. The statement that "it is a straight line" is approximate and true only when applied to the usual working limits. The line eventually bends and resolves itself into a hyperbola, slowly approaching, but never reaching, zero. This curve represents that of the easiest filtered materials. The curve CD is typical of the vast majority of difficult materials handled. The initial flow is




FIG. 4.—Rate of Flow Curve.

A B represents the fall in the flow of a relatively free filtering material. It approximates a straight line.

C D depicts the reduction in flow of a gelatinous or difficultly filtered material. The curve approaches a hyperbola.

E F marks the improvement in the material C D after modifying operating conditions.

high, with a rapid fall until a low rate is obtained, decrease in which is small. The goal of every filter experimenter is to change the form of this graph and make it approach AB. EF will represent the fruit of such efforts and, in lay language, means that by a modification of the material as precipitated, or by modifying the method of handling the material, it is changed to a more easily filtered liquor.

A further study of the curve CD shows us that if it were possible to work this material only for the time represented by OX we would be working at the economical part of its filtration. Such a scheme means, however, short filtering periods, and is feasible only in those types of filters wherein automatic discharge and continuous operation are had. Here we find the fundamental principle of continuous vacuum filtration, and while possibly in a sense this is not ways and means of bettering the rate of flow, it is basic in that maximum capacity is obtained, not by a modification of the filtering characteristics of the material being handled,

but by a mechanical device to meet the conditions of the material "as is." This has its importance when materials are not subject to temperature or density variation and it is required only that the deposit of the solids shall have a sensible thickness and be efficiently discharged. It is true most applications of continuous vacuum filters are on materials of a free-filtering character, but the basic idea is as explained, nevertheless.

The total flow curve is often used and from it capacity is read directly. Its curvature is not as sharp as in the rate of flow curve, and is, consequently, not quite as informative as the latter. The curve is the simple plot of time of filtering, as abscissae and total flow at time of reading as ordinates as shown in Fig. 5.

Too long a filtering period is cumulative in its evil effects. Washing is slower, cake hardness less, and the chance of a clean cleavage of the




FIG. 5.—Total Flow Curve.

The quick rise of this curve indicates that the filtration is rapid at the start of the cycle and as the curve flattens out that the flow has decreased.

cake from the filter cloth jeopardized. This fault of an uneconomical cycle due to the width of the frames in plate and frame presses being too large is entirely too prevalent and is due to inadequate determination of the filtering characteristics of the material being handled. One advantage in leaf type filters is that it is not necessary to continue filtration until a hard cake is obtained. This means, then, that filtration can be discontinued at any time without jeopardizing the dryness of the cake. It is in these filters that the operator is afforded the most opportunity to effect best results as regards maximum capacity. The point to be kept in mind is that the rate of flow is constantly decreasing and when working at the low point of the curve the outflow is not commensurate with the time required. There is a mathematical means of determining the economical length of cycle which gives consideration to the washing, drying, and discharging periods, but it is well to have also in mind the general character of the rate of flow curve.

One of the most illuminating graphs arising from modern filtration developments is that known as the "economy curve." (See Fig. 6.)

Engineers will be struck with the similarity of this with that of the conventional "characteristic curve" of centrifugal pumps. The point of flexure is in both cases the economical limit. In the filtration curve, it marks the limit of the economical filtering cycle more positively than any other curve. While, in practice, the amount of liquor handled per shift may be said to be an infallible proof of the best working of the filters, the experimenter has this means of predicting that cycle productive of maximum capacity and it is more for his benefit that the curve is insisted upon in good laboratories.

The points on the curve are computations of the rate of flow per minute for each cycle, when it is assumed that the tare of the cycle




FIG. 6.—ECONOMICAL LIMIT CURVE.

Note the analogy to the characteristic curves of various centrifugal pumps. The high point on the curve defines the economical limit for the total cycle of operations for intermittent filters.

remains constant and that each successive point on the curve is the flow for the cycle if the filtering cycle had ended at that period. The assumption that the tare is constant is based on the fact that the time of filling the filter preparatory to filtering the liquor is constant, and that the time of withdrawing the excess unfiltered liquor and admitting the wash water is almost constant, irrespective of the amount of cake deposited, that the withdrawal of the excess wash water takes practically the same time for varying filtering cycles, and that the drying, discharging operations and closing up the filter again are practically constants. The time of washing the cakes is variable with widely differing amounts of cake deposited, but, in practice, the variation in length of the washing period is small and for the purpose of this curve may be taken as a constant. Table I is the form in which it is found most convenient to record the data of a test and from it are computed the points outlining the accompanying curve.

Additional information may be gained from a study of these curves, such as a computation of capacity by planimeter methods, etc., but such data are better obtained by other methods, as will be elaborated upon.

INDUSTRIAL FILTRATION

TABLE I.

Time	Elapsed Time	Interval In Min.	Flow in Gal.	Incre- ment in Gal.	Pres. Lb. Sq. In.	Temp. Deg. Fahr.	Dens. Deg. Ba.	Remarks
9:00	0	0	0.0	0.0	0	0	0	Filling
9:05	5	5	0.0	0.0	0	0	0	Filtrating
9:08	8	3	15.0	15.0	10	125	0	Clear
9:10	10	2	10.0	10.0	15	125	0	
9:15	15	5	20.0	20.0	15	121.5	0	
9:20	20	5	15.0	15.0	20	121	0	
9:25	25	5	15.0	15.0	20	121	0	
9:30	30	5	15.0	15.0	20	121	0	
9:35	35	5	15.0	15.0	20	121	0	
9:40	40	5	15.0	15.0	20	121	0	
9:45	45	5	15.0	15.0	20	121	0	
10:00	50	5	15.0	15.0	20	121	0	
10:05	55	5	15.0	15.0	20	121	0	
10:10	60	5	15.0	15.0	20	121	0	
10:15	65	5	15.0	15.0	20	121	0	
10:20	70	5	15.0	15.0	20	121	0	
10:25	75	5	15.0	15.0	20	121	0	
10:30	80	5	15.0	15.0	20	121	0	
10:35	85	5	15.0	15.0	20	121	0	
10:40	90	5	15.0	15.0	20	121	0	
10:45	95	5	15.0	15.0	20	121	0	
10:50	100	5	15.0	15.0	20	121	0	
10:55	105	5	15.0	15.0	20	121	0	
11:00	110	5	15.0	15.0	20	121	0	
11:05	115	5	15.0	15.0	20	121	0	
11:10	120	5	15.0	15.0	20	121	0	
11:15	125	5	15.0	15.0	20	121	0	
11:20	130	5	15.0	15.0	20	121	0	
11:25	135	5	15.0	15.0	20	121	0	
11:30	140	5	15.0	15.0	20	121	0	
11:35	145	5	15.0	15.0	20	121	0	
11:40	150	5	15.0	15.0	20	121	0	
11:45	155	5	15.0	15.0	20	121	0	
11:50	160	5	15.0	15.0	20	121	0	
11:55	165	5	15.0	15.0	20	121	0	
12:00	170	5	15.0	15.0	20	121	0	
12:05	175	5	15.0	15.0	20	121	0	
12:10	180	5	15.0	15.0	20	121	0	
12:15	185	5	15.0	15.0	20	121	0	
12:20	190	5	15.0	15.0	20	121	0	
12:25	195	5	15.0	15.0	20	121	0	
12:30	200	5	15.0	15.0	20	121	0	
12:35	205	5	15.0	15.0	20	121	0	
12:40	210	5	15.0	15.0	20	121	0	
12:45	215	5	15.0	15.0	20	121	0	
12:50	220	5	15.0	15.0	20	121	0	
12:55	225	5	15.0	15.0	20	121	0	
1:00	230	5	15.0	15.0	20	121	0	
1:05	235	5	15.0	15.0	20	121	0	
1:10	240	5	15.0	15.0	20	121	0	
1:15	245	5	15.0	15.0	20	121	0	
1:20	250	5	15.0	15.0	20	121	0	
1:25	255	5	15.0	15.0	20	121	0	
1:30	260	5	15.0	15.0	20	121	0	
1:35	265	5	15.0	15.0	20	121	0	
1:40	270	5	15.0	15.0	20	121	0	
1:45	275	5	15.0	15.0	20	121	0	
1:50	280	5	15.0	15.0	20	121	0	
1:55	285	5	15.0	15.0	20	121	0	
2:00	290	5	15.0	15.0	20	121	0	
2:05	295	5	15.0	15.0	20	121	0	
2:10	300	5	15.0	15.0	20	121	0	
2:15	305	5	15.0	15.0	20	121	0	
2:20	310	5	15.0	15.0	20	121	0	
2:25	315	5	15.0	15.0	20	121	0	
2:30	320	5	15.0	15.0	20	121	0	
2:35	325	5	15.0	15.0	20	121	0	
2:40	330	5	15.0	15.0	20	121	0	
2:45	335	5	15.0	15.0	20	121	0	
2:50	340	5	15.0	15.0	20	121	0	
2:55	345	5	15.0	15.0	20	121	0	
3:00	350	5	15.0	15.0	20	121	0	
3:05	355	5	15.0	15.0	20	121	0	
3:10	360	5	15.0	15.0	20	121	0	
3:15	365	5	15.0	15.0	20	121	0	
3:20	370	5	15.0	15.0	20	121	0	
3:25	375	5	15.0	15.0	20	121	0	
3:30	380	5	15.0	15.0	20	121	0	
3:35	385	5	15.0	15.0	20	121	0	
3:40	390	5	15.0	15.0	20	121	0	
3:45	395	5	15.0	15.0	20	121	0	
3:50	400	5	15.0	15.0	20	121	0	
3:55	405	5	15.0	15.0	20	121	0	
4:00	410	5	15.0	15.0	20	121	0	
4:05	415	5	15.0	15.0	20	121	0	
4:10	420	5	15.0	15.0	20	121	0	
4:15	425	5	15.0	15.0	20	121	0	
4:20	430	5	15.0	15.0	20	121	0	
4:25	435	5	15.0	15.0	20	121	0	
4:30	440	5	15.0	15.0	20	121	0	
4:35	445	5	15.0	15.0	20	121	0	
4:40	450	5	15.0	15.0	20	121	0	
4:45	455	5	15.0	15.0	20	121	0	
4:50	460	5	15.0	15.0	20	121	0	
4:55	465	5	15.0	15.0	20	121	0	
5:00	470	5	15.0	15.0	20	121	0	
5:05	475	5	15.0	15.0	20	121	0	
5:10	480	5	15.0	15.0	20	121	0	
5:15	485	5	15.0	15.0	20	121	0	
5:20	490	5	15.0	15.0	20	121	0	
5:25	495	5	15.0	15.0	20	121	0	
5:30	500	5	15.0	15.0	20	121	0	
5:35	505	5	15.0	15.0	20	121	0	
5:40	510	5	15.0	15.0	20	121	0	
5:45	515	5	15.0	15.0	20	121	0	
5:50	520	5	15.0	15.0	20	121	0	
5:55	525	5	15.0	15.0	20	121	0	
6:00	530	5	15.0	15.0	20	121	0	
6:05	535	5	15.0	15.0	20	121	0	
6:10	540	5	15.0	15.0	20	121	0	
6:15	545	5	15.0	15.0	20	121	0	
6:20	550	5	15.0	15.0	20	121	0	
6:25	555	5	15.0	15.0	20	121	0	
6:30	560	5	15.0	15.0	20	121	0	
6:35	565	5	15.0	15.0	20	121	0	
6:40	570	5	15.0	15.0	20	121	0	
6:45	575	5	15.0	15.0	20	121	0	
6:50	580	5	15.0	15.0	20	121	0	
6:55	585	5	15.0	15.0	20	121	0	
7:00	590	5	15.0	15.0	20	121	0	
7:05	595	5	15.0	15.0	20	121	0	
7:10	600	5	15.0	15.0	20	121	0	
7:15	605	5	15.0	15.0	20	121	0	
7:20	610	5	15.0	15.0	20	121	0	
7:25	615	5	15.0	15.0	20	121	0	
7:30	620	5	15.0	15.0	20	121	0	
7:35	625	5	15.0	15.0	20	121	0	
7:40	630	5	15.0	15.0	20	121	0	
7:45	635	5	15.0	15.0	20	121	0	
7:50	640	5	15.0	15.0	20	121	0	
7:55	645	5	15.0	15.0	20	121	0	
8:00	650	5	15.0	15.0	20	121	0	
8:05	655	5	15.0	15.0	20	121	0	
8:10	660	5	15.0	15.0	20	121	0	
8:15	665	5	15.0	15.0	20	121	0	
8:20	670	5	15.0	15.0	20	121	0	
8:25	675	5	15.0	15.0	20	121	0	
8:30	680	5	15.0	15.0	20	121	0	
8:35	685	5	15.0	15.0	20	121	0	
8:40	690	5	15.0	15.0	20	121	0	
8:45	695	5	15.0	15.0	20	121	0	
8:50	700	5	15.0	15.0	20	121	0	
8:55	705	5	15.0	15.0	20	121	0	
9:00	710	5	15.0	15.0	20	121	0	
9:05	715	5	15.0	15.0	20	121	0	
9:10	720	5	15.0	15.0	20	121	0	
9:15	725	5	15.0	15.0	20	121	0	
9:20	730	5	15.0	15.0	20	121	0	
9:25	735	5	15.0	15.0	20	121	0	
9:30	740	5	15.0	15.0	20	121	0	
9:35	745	5	15.0	15.0	20	121	0	
9:40	750	5	15.0	15.0	20	121	0	
9:45	755	5	15.0	15.0	20	121	0	
9:50	760	5	15.0	15.0	20	121	0	
9:55	765	5	15.0	15.0	20	121	0	
10:00	770	5	15.0	15.0	20	121	0	
10:05	775	5	15.0	15.0	20	121	0	
10:10	780	5	15.0	15.0	20	121	0	
10:15	785	5	15.0	15.0	20	121	0	
10:20	790	5	15.0	15.0	20	121	0	
10:25	795	5	15.0	15.0	20	121	0	
10:30	800	5	15.0	15.0	20	121	0	
10:35	805	5	15.0	15.0	20	121	0	
10:40	810	5	15.0	15.0	20	121	0	
10:45	815	5	15.0	15.0	20	121	0	
10:50	820	5	15.0	15.0	20	121	0	
10:55	825	5	15.0	15.0	20	121	0	
11:00	830	5	15.0	15.0	20	121	0	
11:05	835	5	15.0	15.0	20	121	0	
11:10</td								

The principal help from these graphs is in noting their general curvature, or shape, and comparing the curves obtained from modified operation with that of a previous run. In this respect they serve a most useful purpose, for with all factors kept constant, save a modified pressure, these graphs are indefeasible proof of the existence of a critical pressure and the most definite means of obtaining it.

Some may deem such a discussion too academic, and, when incorporated as the results of a test, a graph is often somewhat superfluous, but to the experimenter working out the problem it is of inestimable value. It is a big factor in maintaining a broad point of view, and it prevents premature satisfaction when better results are to be obtained by means of further research.

g. Homogeneity of Feed.

Often liquors have to be handled in which the solids of suspension are a mixture of coarse and fine particles. For maximum rate of flow agitation must be maintained in the filter so that the deposit both at the top and bottom of the filter medium is made up of a mixture of coarse, free-filtering solids and the fine, more difficult-filtering material. If classification takes place, so that the lower part of the filter cloth is coated with the coarse material and the upper part with the fine, then tapering cakes are sure to be formed and all the evils of discharging warped leaves, etc., will ensue. This leads to a point for further consideration, for if the liquor in the filter classifies and filtration is started, no amount of agitation from that time on is of any practical value. The solids that build up the cake are carried to their positions by their respective stream-lines. When a cake becomes highly resistant to filtration so that the flow is cut down, the stream lines of the liquid are weak and can carry particles only that are easily moved. This is the case when the upper part of the leaves become coated with the finer particles of suspension. No amount of uprising current which will carry the coarser particles upward can aid the deposit of the heavier particles at the top of the leaves. The stream lines are at right angles to the filter surface and strong stream lines are necessary if the velocity is to be sufficient to deposit the coarse particles on the cake surface. The above, therefore, emphasizes the fact that the initial deposit on the filter medium is vital if the best rate of flow is to be obtained.

This, then, brings out another point important in cake building: *To secure uniformity of cake, homogeneity of feed is necessary.*

d. Temperature, Viscosity and Density of Feed.

What is true of pressure as an important factor in the rate of flow is equally true of the *temperature* of the slurry and *density* of the liquid at which it is filtered. Here we have to deal not with a critical temperature or density of filtration, for with most materials practical economy dictates this before the limit which filtering efficiency requires is reached. The hotter the liquid is, the thinner it becomes, and the better will be the rate

INDUSTRIAL FILTRATION

of flow. It is, however, too often unappreciated that there is a very rapid rise in the viscosity with the increased density and decreased temperature as shown in Figs. 7 and 8. In Fig. 8, it is quite apparent that below Y




Fig. 7.—Density—Viscosity Relation.

Increasing the density increases the viscosity but far from uniformly.

a few degrees does not greatly affect the viscosity, but around X two or three degrees difference in temperature marks a distinct difference. Such information is, of course, not due to filter development, but is of value




Fig. 8.—Temperature—Viscosity Relation.

Increasing the temperature lowers the viscosity but, as the curve shows, the drop is not uniform per degree difference of temperature.

to the operator and teaches him the need of a nice control of the temperature and density.

While viscosity is a big factor in the capacity of flow from a filter,

It would seem that the surface tension of the liquid is another factor of real practical importance. Many materials suspended in water are so slow in filtering as to defy economical operation in modern filters, yet, when heated, they become relatively free-filtering. The temperature often need not be higher than 140° F. to make a continuous vacuum filter applicable, whereas at 100° F. the capacity obtained was unsatisfactory. Pottery clays, fine whittings, crude lithopone, and other materials of like character, are today handled with excellent success in rotary drum vacuum filters, in each case, however, maintaining a temperature not lower than 160° F. An explanation of this would seem to lie in the change of the surface tension, making the separation of the solid from the liquid easier. The economy of using continuous filters is, of course, reduced by the B.T.U. consumption in heating the liquors, and so, as a straight filtering proposition, it may be difficult to show the requisite savings to warrant scrapping an existing installation. Where, however, the cake leaves the filter to be dried, feeding a heated cake to the dryer is of positive advantage and the savings in dryer operation will often more than offset the cost of heating the liquor for filtration.

For proper determination of the right temperature and density, costs of heating, evaporating, and maintaining the heat must be known so as to balance the increased work of the filters.

7. Flocculation.

Unless an auxiliary filter medium be employed, colloidal material, or solids so fine as to approach colloidal conditions, are most difficult to handle with any degree of satisfaction or economy. They are difficult to clarify without a filter-aid since they form so compact a deposit as to be almost impenetrable. Fortunately, in the majority of cases, these solids are waste products and can be coagulated, or will allow of the introduction of a filter-aid. The usual method of coagulation is by the production of a flocculent precipitate by chemical reactions. Enough attention to this point seems to be lacking, for too often the goal seems to be to add enough reagent to be able to note a sparkling liquor between the flocculent particles. It does not seem to be appreciated that an excess precipitate adds to the solids of suspension which are of themselves difficult to filter in pressure filters. It must not be inferred that the agglomeration of the particles of suspension does not aid in pressure filtration, although this theory is sometimes advanced.

Centrifugal pumps are troublesome when handling flocculated material, for as soon as the outflow is less than the throw of the pump, the rotor has a churning effect which breaks up the flocculent precipitate. Every chemist knows how much harder it is to filter such precipitates in the laboratory after agitating and stirring them up so as to break up the agglomerated particles, than to handle them with the flocculent condition preserved. This difficulty is easily overcome by putting in a by-pass back to the feed tank controlled by a safety valve so that the throw of the pump is not reduced.

There is no question that flocculation is the best means of obtaining agglomeration of the colloidal material, but it must be remembered that the demand is satisfied when the quantity of reagent produces no excess precipitate. This is, of course, of less importance when only decantation methods are used.

8. Filter-Aids.

If there is added to a difficult filtering liquor before its filtration a quantity of inert, free-filtering material, it is obvious that the deposit on the filter cloth is a mixture of the free-filtering solids and the contrary precipitates. The former build up so as to preserve the porosity to a greater extent than do the latter, and consequently admit of a greater flow of filtrate. The filter-aid is added with the idea of decreasing the resistance of the solids deposited and making the liquor free-filtering, similar to that which carries crystalline or granular solids of suspension. It has been demonstrated that only a small percentage is necessary to effect marked results, but true filtering efficiency dictates the use of quantities in excess of that generally added. It is worthy of note that when good capacity flow is obtained from a filter, a corresponding increase in the volume of the cake is obtained. The greater the bulk of the cake, the better its discharge, and the filter-aid, therefore, simultaneously affects not only the rate of flow but the equally important factor,—efficient discharge.


It would seem that the combination of the flocculating idea and the filter-aid principle ought to have possibilities. It has. The idea, however, must not be to add the filter-aid as an aid to the filtration of a liquor the solids of which have been agglomerated, for to do so only partly solves the problem. In plant practice, but few instances will be found where a flocculent precipitate will not be broken up by the time the liquor enters the filters. The answer is to use the filter-aid to strengthen the structure of the flocculent precipitate by adding it to one of the defecants before its addition to the liquor. This will often require diluting the defecant, and if the water required for this is objectionable on the score of increased evaporation, no objection can be found to substituting clarified effluent for the water.

9. Maintenance of Cloth Porosity.

It is quite evident that the filter cloth must be retained in a free-filtering condition if recurring runs are to show the same capacity as the first run. It is idle to point out that thorough discharge of the cakes from the cloth is required for maintaining high rate of flow, but it is a point that experimenters are often too quick to assume when dealing with a new material. Inspection of the surface of the cloth is not an infallible means of determining that the cloth is clean. The rate of flow on succeeding runs is the only safe way.

From a view-point of clarification we have determined that open or thin cloths are the most advantageous. If we use open cloths it is natural that to arch the solids over the interstices we must let the solids

Fig. 9.—Kelly Filter.
A Modern Filter of the Pressure Leaf Type.



INDUSTRIAL FILTRATION

to initial deposit with far less force than if the interstices are large. In consequence, open cloths require low initial pressure. The question arises, "Is there not a balance between porosity of filter fabric and rate of flow?" Most positively "Yes," but one must not confuse high pressures as necessarily meaning small and large rates of flow. Our ambition is to obtain the most filtrate from the filter and with minimum expenditure of work. Consequently, low initial pressures through open cloths are often as productive of a good rate of flow as high initial pressures through dense cloths.

10. Design of Drainage Member.

Initial resistance of the filtering fabric, drainage member, etc., should be as low as possible. This fact is apparent but has been overlooked in some designs of filters in which excessive drainage has been provided. It must be remembered that the filtrate issues through the cloth drops, the accumulation of which produces the filtrate flow. Initial resistance does not have to be very great to meet this requirement. In the matter of choice of filter media more attention is given to the demand for one of low resistance to the passage of liquid through it and if mechanical wear calls for a heavy cloth, then an open weave is required. If too dense a cloth is used, the velocity of the initial stream lines causes the finer particles of suspension to be caught in the weave of the cloth and to embed themselves so as to cut down porosity. With coarser weaves of filter cloth these fine particles pass through the interstices and escape from the filter as cloudy filtrate which must be refiltered. This is far better than having the filter cloth torn so that it decreases the flow and cannot be effectively cleaned on cleaning.

Chapter III.

Cake Washing.

After filtration, it is general practice to follow with the washing cycle. The function of this is, of course, to regain the valuable which would otherwise be lost in the waste solids (or, when the solids are not waste, to remove impurities from them). Of almost equal importance is the recovery of the valuable at as high a strength as possible.

The keynote of success of our modern filters is their high washing efficiency. While present-day filtration is marked more by advance in labor-saving devices than by any other feature, most economy has been effected in the better washing of the cakes, for, whereas residual soluble in the cakes was formerly counted in whole per cents, today it is in fractions of one per cent. Materials that needed exacting washes were not formerly handled in filter presses, the wash water in which almost always left some parts of the cake incompletely washed. But these materials are today handled most efficiently in the modern filters. Complete washing is possible with every modern filter, yet failure to achieve it is common. In each instance of failure a better understanding of the fundamental principle of washing would have resulted in success and made the filter far more popular.

The reason for the better results obtained is found in the method used, i.e., *displacement wash*. The simplicity of this method is the secret of its success. "Displacement washing" is the term used to define that wash in which the liquid entrained in the voids of the cake is pushed ahead of the wash water without the latter mixing with the liquid. In practice, it is the simple filtering of wash water through cakes, the surfaces of which are equi-resistant.

All credit is assuredly due George Moore, who first realized the value of an equi-resistant cake and made it the foundation of his patents (both process and apparatus). His discovery was the factor which saved the cyanide process of gold extraction from being only a pretty laboratory experiment and made it the forerunner of the efficient systems now employed.

Uniform Resistance to Flow Desired.

Explanation for the practical production of an equi-resistant surface is seen by reference to Fig. 10. Take any points, A, B and C on the cakes, which may have been uniformly built up, or which may be tapering cakes with the bottom thicker than the top. The resistance to flow is the same at all of these points while filtration is taking place. The proof of

this is found in assuming that at A the resistance is less than at any other point; then, according to the law of flow of liquids (which seek the path of least resistance), a greater flow must pass through at the point A. Since, however, the muddy liquor enters the filter and clarified liquid issues from it, the greater flow at A creates a greater deposit of solids there, and this obviously increases the resistance to the flow until it is equal to the point B or the point C. It must, therefore, be acknowledged that during filtration, and at the close of the filtering cycle, the cakes present an equal-resistant surface to the flow of the filtrate.




FIG. 10.—Equal-resistant Cake.

Irrespective of the thickness of the cake, whether uniform or tapering, as shown, the resistance to flow must be equal while filtration is in progress.

The advantage of an equal-resistant surface must be apparent in obtaining a uniform wash of the cake. When the wash water cannot penetrate any part of the cake faster than any other, it forces the liquid entrained in the voids of the cake through as undiluted filtrate. This, of course, is the end desired, but it must not be thought that all the soluble can be recovered without some dilution, even with the best types of filters and with the most expert manipulation. The bulk of the soluble can and should be so regained, but due to capillary attraction and dead-end pores of porous material some soluble is retained and lags behind that forced out from the interstices of the cake. This liquid is recoverable by diffusion with the wash water and is regained as a sweet water, or weak liquor.

These facts are brought out in the graph known as the "Washing Curve" shown in Fig. 11. This is a plot obtained from periodic readings

of the amount of wash filtrate flowing, and its density. The abscissae are the gallons flow and the ordinates the density.

Wash Water Displacement of Filtrate.

Assuming the density of the filtrate to have been 32° Baumé, the curve of the theoretical ideal displacement wash is seen to be a broken straight line and is interpreted as meaning that all of the soluble is recovered at the high density and when all is forced out the density falls to that of the wash water. This is, as explained above, impossible in practical




FIG. 11.—Change of Density of Wash Filtrate.

The theoretical ideal is complete displacement of all strong liquor without any dilution. The leaf displacement approaches the theoretical and represents good practical operation. The plate and frame curve indicates excessive dilution, so often found in practice when washing the cakes in this type of filter.

operation and has its value only when serving to note the efficiency of the practical operation.

The leaf-displacement curve is typical of good operation in leaf type or continuous filters. It will be noted that there is a gradual fall from the maximum density before the sharp break occurs. The explanation for this is that the viscosity of high density liquids is greater than that of the wash water or low density liquids. When washing commences, the cakes present an equi-resistant surface, but as the wash water penetrates the cake some parts of the cake are made slightly less resistant, so that the water flows through somewhat faster at such points. The turn of the curve before reaching zero is the result of the capillary attraction above referred to.

Having discussed the principle of washing in general, let us now consider specifically the washing efficiencies of different types of filters, i.e.:

- (1) Plate and frame presses and leaf filters
- (2) Continuous filters
- (3) Open gravity filters.

INDUSTRIAL FILTRATION

i. Plate and Frame Presses and Leaf Filters.

The curve depicting the wash in plate and frame presses is representative of that obtained from alternative plate system of washing. Here, the wash water finds channels and quickly weakens the strong effluent causing a fall in the specific gravity. For the same reason, an effluent of a gravity equal to the wash water is obtained only by using excessive quantities of wash water. The reason for this is quite evident




FIG. 14.—Typical Cross Section—Plate and Frame Press. (Showing Stream Lines of Filtrate and Wash Water.)

While filtering, all cocks on the plates are open, while washing, every other outlet is closed. Note that the wash water traverses through a double thickness of cake and that its initial travel is in a direction counter to the flow of the filtrate.

when we comprehend the conditions. In a plate and frame, or a chamber, filter press initial filtration is analogous to that of the leaf type filters, and varies from this latter practice only when the cakes on adjacent cloths in each frame meet. From that point on, the pump, feeding the chamber press, does work not of cake building but of cake compressing. This, of itself, is not a serious drawback, but it is practically impossible to compress all of the cake evenly or completely. It must also be remembered that the initial path of the wash water from the alternate plates is in a direction counter to that of the filtrate which produced the cake. This counter current of the wash water is vital. The resistance of the cake

to a counter current wash is seldom equil-resistant, for it is the exception when the frames are completely and evenly packed. Consequently, it is obvious that paths of less resistance are open to the flow of the wash water and universal practice has demonstrated the inadequacy of alternate plate methods of washing filter-press cakes.

Plate and frame presses of the slicing type such as the Merrill press, and automatic discharge type, such as the Atkins-Schriver, employ the displacement system of washing and register marked successes in their washing efficiency. To work ordinary plate and frame presses on this system is to invite nice control if discharging troubles are not to be encountered.

Original Formation of Cakes Must Be Preserved.

From the foregoing, it is seen that the formation of the cakes must be preserved if true displacement wash is to be obtained in leaf filters. Most materials in plant operation vary from time to time in their filtering characteristics, so that in leaf filters it is generally found that there is too much unfiltered material remaining after filtration to allow the wash water to be turned on directly at the close of the filtering cycle. To do so would surely mean a dilution of the strong liquor lying in the filter and to increase unduly the weak liquor production. Practice, therefore, requires drawing the excess from the filter before the introduction of the water. This method allows materials to be washed at the end of their economical filtering cycle and is equally applicable whether the cakes are thick or thin. This feature of leaf filters is an important one and is in contrast to the operation in plate and frame filters, where the cake must be built up until it fills the frames and filtration ceases when the frames are filled. With raw materials varying in percentage of soluble, so that the material of suspension varies in amount and character, filtering until the frames are full often entails filtering long after the economical limit is reached.

Skill Required in Operation.

Unfortunately, this method of washing is successful in direct proportion to the ability of the operator. It is in his power to transfer the unfiltered material and fill in with wash water so that the cakes remain in a condition practically as equil-resistant as when finishing filtration, or, he can defeat the desired ends by failing to maintain the equil-resistant surface. It is positively important that he be instructed not only what valves to operate, but he should also be impressed with what he is trying to effect so that he can visualize the conditions inside the machine. If he fails to maintain a positive pressure, usually by means of compressed air, some cake will slough off the cloths and surely create a path of less resistance for the drainage of the wash water. The same is true if he drains or blows back the excess liquor at too high a velocity. Again, if he uses too high air pressure when holding the cakes on the leaves he is almost positive to dry the upper part of the cakes in advance of the lower part and will either crack the cake or cool it, so that in either case it is

conducive to the formation of unequal resistances to the flow of the water. Obviously, this makes for selective washing. Then, too, it takes too long in substituting wash water for the excess unfiltered liquor if the conditions are the same as though he used too high air pressure. Experimentation will dictate the best pressure to use and the time when once realizing what he must safeguard against has no trouble affecting admirable results.

Direct Washing Method.

When handling materials that run uniformly, the filters can be designed so that the space between adjacent cakes at the end of economical filtering cycle will be minimized. With Sweetland and V1 type leaf filters, in which excess space in the filter is small, it is possible to switch on the wash water simultaneously with the closing of the filter valve. The excess unfiltered liquor is forced through the cake and of the water and the dilution of the strong by the water is negligible. The same is true of Merrill and Atkins-Schrivener type plate and frame presses.

The direct washing method, the name given this system of selecting the wash water without withdrawing the excess unfiltered material, not only advantageous on the score of simplicity of operation and saving of time, but allows the greatest approximation to the true diaphoretic wash. The reason is clear, for there is no possibility of any cake being off the filter cloth, no cracks to be developed by air drying, nor is the equil-resistant condition of the cake is automatically preserved as there is a positive pressure maintained in the filter during the transition from feeding liquor to admitting wash water.

It is interesting to note that the quantity of sweet water or weak liquor produced should approach as an ideal that amount which equals the volume of the voids in the cake. It has been explained that capillary and adsorptive action require something in excess of this in practice, but the actual amount required is often reduced when the liquor strength of the strong liquor is done by degrees.

By this means the gravity prevailing when fresh water is turned is much reduced from the original gravity. In practice weak liquor washes are used for this purpose so that all water entering the filter leaves it as a strong liquor. The same scheme is worked with much success in continuous counter current decantation installations, where a semi-dewatered solid instead of an equil-resistant surface is subjected to the weak liquor washes.

The conventional method of discharging plate and frame press requires that the cake be hard and compact. Cakes washed by the present methods do not join together and their outer surface, therefore, not compressed. To discharge such cakes from plate and frame press is laborious and unsatisfactory unless effected by methods such as used in the Merrill filter press or the Atkins-Schrivener machine. In these machines the cake is cleaned out without opening the press and sloppy cakes offer no difficulty in their discharge.

Cloudy Wash Water Preserves Equi-Resistant Cake Surface.

If displacement wash is simply the filtration of a wash water through an equi-resistant surfaced cake, why are there so few instances of cakes washed with volumes of wash water equal to the volume of the cake washed? The answer, applicable in every instance, is that the equi-resistant surface has not been maintained.

For years we were concerned with how to prevent this loss by shortening the time for withdrawing excess unfiltered liquor and filling wash water; using reduced pressure during transfer; using automatic floats for admitting compressed air, and venting excess air, etc. Today, we need not put so much importance upon these items, although they cannot be altogether done away with and each of them plays a part. We have simply carried Moore's discovery another step forward, and instead of washing with clear water we use middled water, the solids in which are the washed solids of a previous run. Cloudy wash water cannot be satisfactorily made by mixing clear water with unfiltered liquor, for then the soluble content in the liquor will be added to the cake and if the soluble keeps on being added washing must be prolonged indefinitely.

The difference in using a clouded wash water rather than a clear water is obvious since the filtration of muddy liquor automatically preserves the equi-resistant surface, or,—renews such a surface, if through mishap or faulty operation this condition were lost after the finish of filtration. With clear water, however, a point of lower resistance becomes more so as washing progresses. Oftentimes weak liquors below certain specific gravity are discarded because the cost of concentrating or recovering the soluble far outbalances the value of that soluble. A virtue of displacement wash is that the amount of this weak liquor is so small that it is not thrown to waste.

Arrangement of pumps, etc., for the application of this scheme varies with local layouts but the results obtained are well worth the cost of the installation. There are plenty of instances where materials like pottery clay, Fuller's earth, etc., are solids of relatively slow filtering characteristics, which are preferable to add to the water rather than to return washed solids of a previous run. Organic solids capable of fermentation, or carrying other soluble organic compounds capable of scouring, should not be returned to the wash water tank. The volume of solids to have present is also for local decision. If the wash is progressing properly the wash filtrate should be of a density not far from that of the original until close to the end of the cycle, and the initial flow should never be any faster than that obtainable at the finish of the filtering cycle.

a. Continuous Filters. Spray Wash.

All of this discussion, relative to an equi-resistant surface, is equally pertinent to washing the cake in continuous vacuum filters. Here, the wash water is applied as an atomized spray, but, in theory at least, the water sprayed on the cake should, in its passage through the washing arc, envelop the cake and be equivalent to submergence. In practice,

this is approached but seldom attained. It requires far too delicate and frequent adjustment for the volume of water to be changed to accommodate changes in the filtrability of the cake deposited. There is no such thing as absolute uniformity in cake building, and likewise no uniform permeability of wash water through the deposit. Practice is determined on the basis of averages and the arc for washing extended to a point beyond that normally required, so as to be safe. If the spray is too heavy, the excess water accumulates, trickles down the ascending cake, and drains into the container mixing with the strong liquor. This is, of course, objectionable, but the operator should not go to the other extreme of applying too little water, for then air-drying commences and the wash water will often be short-circuited. It is for this reason that with cakes difficult to wash or the soluble it is advisable to augment the spray wash with a repuddling of the discharged cake with water or weak liquor, and to filter and wash it on a second machine. This makes for efficient washing, especially if the spray wash on the first machine is the effluent from the second machine. Then the strong liquor in the cake of the first machine is recovered at a high gravity.

The main weakness of the washing methods for continuous drum type filters is in the fine atomization necessary to spray the water on the cake. The water must be clear and free from pipe scale to prevent the nozzles clogging. Obstructions in the atomizers result in a coarse spray which has an injurious corroding effect on the cake. It was to overcome this weakness that the F.R.Inc Non-Atomizing Wash was developed. The mechanics of this device is described later in Part II, Chapter VI, Section 3, on "F.R.Inc Apparatus." When the cake compressor is used for washing the cake, the belt is made of a porous material, like burlap, or an absorbent material like wool felt. On the ascending side of the drum as many open saw-tooth troughs as required are distributed across the face of the drum and spill water not upon the cake itself but on the moving belt. More water is applied than is soaked up by the belt, or sucked through the cake by the vacuum, and the excess water travels down as a sheet draining into a collecting trough located under the lower kiln. By this means more water is supplied than the cake will take, making a better approach to cake submergence; trouble from atomization is eliminated, and the control of the quantity fed to the filter is a simple matter of adjusting the position of the upper trough.


3. Open Gravity Filters.

When handling extremely free-filtering solids such as calcium sulphate from phosphoric, citric, etc., acid manufacture, it is surprising how well the soluble can be extracted in open gravity filters. These filters are usually home-made machines with false bottoms covered with cocoa matting, burlap, etc., or with the old cinder bed bottom. The one essential point is that the liquor and wash water must drain by gravity so that the cake is built up uniformly. The cake formed is granular and allows considerable flow per unit surface, but the percolation of the wash water

is slow enough so that shortly after the heavy liquid in the voids of the cake is displaced the remaining soluble has had time to diffuse through the wash water. This accounts for the admirable wash obtained in this class of filters, which obviously is confined only to those materials of an extremely free-filtering nature. New means of discharge of the cake from this type of filter is described in the chapter on "Discharging" wherein is explained how the manual labor hitherto necessary with this type of filter is now obviated.

Counter-Current Washing.

In washing cakes from liquors that are corrosive to filter cloth, or that clog the drainage member with scale deposits, the counter current system of washing used in continuous decantation systems is extremely



Courtesy The Dorr Company

FIG. 13.—Chart of Continuous Counter Current Decantation System.

The solids settled from the first thickener are repudged with the overflow from the third thickener and settled in the second. The successive steps result in the solid going from the first to the last thickener and the wash water from the last in a counter direction. Not only is the solid well washed by this system but the wash water is enriched so as to require a minimum evaporation.

viable. This is, in effect, step-washing wherein the overflow from one tank is of constant gravity and the underflow repudged with a weak solution, or, in the final step,—water. The advantage of such step-washing is apparent in that all water entering the system leaves as strong liquor requiring no evaporation. The counter current of solid versus water makes the name truly descriptive. Generally displacement washing in filters should be sufficient to accomplish the results desired. It is practical with rotary continuous filters, however, to discharge an incompletely washed cake, repudgle it with fresh water, or weak liquor, and refilter and wash on a succeeding filter, or filters. In such cases, the filtrate from a weak liquor is used to repudgle cakes from strong liquors and a true counter current scheme is set up. This principle is finding an ever increasing application in leaching solubles from materials easily filtered but hard to handle in ordinary leaching methods. The substitution of filters for settling tanks makes possible some marked advantages: clarity of liquid is positive, speed of operation constant and faster, less

Liquor is in process and, due to lower moisture content in cake, a better dilution of the remaining soluble in the wash water is obtained.

Washing in Plant Practice.

It is nearer fool-proof practice to have the operator work on a time or batch limit basis for the determination of the limit of the washing period. Theoretically it is more efficient to make this determination by periodic testing of the gravity of the wash filtrate, for no two batches wash absolutely evenly and, in one case, time is wasted to continue washing when the soluble has been exhausted and, in the other case, soluble is left in the cake that should be regained, unless the hydrometer shows the desired limit by test when this automatically defines when to stop. As pointed out above, however, hydrometer readings, or any other method, is no real determination if the equil-resistant surface of the cake has been lost through dropping cake, air-drying, etc. When operating on time basis the actual control of the filter operation is taken from the filter operator and put in the hands of the superintendent or his appointee. The procedure in this case is to make representative runs either with the plant machine or on a laboratory size unit in which the superintendent determines the average time necessary for the recovery of the soluble.

The control is similar when employing the batch system of washing, when the operator must take a given number of inches out of the wash reservoir or must fill the wash effluent tank so many inches. In the long run of day-in and day-out operation this practice will show a soluble loss very creditable for factory scale work in which labor is variable, sometimes dependable but other times in need of constant supervision. However, batch or time control systems are not infallible where wilful operators are employed. It happened in the writer's observation that an operator, finding the time left on his shift growing short and being behind in his schedule, opened the drain valve on the filter and ran out first the strong solution and was proceeding with the weak liquor when stopped. Such unprincipled action may not have a rightful place in this discussion save to show the necessity for recording meters or floats on strong liquor, weak liquor and even on wash water. Sewer drains should be eliminated. If recording instruments are used and conscientious operators are employed these are found to be distinct aids in keeping the data on each run. The success obtained in this one plant for preventing malicious waste, and the opportunity for better control will have an appeal to many plants having extensive batteries of intermittent filters.

The general practice of determining the end of the washing cycle by hydrometer readings needs caution. Theoretically, the gravity of the wash filtrate should be higher than that of the liquid remaining in the cake. This is approximated only as the operation approaches true displacement washing. Any lapse from this will mean that the wash has been imperfect, and the hydrometer will read considerably under that of the liquid in the cake. Irrespective of the volume of increased solution produced, it will be found that money is saved by taking a safety measure

and insisting on the operation extending beyond the point on the hydrometer which it is desired that the cake shall contain.

Daily, and in some cases, individual, tests for each run should be made for the soluble remaining in the cake. This data is valuable for factory records, and has its psychological effect on the operators. The latter is often spoiled by delays in acquainting the operators with the results of the analyses as quickly as possible. Even a conscientious workman will fail to reason out the cause for a high percentage showing in some run if it is delayed so that several runs have elapsed in the meantime. It has been often found that instead of really pumping wash water into the filter a weak liquor has been made of the wash water supply through a leaky valve, an overflow of a tank, wrong switching of valves, etc. Such troubles can usually be overcome by working up a part of the enriched material as additional weak liquor and using a fresh supply of wash water. There is no better indication of trouble than from the analytical results, and obviously, the sooner the trouble is ferreted out, the less the loss to the company. It cannot be over-emphasized how important it is for the best results that the individual operators be encouraged to become real experts on filtration. Supervisory control by the superintendent or his technologist is, at best, but periodic or intermittent, while if the operator is capable and fully instructed pride in his job automatically provides supervision of the finest quality. Nothing adds more incentive for maintaining good work than prompt reports to the operator of the analytical results. Delays in transmitting such reports are not always due to lack of desire to co-operate between laboratory and filter station, but more often the laboratory routine will not admit prompt action. Such conditions have several times been noted and without exception the chief of the laboratory appreciated the need of better co-operation and changed the laboratory routine to meet the demand.

The above sounds like the conventional hint of the importance of laboratory analyses, namely, to check plant practice, and this is of course true, but it has another importance also. When, prior to the advent of the modern filter, filter press operation was hard and sloppy work, the operators could be mastered only from strong and unskilled workers. Today filter operation is quite the reverse,—the operator is more intelligent. To such men laboratory reports are not so much checks on their work as co-operative aid. A rather remarkable evidence of this difference in the appreciation of laboratory analysis comes to mind in recalling a large chemical plant which discarded plate and frame presses and put in Sveastland filters. One operator out of five was chosen for each shift and resulted in two Italians and one old Irishman being selected. The Italians picked up the scheme of operation first but the Irishman had better uniformity in his washing results. A friendly rivalry ensued, and instead of fearing the reports from the laboratory, each would fairly bound the laboratory by telephoning for the percentage of his last run. Needless to say, these filters are praised in the most glowing terms by that management who point to the savings on the better washing of the cake, which alone turn 400 per cent per annum on the installation cost of this battery of filters.

INDUSTRIAL FILTRATION

If laboratory analyses are reports on work done, the question arises is not such a report merely a cry over spilled milk? "Yes," for that particular run, but it guides the operator on succeeding runs. If laboratory analyses show continuously good results, is it not useless work to continue making the analyses? There are instances where with uniformity of raw product, control of the operations preceding filtration are refined so that the material to be handled in the filter runs truly uniform. In such cases it is quite admissible to make the analysis per shift instead of per run, but if the raw product is liable to changes or if the batches cannot be controlled with exactness, the operator needs the analysis to verify his operation.

Chapter IV.

Cake Drying.

Drying the cakes has been ranked lowest in the cycle of filter operation, but it is now realized that this department is worthy of more attention.

To begin with, if filtration is defined as the separation of solids from liquids, then the drier the discharged cake, the closer the approximation to this definition.

Dryness of discharge is obviously advantageous in chemical manufactures when bone dry precipitates are the products turned out. Naturally, when a further drying operation is required, reducing the moisture before feeding the cake to the dryer relieves the duty of the dryer and it is generally cheaper to extract moisture mechanically than to evaporate it, using up good B.T.U.'s.

At one time drying was considered necessary only when the solids were desired as a completely dried powder. It is now realized that to dry,—meaning to *desiccate*—the cake *before its discharge*, is good practice in almost all instances, including those where the solid is a waste to be discarded.

When the cake is a waste, the percentage of moisture in the cake is not a vital consideration save to guard against losses of valuable soluble in the discharged cake. If the washing operation has been efficient, drying the cake may be superfluous, but if defective washing has taken place, then decreasing the moisture content decreases the soluble in the cake. In other words, the drier the discharge, the less liquid present and consequently the less soluble thrown away.

When the solids are wastes, the drier the discharge, the easier the cakes are to handle in disposal by transportation. This is clearly demonstrated when factories located in the heart of a city have to truck these wastes to distant dumps, or lighters at wharves, when sloppy cakes spill on the pavement and increase the labor of dumping the load.

Drying the cake is fundamentally dependent on the formation of the cake. If a compact cake is produced, the voids in the cake are minimised; if a fluffy cake is formed, the percentage of voids is large. In either case the work of drying the solids is the removal of the liquids in the voids. Obviously, those cakes having low percentage of voids require less duty on the drying operation than those with high void content.

Firmness of Cake.

It is somewhat academic but nevertheless important to understand clearly the theory of cake formation which bears such a relation to drying

efficiency. When a filter is first started up or when a section of a continuous filter first dips into the liquor, the rate of flow is greatest. The flow may quite as readily be conceived as the summation of the delivery from every square inch of surface. On each unit area, cake is being deposited and its compactness is in direct proportion to the velocity of the liquid being filtered. When the velocity is high the stream lines are said to be strong, and weak when the velocity is low. Therefore, if the velocity is maintained at a high rate for a long period, the stream lines are strong and the cake firm. This, then, gives the reasoning on which better drying effect is obtained when starting with low pressure for the handling of difficult filtering materials, because this low initial pressure does not build as resistant a cake and admits of a greater flow throughout the cycle thereby. Obviously, the cake produced by strong stream lines must be a dense cake if we consider the cake as being built up by arresting the particles of suspension carried by the stream lines (its momentum being in direct proportion to the velocity of the stream line). The greater the impact upon the cake, the denser the cake produced.


Efforts to get dry cakes have in the past been evidences of insufficient knowledge not only of the principles underlying best drying methods, but also of general economy in filtration. Until recently one of the most progressive sugar mills filtered the settlings to hard, compact and relatively dry cakes, repuddled the discharged cakes with fresh water and re-filtered the mixture. The low sugar content in the final cake proved the wisdom of this method of preventing sugar losses in press cake, but careful experimentation proved that this process did not result in any profit worth the effort. The long time required to get the hard dry cake in the first presses made the impurities in the cake more soluble, so that when mixed with fresh water they dissolved and lowered the purity of the recovered sugar to a point where they made molasses rather than crystalline sugar of the recovered sucrose. Time was the factor which nullified these results. How to decrease the time required in obtaining dry cakes in frame presses is pertinent not only in the sugar industry but in chemical manufacture in general and in the pigment and color industry in particular. Usually the time consumed has its greatest bearing on the capacity of the filter since *time used for drying is time lost for filtering*.

Plate and frame filter presses stand in a class by themselves as filters delivering dry cakes. This is because the cakes are more compact than those obtained from any other type of filter. We must therefore discuss the agents at work in making hard cakes.

Cakes in Plate and Frame Presses.

In plate and frame presses the deposit in each frame of the press starts as an independent cake on the two walls of the frame which build up until they meet. Further filtration is not a pure cake building operation but is rather cake compressing. The solids are confined in the frame and as more solid enters it jams the particles closer, decreasing the voids in the cake. Filtration in filter presses, therefore, varies at this point

from filtration in leaf filters, in that the pump begins to do the work of cake compressing rather than continuing the work of cake forming. It is this compressing action that helps so materially in the production of compact filter press cakes. The principle of cake compression for dryness of discharge is unfortunately not applicable to leaf type filters. Here, the cakes must not be allowed to form so as to touch each other, or otherwise all the advantages of displacement washing in self discharge are jeopardized. Also, overcharging in pressure leaf filters is insidious in its evil effect of warping the filter leaves. Difficulty from tearing the



Courtesy T. Shriver & Company

FIG. 14.—An Up-to-Date Recessed Plate Press.
In general appearance quite similar to the plate and frame press.

cloths on distorted leaves and from straightening the drainage members is apparent, but in a well-designed and well-operated machine the filter leaves are spaced so that the cakes do not meet. When the leaves are bent out of shape it is practically an impossibility to straighten them completely, at least while in the filter, so that the original spacing is changed and some of the leaves are on closer centers. This, of course, is a condition ripe for continuing this difficulty and becomes a constant source of trouble. It is not generally understood just what produces the distortion of filter leaves. It is not that the leaves bend away from the cakes which have joined together but that, by their having joined together, the pressure between them is lowered while the exposed sides of the leaves are subject to the full pressure. This gives an excess force which, acting over the entire surface, exerts enough pressure to cause the leaves to bend in toward the joined cakes.

Cake building is assumed to have progressed according to the best

INDUSTRIAL FILTRATION

methods for clarification and capacity, yet the resistance for drying is still in the majority of cases too high. There is only one solution—make the cakes join quicker by reducing the width of the frames. Too wide a frame requires too long a cake building period and allows too great a resistance to the flow to be set up before the work of cake compression commences. It is thus seen that for any particular material there is a balance between the maximum caking capacity of a press and the dryness of the cake consistent with economic operation. These data are best determined by experimentation on the material in hand to determine its filtering characteristics without giving thought to dryness of discharge. Knowing the cake thickness obtained before the filtrate decreases to a small flow will indicate the size of the frame best suited for that material. Change in width of frame is not a new idea but has been well appreciated for many years. The manufacturers have been loath however to reduce frame widths to a point where the walls of the inlet ports are thin. This has been the limiting specification but the same area of port inlet is obtainable in several narrow inlets as in one wide port and with no greater tendency to clog the inlet than in conventional ports. This design obviates the necessity of chamber presses with the annoyance of center feeds. It is surprising what a difference $\frac{1}{4}$ in. frame thickness will make with many materials in the time required for drying. The loss of volume of cake per frame is negligible as compared with increase in cycles, ease of discharge and better all-round efficiency. Frame thickness should be determined almost entirely on the basis of drying time required.


Moisture Displacement by Compressed Air.

Drying the cakes in leaf filters, therefore, must be obtained by displacing the entrained liquid in the voids of the cakes by some gas (compressed air, steam, etc.). This part of the filtering cycle is undoubtedly the weakest in the operation of leaf filters. To start with, the cakes, as built up, are high in voids, a mere examination of the cake showing the exterior of the cake to be far wetter than that against the filter cloth, and the bulk of the liquid extracted from the cakes must pass through an ever-increasing resistance until penetrating the filter cloth. This, of course, entails high duty on the drying agent.

When drying with compressed air, which is in reality filtering compressed air through the cakes, the effect is to supplant the liquid in the voids of the cake with air. This, obviously, is less support for the particles of the cake, so that there is a rearrangement of the particles,—generally spoken of as the "shrinking of the cake." The shrinking results in cracks developing which immediately form paths of less resistance for the passage of compressed air. At this stage the drying effect is negligible in comparison with the work of compressing the air and best practice is to halt the drying operation at this point.

Prevention of Cracking of Cakes.

Best drying operation in leaf type and continuous vacuum filters is obtained, therefore, by proceeding in that manner which decreases the early formation of cracks. With granular and similar materials this is so practical that the difference of per cent of moisture in cakes of such materials as discharged from modern filters and moisture in cakes as discharged from filter presses is not large. When handling fine, flo-



Courtesy *Filtration Engineers, Incorporated*

FIG. 15.—Recent Improvement to Continuous Rotary Drum Filters.
Flame Cake Compressor for washing, dewatering and discharging the cakes.

ulent materials it is more difficult to prevent early cracking. The procedure in such cases is to build up as dense a cake as possible before admitting the compressed air and to remove as much moisture in the cake at as low a pressure as possible. The means of forming the dense cake can best be determined by experimentation, but it is often found that if the initial filtration be carried on at a low pressure and allowed to rise to a point considerably less than that used during the washing operation, good results are obtained. In vacuum continuous filters, especially those of the drum type, flapping and cake-compacting mechanisms can effect this result mechanically. In any design of vacuum continuous

filters, where cake cracking cannot be avoided, there is a big saving on the duty of the vacuum pump if the automatic valve be constructed so as to shut off the suction at the time of crack formation.

Leaf type filters constructed so that the outlet of the leaves is at the top of the leaf are not as satisfactory as those that drain from the bottom. The reason for this is quite apparent, for bottom-discharge leaves drain out all the liquid, whereas the top-discharge pockets the liquid and on discharge that liquid is forced back through the cloth and mixes with the discharged cake. This is the advantage of bottom-drainage filter leaves and is the only reason for drier cakes being obtained from their use.

It is a proved fact that many materials may be discharged from leaf or continuous filters higher in percentage moisture than cakes of the same materials discharged from filter presses and yet in subsequent driers will be found to work better. This is due to the cake formation admitting a better heat conductivity and escape of the steam vapor. True, if the cake from the filter presses be broken up, then the advantage lies with the filter press cakes.

We must also remember that in true cake building the deposit against the filter cloth is the densest, while that farthest away is softest and contains a greater percentage of liquid. In dewatering this cake, the liquid must penetrate through the ever-increasing dense parts of the cake. Here, then, is the clue. If the resistance of the dense deposit is too high, the work of getting the liquid from the softer portions through it is increased. How to reduce this resistance is the question.

Cake cracking on continuous drum filters has been the prime draw-back in obtaining dry cakes from these machines. Some installations are supplied with oversize dry vacuum pumps and are able to get the moisture down irrespective of cracks. This is, obviously, a poor use of power. To compress the cakes, decreasing the voids in the cakes is the best method of attack for dewatering the cakes. This is accomplished by compressing the cake on the drum of a continuous filter with a belt and rollers as described in the chapter on "FElinc Apparatus." Success with such device is obtained only when the cake is not disrupted. Rupture of the cake prevents free passage of the water in the cake through the filter cloth and gives trouble from cake adhering to the belt. If the cake is properly compressed by the belt, cracks cannot form and therefore small dry vacuum pumps can be used. This creates a saving not only in first cost of pumps but in power required for their operation. By this means cakes can often be discharged containing less than half the moisture that they would contain without this device. The dryness will vary with different materials and there is much flexibility in the choice of the cloth used for the belt and in the pressure applied to the rollers. In handling a free-filtering material the belt can be much denser and the pressure much heavier than in handling slower materials. This is accounted for since the air penetrating through a freely filtered solid is not as necessary as in the case of the difficult filtering material.

Heating.

Heating the slurry for filtering even when it is a water mixture will prove beneficial in drying the cakes. A cake from a hot liquor can be built up much thicker than from the same liquor cold, even though it be a water mixture. This enables moisture to be extracted more easily from the deposited cake and the heat carried by the solids evaporates some remaining moisture. Furthermore, if the discharged cake is fed to a dryer, the higher the cake's temperature the less heat is required in the dryer for complete evaporation of moisture. This fact led to the idea of making the cake from a continuous filter directly conveyable by wire belting to a dryer. This principle is the basis of the FElinc Drying System. In this, the cake, while still on the drum, is enmeshed in a wire belt that conveys it into a dryer. Discharge of the cake as a dry powder is effected by a beater which dislodges the dried solid from the wire belting into a covered hopper. This device completes the separation of the solid from the liquid by discharging a really dry cake from a filter.

Chapter V. Cake Discharging.

Discharging the cakes from filters is a necessary evil representing time lost for filtering or washing. Where the cakes are valuable and subject to further processing, discharging them in a condition easiest for the subsequent treatment is a matter of technique and proper choice of machine. Discharging the cake is in many respects the keynote of efficiency in filter operation. Any type filter that cannot be operated so as to keep the cloths in a free filtering condition for recurring runs is not only inefficient, but a makeshift. Let clarification, washing or drying be faulty and discharge satisfactory, and the filters can still operate with a certain degree of economy. More filters are operating poorly by reason of incomplete, or time-consuming, discharge of the cake than for any other reason, and in too many of them this is needlessly so.

"Discharging" means *removal of the cake so as to render the filter cloth suitable for refiltration*. If discharging is complete with each cycle, the filter maintains its capacity; if incomplete, repeated operation is likely to show a decreased capacity falling off in more than arithmetical progression as the clogging effect is cumulative.

The fundamental of complete discharge is that the filter cloth (both its surface and pores) shall be cleaned 100 per cent. Surface cleaning is obviously easy and simple; *complete* cleaning is the subject for discussion.


Complete cleaning signifies removal of solids from the interstices of the filter cloth. If the cakes are sufficiently firm so that in cleaving from the cloth they pull all the particles out of the cloth, complete discharge is easy. Here we find the secret of the familiar "good hard cakes" in frame presses, for a hard cake is coherent and easy to discharge. Other advantages in getting hard cakes are attendant,—the fundamental is their easy discharge.

In modern filters, especially of the leaf type, hard, compact cakes are rarely obtained that can compare with the cakes from frame presses, which are compact in form and fall out of the frames as operators move up successive frames. In modern filters, reverse current of compressed air, steam, water, etc., acts as the discharging agent, disengaging the cakes from the cloth and allowing the solids to fall by gravity or to be removed by a scraper or by striking streams. Reverse pressure need not be high enough to blow off the cake, although there are numerous materials that fall off while the reverse current is on. This point is vital, as evidenced by the caution every modern filter manufacturer makes of

using reduced pressures only. Obviously, their concern is in an effort to conserve the life of the filter cloth. High pressure, when using steam, represents high temperature, and, unless there is sufficient condensation to cool the temperature in the cloth, this is a factor in deteriorating the cloth.

Reverse Current Discharge.

Some of the most marked advances in filtration are due to the introduction of those continuous filters which employ reverse current discharge. Filters working on sodium carbonate, free-filtering calcium carbonate, or gypsum, may not require this means of discharge on account of their extremely granular or free-filtering characteristics, but cement slurries,



Courtesy United Filter Corporation

FIG. 16.—American Continuous Rotary Filter—Disc Type.

The filter area is arranged transverse to the axis instead of around the periphery of the drum, as in drum filters.

kaolin and other finely divided materials are inapplicable without this means of discharge. If some of this kind of material is left on the cloth, recurring filtration causes fine particles to wedge into the deposit and scale-like impenetrable mass results and most effectively blocks off further filtration.

The advantage in the use of compressed air, steam or water as the

discharging agent is dependent upon local conditions. In leaf filters reverse current through the leaves while they are submerged is often more efficacious than the same current through the leaves suspended in the atmosphere. There is good reason for this, for with the submerged leaves the water has an opportunity of getting underneath the cakes and helps release the cake when air current issues through the cloth.

Some operators are quick to condemn reverse current discharge because it will, in some cases, clear small areas on the leaves and leave the remainder undischarged. It is true that if the air can escape through a part of the cake it will not issue through the rest of the leaf forcibly enough to release the whole cake. Such conditions indicate that either too dense a cloth is being used, or else that there is some tenacious constituent in the cake which defies discharge. In this respect it is well to point out the analogy between the nap on the surface of a cotton, or cellulose, filter cloth and the hair used in plaster for walls and ceilings. Each has a blinding action and the nap of the filter cloth is a big factor in causing ineffective discharge, so that metallic fabrics are often advantageous just for this point alone. A discussion of this effect of nap will be gone into later.

It cannot be too strongly emphasized that automatic discharge from leaf type filters is due to the combination of the releasing of the cake from the cloth and the fall of the material due to gravity. Therefore, any impediment that hinders either factor jeopardizes the discharge. Some cakes have a relatively high tensile strength,—are leathery in texture,—so that the mere bridging over of the cake at the top of the leaves is sufficient to hold those cakes from discharging. In such cases it is good practice to coat over, or cover, the rim of the leaves to prevent filtration at this point so that no bridging effect is possible. The same is true of any obstruction which tends to hold the cake, such as bulky side aligning lugs in Sweetland filters, unflattened drainage pipes in leaf construction, etc. If, therefore, the reverse current of compressed air is ineffective in releasing the cake from the surface of the cloth, if the cake is of too small a bulk, or is prevented from falling by some obstruction, the discharge will be unsatisfactory.

Use of Steam, Air, Water or Scraper.

Determining whether to use compressed air, steam or water, etc., as the agent for discharge, is a matter best decided in light of local conditions. Generally speaking, compressed air is best. Its pressure is easily controlled, it adds no moisture to the discharged cake, and its temperature has no deleterious effects on the filter cloth, and it distributes itself well across the entire area of the cloth. It does, of course, have a cooling effect and when handling hot liquor it may then be that steam can be substituted to better advantage. Steam is necessary when handling materials that must be maintained at high temperature, and it stands today as preferred to compressed air for this duty. The trouble with

compressed hot air is that the heat of compression added to the temperature of the hot air puts a strain on the compressor. Condensation of steam on the inner surface of the cake often facilitates discharge from leaf filters when this lubricating effect makes the cakes slide from the leaves.

Water, or any liquid, is in a sense the best reverse current because it more forcibly pushes the cake from the cloth, but its use is obviously limited. Unless the leaves are submerged, the water will often fail to remove the upper parts of the cake before it issues through the cloth at the bottom of the leaves and never issue through the upper areas. Reverse water, hot or cold, is the agent that opens the pores of the cloth more positively than any other, but it is hard to distribute across the total area of the leaves and the weight of the water in a vertical leaf puts a heavy strain on the cloth at the bottom with an excess issuing from the bottom. The most successful method of reversing water is to close the bottom discharge valves and to open an overflow at the top so that the water that passes through accumulates and balances the load at the bottom of the leaves. It is sometimes possible to feed both air and water as reverse currents and it is always possible to feed compressed air after the water has filled the filter. The bubbling action of the air stirs up the water and aids considerably in cleansing badly clogged cloths. This is especially effective if with turning on the air the bottom drain valves are opened. It is yet to be proved good practice to introduce steam with water, or after a reverse current of water, as the steam simply condenses and heats up the water, its purging effect being lost.

When cakes are thin and have not sufficient bulk to fall off of their own weight, when released by compressed air, discharge from leaf filters is impractical without submerging the leaves or without using scraping methods. If the latter must be resorted to, it must be realized that the scraper has the tendency to smear the cake into the pores of the cloth unless the reverse current of air is operating at the same time. This is the basic reason for the efficiency of discharge in continuous filters and in the automatic discharge plate and frame presses.

Discharge from Gravity Tank Filters.

The discharge from gravity tank filters has usually been by the laborious method of hand shoveling. It is simple, however, to rig up automatic means, especially if wet discharge is not objectionable. All that is required is a drainage opening and to forcibly eject the cake with a water hose. It is also possible to discharge the solids mechanically by using a rotating raking device that can be lifted free of the liquor level while filtration and washing takes place and that can be lowered into the cake when ready for discharging. The weight of the rakes will be sufficient to plow into the solids. The rakes must, of course, be designed to move the mud toward the outlet provided in the tank.

Thickness of Cake.

Often thin cakes are held to be incapable of discharge by reverse current methods, whereas the trouble lies in the construction of the filter leaves. When the reverse current of compressed air is first turned into the leaves, the effect is to balloon out the filter bags, especially with dense cloths. When the bag is distended, the upper part of the bag supports the cake from falling, even though the reverse air has efficiently disengaged the cake from the cloth. This is obviously a contrary condition for the best discharge of the cake. It is minimized by securing the cloth to the leaves at intervals across the entire area of each leaf, or by lateral stitching of the cloth to form pockets into which wooden slats, etc., drainage members, are inserted. Then the ballooning effect is decreased sufficiently so that the discharge of the cake is just as efficient at the top of the leaf as at the bottom. In continuous vacuum filters the sections are narrow enough and the wire winding is spaced close enough that ballooning of the cloth gives no trouble with these machines.

Very thin cakes are difficult to discharge but do not offer the difficulties encountered in discharging cakes that are too thick. In leaf filtration, cakes are too thick only when adjacent cakes touch each other. Such a condition is diametrically opposite to the theory of operation in this type of filter. It is fundamental that a space remain between adjacent cakes that there may be room for the free fall of the cakes when released from the filter medium. When the entire space between the leaves is filled with cake, it is rarely that the cakes can be discharged. Overcharging of a leaf filter is bad operation and indicative of poor control. If it were that the extra time required for discharge were its only disadvantage, it would not be so necessary to emphasize this point. But, overcharging is productive of warped leaves and they kill any hope of efficient filtration.

Filtrate and Cake Rating.

Overcharging is due either to too long a filtering cycle, or to too narrow a spacing of the filter leaves. Either condition is easily controlled and good filter operation demands the prompt correction of those conditions. There are liquors which, as the precipitate is commonly formed, contain too high a percentage of free-filtering material to be easily controlled in leaf type filters. Wherever possible, these materials should be handled in continuous type filters, which are more adaptable to this class of work, but where temperature, acid content, etc., call for leaf filters, the widest practical spacing should be employed, and if the solids still build too freely, then the liquid content of the material should be increased by returning some of the filtrate.

Consideration of overcharging brings out the point too often overlooked, namely, that the rating, or duty, of a filter can be either in terms of filtrate delivered or in cake built up. With very free-filtering materials the latter view is safer, and while it must be measured by the

quantity of filtrate delivered, or by the time of filtering, it is the prime consideration, for seldom is the economical limit of filtration for such materials reached by waiting for the filtrate to decrease in flow to its economical limit. To do so would build up a cake too voluminous and heavy for the best operation, both as regards washing and discharging. In design, Sweetland type filters are admirably adapted for those solids which easily fall from the leaves, for the lower half of the machine opens away from the leaves which do not have to move through the cake. In practice, however, the cake in the lower half is often a load in excess of the power of the operating cylinder and makes for dangerous banging of the counter-weights against the shell. Also, the cake remaining in the lower half has to be removed by hoing it out by hand, or hoing it out with water.

Nap on Filter Cloth.

Discharging the cakes from leaf type and continuous filters is practical only if the cake formed is deposited upon the surface of the medium. A surface containing nap, fibres, or similar roughness, is obviously one from which the discharge is complicated in proportion to the amount of such roughness. The cake will adhere to these surfaces in a manner quite similar to wall plaster in which the rough surface and hair form reinforcements. In discharging, therefore, it becomes essential that this factor receive attention.

Probably the simplest attack in overcoming the difficulties of nap in the filter cloth is to eliminate it from the cloth. Manufacturers of filter cloth,—up to this time, at least,—have not given any attention to the reduction of nappy surfaces, save possibly when they use selected stock such as Egyptian cotton or long staple domestic cotton, etc. This means that the local consumer must provide his own means for reduction of nap. There are several ways of effecting this, notably singeing the cloth or mercerizing it. Singeing requires considerable dexterity if it is to be successful without injuring the cloth. To merely remove the top, or apparent, nap is to do the job but partially. The nap in the interior must also be removed, and this implies that the flame when singeing must extend into the interstices. The control necessary when using dense cloths is practically too severe to be workmanlike. On thin or open cloths the singeing flame can easily extend clear through and make a real job.

Mercerizing is the process of treating the fabric with a corrosive liquor for a period, or in solution of such strength as to limit the action to the surface of the yarn or fabric. In mercerizing cotton cloths, caustic soda solution is the usual agent. The control of this process is not extremely difficult, but the causticized material must be washed clean, or else, in drying, the alkali present will concentrate and spoil the cloth. This process involves both equipment and labor that the average plant will not care to install. It is only large filter stations, using bolts of cloth at a time which will ever find it economical to go to the trouble of reducing nap. Consequently, the average installation is one in which

the nap is present and must be taken care of by other means, such as pre-coating.

Pre-Coating Aids Discharge.

Mention has been made before of the inter-dependence of the various phases of the filter operation, but here is a very positive example. Under "clarification" we found that best practice demanded that the filter cloth be coated with a free inert material,—this process being known as "pre-coating." In discharging, this deposit serves as the means of laying down the nap necessary for easy discharge, and consequently the choice of pre-coating material is but slightly affected whether we are considering it for its discharging qualities, or for its use in aiding clarification. If in self-discharge filters the material handled is free-filtering, discharge is always simple. When handling gummy, gelatinous, or colloidal materials, the discharge is quite the reverse. In fact, failure to effect a discharge of the solids from such liquors long prevented the application of modern filters to this class of material. It was in conjunction with the application of Sweetland filters to sugar refinery liquors that the proper handling of such materials became practicable. The essence of the difference between success and failure here lay in coating the surface of the cloth, thereby laying down the nap which made discharge possible. The required amount of deposit is astonishing to many who have not been familiar with the process. Time and again inspection of the filter cloth after pre-coating will show hardly any visible deposit except by scraping the surface. For instance, in pre-coating the cloths for handling the settling in liquors in raw sugar houses in the tropics it was standard practice to make up the slurry so that one pound of filter-cel would coat 100 square feet of filter cloth. This amount, if added to clear water, contained a considerable factor of safety, as tests showed that the deposit was sufficient when one pound was distributed over 200 square feet. The test by which the operator determines whether his pre-coat has been sufficient or not is in examination of the discharged cake. This contemplates, of course, dry discharge, as sluicing discharge gives him no opportunity to inspect the cake. The surface of the cake which has been adjacent to the cloth should show a thin deposit of the filter-aid, usually as a white coating. If this coating is not complete over the entire surface of the cake it is probable that the missing portion is still adhering to the cloth, or, more likely, that it is from that area of cloth which has not been coated. Surely another proof of the effectiveness of the pre-coat is the capacity obtained from the succeeding run. There have been cases where this proof failed, however, for the material may change and the reduced flow may then be due to the characteristics of the material filtered and not to the porosity of the filter cloth. When a cloth shows signs of plugging up, these clogged areas get less and less pre-coat with each succeeding run and consequently grows less and less porous. With this in mind, therefore, it becomes economical to be generous in applying the pre-coat, so that a cloth will be safeguarded from this clogging effect from the first operation on through each succeeding operation.

Sluicing Discharge.

When filters are working on liquids containing a small percentage of solids, they are better known as clarifiers. In this class of work, the solids build up to form only a thin coating on the cloth and a discharge by reverse current methods in leaf filters, or any discharge in continuous filters, is impracticable. The customary method is to sluice the solids off the filter cloth by forcibly spraying water on the surface of the cloth. This is efficient when the solids have not penetrated the pores of the cloth. Success of such methods is evidenced by the record of the Merrill plate and frame presses in the cyanide industry and Sweetland filters in cane sugar refineries. In both these filters the sluicing is done by rocking the sluicing pipe, or manifold, back and forth so as to project the sluicing streams over the entire surface of the cloth. This operation is invariably done without opening the filter and in respect to cleanliness of operation is distinctly advantageous.

In sluicing discharge, the projected streams of water across the surface of the leaves must be of sufficient velocity and quantity to cut the cake away from the cloth and disintegrate it so that it will drain from the filter as a shirry. The angle of incidence of the stream upon the cloth must be such that the water, rebounding, will not interfere with the projected liquid. Obviously, a stream perpendicular to the leaf represents the inferior limit, while that projected parallel represents the other limit,—both of which produce zero discharge. In practice, the sluicing nozzles are located in a sluicing manifold at one corner or at one side of the filter element. The angles of incidence are then variable, being greater when the streams play against the cloth nearest the nozzles and least when playing against the cloth farthest from the nozzle. In order, therefore, to have the average effect, the best efficiency at the two extremes is sacrificed. This is the basis of the design of sluicing nozzles, although, in practice, the actual sluicing is facilitated by changing the position of the nozzles by longitudinal movement of the sluicing manifold. This makes the nozzles have changing positions from that practically adjacent to the filter cloth on one leaf to that adjacent to the cloth on the next leaf. In the latter position the angle of projection in removing the cake farthest from the nozzle is best. The entire design is based on the premise that each leaf is a flat surface at right angles to the sluicing manifold. In practice, leaves in Sweetland filters approach this condition but never realize it. Notwithstanding, however, this method of discharge is very effective when applied to cakes of small thicknesses. In Sweetland filters the sluicing manifold is located in the upper part of the filter and so long as the drainage openings of the machine in the bottom are large enough, so that there is no backing up of the sluicing water, the entire surface of the filter cloth is subjected to the sluicing streams. In Merrill sluicing frame processes the sluicing pipe is located at one,—or, in some cases, at both,—corners of the press. The usual application of this type of machine is in materials of slow but relatively uniform cake building properties. In consequence, a greater volume of cake is built



Courtesy Valley Filters

FIG. 17.—Valley Rotary Leaf Filter.
Pressure leaf type in which the leaves are revolvable.

up than in the usual application of Sweetland filters requiring sluicing discharge. In order to disintegrate such cakes, the streams must work on the cake nearest the outlet channel and this is at the bottom. Probably the machine most ideally designed for sluicing discharge is the Valley filter wherein the sluicing nozzles are stationary and the leaves rotate against the projected streams. This means a more positive directing of the water against the cake and since the stream needs to reach only from the periphery to the center of the leaves, the distance that the stream must carry is only half that required in Sweetland filters.

There will be found extremely few instances where sluicing discharge is found practical and pre-coating impractical. The mere fact that the filtered solids can again be mixed with liquor, or water, defines that the solids are waste products, or subject to further processing. In either case, therefore, it is seldom that an inert filter-aid will do harm. Sluicing discharge should always be limited to those cakes of thicknesses that defy discharge in the dry state. Theoretically, sluicing discharge should be practical in combination with reverse current in that the reverse current would lift the cake from the cloth, while the sluicing streams would sweep the cake from the surface. Practically, however, the reverse current, by virtue of its ballooning effect on the cloth, jeopardizes the effectiveness of the sluicing streams. The nearest approach to a practical combination of these two methods is when steam is used as the agent for the reverse current and hot water as the sluicing agent. The water, playing upon the cloth, condenses the steam and collapses the cloth at that point so that there is no ballooning in that region. However, if pre-coating the cloth is a part of the operation, reverse currents are not necessary so long as the sluicing nozzles are working right. If one were to point to that discharge in which pre-coating is most valuable, it is probable that it would be when sluicing methods are required.

One would think that the design of the sluicing nozzles would be a matter of accurate design. Much experimentation has been made on this point but the simplest design is the one most used. Simple pipe nipples, usually $\frac{1}{4}$ in. extra heavy pipe, threaded into extra heavy pipe as a sluicing manifold, is all there is to it.

The matter of uniform feeding of the water under pressure to all the nozzles is also a matter that would first seem to entail some niceties of design. It is required only, however, that the total area of the sluicing nozzles shall be less than the internal area of the sluicing manifold. When a long filter with leaves in narrow spacing would require an extra large pipe for the sluicing manifold, it is better mechanics to feed the sluicing water at both ends with pipes of equivalent size to a sluicing manifold. In this case, the water has to distribute through half the length of the filter only and consequently the ratio of nozzle area to manifold area is maintained with a pipe of internal area only in excess of half the nozzle area.

The longitudinal motion of the sluicing manifold, referred to above, should be uniform, especially if the filter is designed with one nozzle per side of leaf. This is not generally the practice, as some operators desire

to eliminate the operation when a sluicing nozzle throws its stream between the leaves without hitting either leaf. Operators usually pass this point with a rapid movement but in daily practice this does not pan out well. It is better to sacrifice the water and sluice automatically. The details of the mechanics covering this point (described in the chapter on "Sweetland Filters") are quite ingenious.


There is one other factor in sluicing discharge that has value although its amount is somewhat indeterminate. This is the rebound of the sluicing stream projected against one leaf playing upon the adjacent leaf and the possible rebound from it, duplicating the action. This seems a reasonable conjecture, although one is apt to think of a water jet being broken up into a spray if subjected to sufficient baffling. However, the stream is not that of clean water but one containing solids which undoubtedly start as accumulated solids, the effect of which must approach that of sand in sand blast operations (such as cleaning facades of buildings, iron castings, etc.). One is convinced that this is a factor after noting the discharge used on a battery of Kelly presses in a sugar mill in Cuba. Here, the superintendent in desperation resorted to the use of compressed air at 70 lbs. per sq. in., pressure from a sand blast nozzle as the means of discharge. The operator played the nozzle against the leaves near the top and the deflected blast so moved the cake that the bottom of the cloths were always clean, and ahead of the top of the leaves, without even lowering the nozzle.

Discharge from Leaf Filters.

Experience has proved that it is a fallacy to attempt to partially discharge the cakes from leaves of pressure leaf or suction filters, with the hope that the agglomerated solids will fall to the bottom of the filter, leaving the upper part of the leaves clear and in a free-filtering condition. There is always a momentary rush of filtrate at high capacity after attempting this scheme, but it does not last, for the cakes re-form and the solids present are increased so that the resistance builds up quickly. If the scheme were practical, so far as increasing the rate of flow is concerned, it would be hazardous when desiring to make a final discharge even if the leaves had not been warped out of shape before opening up the machine. If the leaves are on such wide centers that the dislodged cake will not bridge over between the leaves, this scheme would be better substituted by putting in more leaves on closer centers, and getting greater filter area.

Materials Difficult to Discharge.

When handling materials that cannot be effectively discharged, those filters in which the cloth can be most easily removed and replaced by clean cloths are the best the market affords. Fortunately many materials hitherto resisting all methods of effective discharge are today, by reason of our better knowledge of the art, satisfactorily handled. There can be



Contact Resistance Testing Technique

FIG. 22—Worst Series Lead Time—25 Hours to 250 mΩ Series Resist.

no refutation to the fact that inefficient operation of filters paves the way for substitute methods of clarification,—decantation, flotation, centrifuging, etc.,—and faulty discharging discredits filter operation most severely.

As is pointed out in the chapter on "Clarification," dense filter cloths are not good media for best filter operation. We have come to realize that the filter cloth is best designed when used as an auxiliary filter medium, so that we need no longer choose a cloth solely for its clarification properties. This fact alone is responsible for a considerable advance in the better discharge from many installations. No explanation is necessary for the reason for this. It is apparent that dense cloths retain particles caught in their pores much more than thin or open weave cloths.

Open cloths have a further advantage in that they allow the reverse current of the discharging agent to exert a greater force in disengaging the cake from the filter medium than do dense cloths. The latter balloon out with the introduction of the discharging agent and prevent discharge of the solids; in fact, support the cakes and allow but little of the reverse air or steam to act upon the cakes.

The effectiveness of the discharge is often inaccurately indicated by an observation of the surface of the cloth. The Rate of Flow on the next cycle is the best proof of the thoroughness of the cleaning action. Some operators working on granular material see the cake fall from the filter cloth the moment the pressure is released and see no need of further cleaning the cloths by reverse currents. To see those filters hung up while the leaves are taken out and hand scrubbed proves the utter inadequacy of the discharge. To leave only a minute film upon the cloth will in time necessitate strenuous methods in order to regain the original porosity. *Thorough discharge is necessary at all times.*

Chapter VI.

Filter Media.

Industrial filtration involves the separation of a comparatively large amount of solids from a small volume of liquid. The rate of flow of liquid through the filter medium is low; hence woven fabrics through which only a small flow is obtainable are used most successfully. Fabrics of high resistance to flow of water through them have for years constituted the typical filter cloth for industrial filtration. Today cotton duck represents one limit, the dense, and unbleached muslin the other limit, open.

Filter fabrics can be divided into two main classes; those used for neutral or non-corrosive liquors, and those for corrosive liquors. The latter are mainly special media of wool, metal, asbestos, stone, etc. For non-corrosive liquors cotton is the material used almost without exception.

Cotton Filter Cloths.

Weaves.—Cotton filter cloth fabrics are made up in duck or plain, twill, and chain weaves. Plain weave has the square or right-angle appearance of all ducking and is woven by the filling or weft passing over one warp and under the next, known as "over one under one." Twill has the diagonal lines so characteristic of its weave, and is made by weaving "over two and under two," with the next filling splitting the warp members. Chain, or as it is also known, broken twill, has a herring-bone appearance and is woven with one filling going over two and under two, the next reversing this order, the third being a true twill sequence, and the next repeating the above cycle again. For each weave there is considerable modification, depending on the weights of yarn used and the number per inch. Muslins and drills are trade names for very light duck and twill weaves.

The nomenclature of the various weaves should be better standardized. At present a duck is known by a number (as 60) or by the weight per unit measure (10 oz.). Twill and chain weaves are designated by the number of warp and filling members per inch, as for instance No. 2232, where there are 22 warp members per inch and 32 fillings. There is ambiguity here, for the twills woven of different yarns under the same number of members must weigh differently. A combination of weight per unit and designation of the number of warp and filling members would do much to clarify this.


Use of Muslin.—The commercial use of unbleached muslin and other comparatively frail filter cloths marks a distinct advance in the subject of filter media, and represents the application of a principle long understood but impractical until the advent of our modern filters.

Filtration through fabrics should be surface filtration wherein all the particles filtered out of the liquor accumulate on the surface of the medium, as distinct from bed filtration wherein some of the solids are caught through the depth of the filter bed, as in sand or charcoal filters. A thin fabric has not sufficient depth to hold solids within it, whereas thick media will often hold back solids that penetrate the surface. Proof of this is furnished when the surface of a heavy twill or duck cloth will often be quite clean, while the cloth is almost impervious on account of particles lodged within the cloth.

When bag filters, gravity or suction filters, and filter presses were the only agencies at hand, strength of the fabric was the primal specification for all cloths. In bag filters, strength is required lest the weight of the liquor inside the bag burst it, and in tank filters unloading by shoveling out the cake requires a cloth of substantial strength. In filter presses the strength required is not so much due to the pressure of filtration as to the squeezing effect at the gasket joint between the abutting plates and frames. Too much emphasis has often been put upon this point. The absolute pressure on the cloth between the plates is not excessive save where the cloth is laid in a wrinkled condition and the pressure has to be increased to stop leakage at such places. To correct carelessness in laying the cloths, strong fabrics were required. For a time, manufacturers of this type of filter were too much engrossed in their schemes of drainage, washing methods, accuracy of machined surfaces, etc., and overlooked the cutting edge of the gasket surfaces. Only a strong cloth would not be cut through by those sharp edges. A rounded edge overcomes this and eliminates the breakage at this point.

Factors in Selection of Cloth.—It is obvious that the yarn used in the cloth is the determining factor in structural strength. It is also important that the cloth be dense enough to make a tight gasket joint when the press is made up. These factors have determined for the most part the specifications of the filter cloth used in filter presses.

Other factors, especially in our modern filters, affect the selection of the best filter medium. The filter cloth is fixed to the drainage member either as a sewn bag, or a wired sheet, or a clamped covering. This precludes quick changes. In consequence a cloth must have an economical life or the attendant expense of replacing the medium will make the entire filter operation excessively costly. Also, in modern filters the discharge of the cake should be without hand labor. This means automatic or semi-automatic discharging methods, the efficiency of which is largely dependent upon the filter cloth used.



Courtesy Turner, Eising Company
Deck or Square Wares

FIG. 19—Typical Filter Cloth.

Chain Wares.

Properties Affecting Discharge of Cake.

The discharge of the cake from the filter cloth can generally be accepted as a simple matter so long as the deposited cake is entirely on the surface of the cloth. Even with the most freely filtering liquors containing granular solids in suspension, some fine solids penetrate the surface and entrench in the interior of the cloth. Automatic means of discharge are practically worthless in cleaning the cloth from these solids. Such a condition is fatal to modern type filters, and in some industries where it is almost impossible to prevent solids penetrating the surface of the cloth, as, for instance, raw cane-sugar manufacture, plate and frame filters are still supreme. In these filters the cloth can be changed after each operation. Naturally if the cloth is open or so thin as to prevent the fine particles from collecting within the fabric, discharge of the cake from the surface cleans the cloth.

Smoothness of Surface.—Experience has proved, especially in the case of slaking discharge, that the surface of the cloth must be smooth for the best results. A duck weave has proved a better cloth than a twill weave of admittedly better porosity.

Porosity.—A new filter cloth held up against the light may show open pores, and yet become positively dense when wetted or in operation for a few runs. In this case the reverse current cannot permeate well and tends to belly out the cloth without lifting the cake away from the cloth. Some operators have had but little better success in discharging when trying out open cloths. A too porous cloth lets the reverse current through too readily, so that it discharges small patches of cake and lets the incoming air pass out through these openings without penetrating the rest of the surface. There is a definite porosity for any particular material being handled, and this can be determined definitely only by actual test.

Selection of Drainage Members.

There are means of protecting a cloth so as to increase its life, but none is more effective than adequate support in the drainage member. A screen of 5 mesh per inch or greater should have a protector for light cloths. This can be a lighter or finer mesh screen, or it is cheaper and easier to envelop the drainage member in an open weave burlap. The latter cushions the filter medium against the drainage member and in addition to increasing the life of the cloth it will often be found to add somewhat to its capacity.

Every filter cloth is affected by the kind of drainage under it. Efforts to give the maximum drainage have resulted in excessive drainage in some cases. The foreign presses used in the breweries for sweetening off the mash are examples. The drainage member here is made up of 0.125 in. by 1 in. steel flats spaced at 0.75 in. centers and set edgewise to the cloth. Only a heavy woven fabric can safely bridge these spaces even under a low

head of 5 lbs. per sq. in. This drainage member, requiring a heavy filter medium, unnecessarily complicates the operation of these filters. Albuminoidal material lodges in the cloths so that they must be removed after each run, whereas a thin weave could be cleaned *in situ*. If we take the flow from the outlet of a filter element even when the filtrate is flowing fast and distribute it across the entire area of the element, it is evident that the flow through a square inch is hardly faster than in drops at a time. So long as the space for the flow to the outlet does not set up an appreciable back pressure, it is sufficient. In an experiment made some years ago on a free-filtering calcium sulfate slurry, two leaves were connected to a common header and tested under the same suction pressure, with all operating factors maintained constant. One leaf had a drainage member made of wooden slats, the other, using the same-sized collecting frame, had one layer only of a thin burlap. The burlap leaf lagged at first, but in less than half an hour the cake on both leaves was the same. A large chemical plant recently discarded iron screen drainage members and substituted five layers of burlap and obtained a higher rate of flow. Naturally with a soft drainage of this nature thin cloths can be substituted for the old heavy cloths with marked success.

Requirements of a Filter Cloth.

We no longer give primal consideration to the rate of filtration for any cloths. With few exceptions the resistance of the depositing cake to the flow of filtrate is many times that of even dense cotton ducking, so that the initial resistance of the filter cloth is trivial in comparison. This is not true of paper pulp filtration, where only a small suction is employed and where the pulp is free-filtering. The filtering rate of the cloth will be found to be of moment only when its resistance increases with recurring operation due to poor cleaning of the previous loading.

Formerly the first consideration of a filter cloth was its clarifying properties. Today this is quite secondary. Most operators are realizing that the true filter medium is a layer or film of the solids which are being filtered out of the liquor. Of course, with this in mind, provision must be made for the cloudy filtrate obtained at the start of filtration. If extremely open weaves are eliminated, the amount of cloudy filtrate is not excessive for refiltration, and clear filtrate should be obtained shortly after starting up. When it is indispensable that only clear liquid be obtained, as in the case of cane sugar syrups in refineries, pre-coating the cloths with an inert, free-filtering solid automatically provides the filtering layer.

A novel and uncommon observance of a principle commonly known to all of us came to notice recently. Animal and vegetable fibers used in the manufacture of the ordinary filter fabric are absorbent. In a plate and frame installation handling a mildly caustic liquor the plant superintendent noticed that his cloth failed more quickly in the gasket portion than in the filtering area. The wash water penetrated through the filtering area but failed to wash out the soluble between the abutting gasket surfaces,

He made this part of the cloth non-absorbent by painting it with a tar base paint, thus materially increasing the life of the filter cloth with no noticeable expense.

Allowance for Shrinkage or Stretch.

The consideration of shrinkage and stretch of filter cloths is of vital importance. Every cotton yarn shrinks when wetted, and the amount varies, depending upon the physical constants of weaving, that is, the tension under which the cloth is woven, the density of the threads, and the number of intersections. Duck and chain cloths shrink much more than twill weaves. Stretch is the reverse of shrinkage and is due to mechanical pressure, usually that of reversed compressed air in discharging. Twill weaves give much more than any others and make trouble in pressure leaf filters especially. These points must be taken care of by the local user by providing extra material for liquors in which the cloth shrinks and by making up the leaves as tightly as possible where stretching is to be encountered.

Media for Corrosive Materials.

So far we have considered the material being filtered noncorrosive to the medium. Alkalies and acids are, of course, hard on vegetable and animal fiber. Some salts like aluminum sulfate have a contracting action, and unstable salts, such as some of the ammonium salts, give trouble. The degree of the deleterious effect depends upon the concentration of the liquor and the temperature. Actual test is the best means of determining whether a cotton, wool, metal, or stone medium is required.

For weak caustics like milk of lime, cotton can be used economically. But wherever cottons are used with even the weakest alkalies, precautions should always be taken that the caustic does not concentrate. Letting a filter stand several days so that the cloth becomes dry before the filter is again put into operation is manifestly poor practice, as the drying of the cloth concentrates such caustic as is present. When a press is standing idle, it is good practice to fill it with water or remove the cloths and submerge them. Wool is the poorest material to use on caustics of any strength. This should be remembered where a cake filtered from an acid liquid, in which wool is a very good medium, is washed with a caustic.

Strictly speaking, the world's best acid filter medium is silica, or other inert compounds as carbonium, aluminum, etc. Filros, a porous fused silica, is typical of this class of material. Mechanically these media do not lend themselves as well to the types of industrial filters most widely used. They are sometimes faulty on account of their lack of uniform porosity and the possibility of solids penetrating the surface, never to be removed.

Metallic Cloths.

Alkal filtration prior to the advent of metallic cloths was a troublesome if not an impractical process for industrial work. Metallic cloths

today are practical media capable of withstanding the action of the strongest caustic liquors, but there are principles to be observed if their application is to be economical or efficient. Most alkaline liquors carry materials in suspension, or in solution, that have a tendency to scale formation. When handling such materials it is almost always imperative that an open weave of cloth be used, for the scaling effect is rapid upon the filter medium due to the lower pressure on the outlet of the leaf, often sufficient to induce evaporation with the consequent scale deposit. Obviously, a closely woven or rolled cloth is rendered impenetrable quicker than a more open cloth. In closed delivery pressure filters, scale formation can



Courtesy United Metals Corporation

FIG. 20.—Sweetland's Patent Metallic Filter Cloth.

The pioneer in metallic filter cloth.

Courtesy Newark Wire Cloth Company

**FIG. 21.—Metallic Filter Cloth.
Double Dutch Weave.**

be lessened, and in some cases eliminated, by maintaining sufficient pressure on the outlet of the leaves. With hot liquors this pressure raises the boiling point at the surface of the medium and with supersaturated liquors crystallization is retarded, or eliminated, when the liquor is under pressure. The amount of back pressure required is variable with the material handled, but it will be often found sufficient when a standpipe is run to the floor above. Good design will make this a U-pipe, broken at its high point to prevent any siphon action, and returning the effluent within the observation of the operator. Such a back pressure must operate to decrease the flow, but the amount of decrease can be offset with a higher pump pressure. Too many times this decrease is exaggerated. This same argument arises where a suction is put upon the outlet of a pressure filter. In either case, the effective working pressure is the difference in pressure between that in the filter outside the leaves and that inside the leaves. Consequently, a back pressure simply subtracts from, a suction simply adds to, the effective pressure in pounds per square

inch and surely the simplest expedient to increase the working pressure is to increase the pumping pressure.

One of the factors of safety provided in the Sweetland weave is that any imperfection due to faulty workmanship can be reduced by rolling the cloth between heavy cylinders, thus closing up the imperfection. Much criticism has been leveled at this rolling, on account of the injury to the wires. If the metal is soft enough the rolling has only a small, if any, deleterious effect. If heavier wires of improperly annealed material are used it is quite evident that rolling is a poor expedient.

The improvements in twill weave instead of square weave, strength proportioned to the warp members, monel metal for iron, etc., are later-day improvements making the cloth a better medium. The wire cloth company who turned out the first commercial cloth later perfected a weave from the old Dutch cloth of commerce which has proved to offer some striking advantages. Much heavier wire can be used and the smooth finish of its surface as well as the evenness of its weave are some of its commanding features.

In some liquors the metal is slowly attacked so that its life is definite. For such work there can be no discussion as to the kind of metallic cloth to use. The wire of maximum cross-section is desired and the cloth using it should consequently be selected.

Cleaning of Filter Cloths.

The filter medium often becomes fouled as a result of incrustation, either from handling supersaturated solutions or from precipitation caused by lowering the pressure of the liquor. In order that the porosity shall be maintained sufficiently to obtain production, the cloth must be cleaned with an agent that will dissolve the incrustation. This is particularly true of metallic filter cloth used on caustic liquor containing calcium compounds as precipitates. The use of an acid, such as hydrochloric, to remove these incrustations is, of course, fraught with danger to the cloth. In most instances the incrustation is unnecessary. Calcium carbonate will often deposit because the liquor contains bicarbonate. If the temperature had been raised and held at the boiling point the bicarbonate would have broken down to normal carbonate. This is very evident in beet sugar manufacture. There is a safety provision for even these liquors as they are generally handled. In closed outlet filters all that is required is that there shall be a back pressure on the medium above the actual point of precipitation. In practice this back pressure can take the form of a pipe delivering the filtrate to an outlet some feet above the filter. In a magnesia plant the scale that formed on the vertical pipe required a change of a section of the pipe each week. This, however, was a great improvement on having the filter cloth plugged up with this deposit. Of course, this remedy is not applicable to suction filters. In this case pretreatment is the only outlet, and where this is not feasible a different type of machine is probably the solution for successful handling of this material.

Chapter VII.

Theory of Filter Application.

When consideration is given to the fundamental principles of filtration in designing the machine and in operating it, no other system is as simple, direct, and positive for clarification of liquors handled in the industries. When, however, the operation or design of the filter is faulty, then centrifugals, decantation methods, flotation schemes, etc., can be substituted and found more economical.

It is rare that work done in one operation by a filter can be duplicated by other methods without repeating the operation, or supplementing with the use of a filter. The scum from flotation machines is washed and dried in filters; the residues from decantation installations is de-watered in a filter; and it is common to complete the clarification of liquids having from continuous centrifugals through a clarifying filter. Such methods sever too much of "two bites at a cherry" and can scarcely be considered when the correct filters are installed and operated properly. One cause for the substitution of filters is found in faulty design. This is not serious when insufficient filter area or cubical caking capacity has been provided, for such troubles are overcome by additional machines. When, however, wrong types are employed, real difficulties arise. It is becoming better recognized that no one filter can satisfy all requirements and that some types are better for some specific duties. The following classification meets general conditions, although local considerations may require radical modification in it:

Types of Filters and Their Applications.

Plate and Frame Filter Presses.—Dry discharge; material requiring frequent filter cloth removal; acids, saline liquors in machines of wooden construction.

Vacuum Leaf Filter.—Acid filtration; open tank.

Pressure Leaf Filter.—Generally applicable to all materials, but less satisfactory on acid liquors and those containing too freely filtered solids.

Vacuum Continuous Filters.—Free-filtering liquors, not too hot.

Vacuum Dewaterer Hoppers and Rotating Sand Tables.—Crystalline or granular solids too fine for good centrifugation or corrosive to centrifugals.

INDUSTRIAL FILTRATION

Surmounting Difficulties of Vacuum Filters.—Some important filter installations have been made of intermittently operated type filters where, from the nature of the material, continuous type filters would seem to have been the better machines. In these cases the continuous filters were found lacking because of inability to deliver a positively brilliant filtrate and to hold their vacuum, due to excessive cracking of the cake when air dried. Both of these difficulties are surmountable, and continuous filters should have been used. To overcome the clarity objection the valve should have been constructed with another outlet which registers with the arc in which the filter cloth first dips into the liquor and the initial cake is formed. Here is the only opportunity for cloudy liquor, and the delivery into this outlet should be returned to be refiltered. For the second there is no good reason, with drum type filters at least, for blanking off the valve at the point where the cracks allow free air to pass through. In this way the capacity of the vacuum pump is maintained, for effective suction will be found well able to hold the required vacuum.

The matter of design does not end with the selection and construction of the filter best suited for the material in hand, but must include the layout of the machine in the plant. It is most important that the layout be made so that the operator can conveniently observe the operation and handle the valves.

When plate and frame or chamber filter presses were practically the only form of industrial filter, manufacturing conditions were easier than those prevailing today. Labor was plentiful, and less costly, maintenance costs were low and time could be taken to re-handle material than that would be prohibitive today. Naturally, when an invention like the Dorr Thickener came on the market, the savings effected thereby made it decidedly evident that the old-time filter presses should be discarded.

Decantation and Flotation Methods vs. Filters.

Dorr Thickeners found advantage not only because of their automatic features, which reduce labor and obviate filter cloth renewals, but also because their counter current system of washing removes the soluble from the solids and produces strong liquor of all water used for washing. This, of course, decreases the duty of the evaporators and, therefore, lessens the cost of concentration. Besides this, Dorr Thickeners can be made alkali- or acid-resistant, and, consequently, it is possible to use them on liquors corrosive to materials used in filter construction. In fundamental principle, filters would seem to surpass Dorr Thickeners, but in actual plant practice the results often favor Dorr apparatus.

Continuous decantation systems are highly economical methods for handling large volumes of liquors, the solids in which settle readily and leave a satisfactory clear supernatant liquor. Their low labor and operating costs as well as their automatic operation are distinct advantages. They are especially applicable for the handling of calcium sulphate thrown down from phosphoric, oxalic, citric and similar acids, for they are easily constructed acid proof to these materials and effect results seldom

approached by filters working on the same liquor. By using weak liquor washes on the successive settlings so that the settlings progress from strong to weak liquors with a final mixing with fresh water, while the supernatant liquors advance from weak to strong liquors, all water entering the system leaves it as strong liquor and the settlings are discharged from the system low in soluble content. The final settlings can then be handled on a continuous type filter, if desired. The large area required for such an installation is prohibitive in some plants, but it will often pay to construct a new department for an installation.

Flotation methods of separation are effective in clarifying liquors, the solids of which are capable of being propelled upward by bombardment of the fine air bubbles ascending through the liquor. In handling greases, gums, fats, etc., this method of separation has much to commend itself, for such materials are difficult to filter and do not settle or float readily.

The advance of Dorr Thickeners, etc., into industrial application, even in the face of modern type filters, is due largely to faulty filter work rather than to inherent advantage in Dorr machines. The Dorr is simply a wonderfully clever scheme for maintaining a constant settling depth for decantation and the collection of the solids in a greatly thickened condition. The work of clarification is due to gravity, as in any decantation process, and the time element and area required are always vulnerable points where filtration should excel.

Filter Defects.

The defects of modern filters are surmountable. These difficulties are briefly summed up as difficulties with:

1. alkali or acid resistant materials of construction
2. cake discharge troubles, due to—
 - a. cake building
 - b. cake removal.

Remedies for these difficulties are discussed in the chapter on "Plant Practice."

Much of this trouble is not found in continuous filters. Here agitation is much simpler and changes in cake thickness make relatively much less difference in operation. The drawback to the conventional continuous filter has been its inability to discharge cakes that are thinner than $\frac{3}{4}$ in. thick. Thin cakes are hardly affected by reverse current of compressed air, and the work of discharge is almost wholly that of the scraper. Such use of the scraper is poor design, for it is too easy for the scraper to smear a thin cake into the cloth. The scraper should properly be a deflector for the cake, not a cleaver of the cake from the cloth.

Continuous Filters Made Universally Applicable.

The use of the scraper in discharging cakes from continuous filters has limited applications of these filters to those materials in which cakes

INDUSTRIAL FILTRATION

greater than $\frac{3}{4}$ in. thick can be built up. Often the rotation of the drum has to be slowed down so that sufficient cake can be built. This lessens the effectiveness of continuous filters and narrows their field of application. If the cake is discharged by adhering to an enveloping cloth, as in the FElinc Filter, the thickness can be anything from $\frac{1}{2}$ of an inch up. There are few materials found in industrial work that will not build a $\frac{1}{2}$ in. cake in three minutes or less, including unthickened liquors, and, hence, it is not impossible that continuous filters may be made universally applicable.

Chapter VIII.

Auxiliary Equipment.

Faulty accessory equipment has too often caused unsatisfactory operation in filter installations. It must, therefore, be recognized as vital to good filter work and no discussion of filter operation can be thorough without attention to it. This chapter will, therefore, make some definite suggestions of outstanding importance and call the filter man's attention to the necessity of a study of his own auxiliaries in solving individual problems.

The auxiliary equipment used with industrial filters varies somewhat with the materials employed. In every case, however, piping, fittings, cocks or valves and pumps are required. For pressure filters the pump is a slurry feed pump and if compressed air is needed an air compressor is necessary. For slaking-dissolve pressure filters, a high pressure water supply is required and often has to be furnished by an auxiliary pump. In continuous filters a dry vacuum pump is always necessary, forgetting the few installations where wet vacuum pumps are applicable, and generally some exhaust pump to carry off the filtrate from the vacuum receivers. Often an additional circulating pump is required with a continuous filter.

The piping necessary for the carrying of the slurry should be oversize. The slurry best adaptable to filtration runs high in solids. Any restriction in the flow provides a fine element in which settling can take place. If the velocity of movement is not sufficient to remove the settled material the pipe area is reduced. Again, extraneous precipitates are common industrial materials. These have a pronounced tendency to scale on metallic surfaces. This scaling likewise reduces the pipe area. As this condition is inherent in the materials being handled it is obvious that all piping of the slurry should be as short as possible.

Corrosion of piping should be minimized by insulation of resistant material. With water liquors there is present some constituent which has either a catalytic or an electrolytic action. This creates an insidious corrosion which attacks the pipe threads more violently than any other point. In steel cases flange connections should be sulfitedubed for threaded fittings and the flange fittings made up in a pipe threading machine where the fitting can be tightened more securely than at the filter.

Fittings on slurry lines should never be so installed that the pipe cannot easily be inspected and cleaned. Elbows and tees should be substituted by crosses and plugs. Accessibility to a pipe line is a safety

INDUSTRIAL FILTRATION

precaution against pipes plugging up. Long sweep fittings are better than abrupt right angle turns. Erosion is less and friction loss decreased. Unions should be installed plentifully. A change in the layout is always simpler if a line can be conveniently broken without tearing down a




Fig. 22.—Marco Valve—Lubricated Plug Cock.

All the advantages of quick opening, direct passage, etc., of the familiar plug cock have been preserved, and by means of the lubricated plug, the valve is also non-sticking and non-leaking.

long length. Replacement of a defective or a completely blocked line is facilitated if unions are disturbed frequently.

Valves and cocks undergo heavy duty in filter work: gritty material rests on the seats, corrosion freezes the cocks and stuffing boxes on the handles are hard to keep tight. Broadly speaking, a quick opening valve is the ideal valve for filter slurries. Globe valves should be confined to gas

work only, i.e., for compressed air and steam lines. Gate valves are superior to the ordinary plug cock but the leakless, non-sticking, Merrill-Nordstrum cock is probably the best shut-off cock for filter slurries. The lubrication used in this cock is now supplied so as to be applicable to caustics, acids, hot or cold liquors. For acid liquors requiring lead valves, the Coco disc valve is undoubtedly the best. Here is a valve with an easily replaceable seat so that a tight cock can be maintained.

Slurry circulating or feed pumps were a matter of local choice of either a ball valve reciprocating pump of plunger or horizontal type and a centrifugal pump. The pulsations and high heads of the former were considered as against the wear on impeller and leakage at stuffing box of



Courtesy The Chemical Equipment Company

FIG. 53.—Coco Valve.

Can be constructed of lead for acid work. The fine contact on closing between cone and rim of hole in disc seat insures positive cut off. The unique design permits quick and easy renewal of seating disc.

the latter. The characteristics of a centrifugal pump are in its favor, as the demand for a feed pump is large initial volume with slowly increasing pressure, and for a circulating pump for large volumes at low heads. Therefore, when the LaBoor centrifugal-eductor pump came out the ideal filter press and circulating pump was found. In the LaBoor type "L" pump the large clearances, the open impeller and the non-leaking stuffing box answer the drawbacks prevailing in the ordinary centrifugal pump. There is an added advantage seldom realized in this pump, namely, that more than half of the throw of the pump is educted directly from the center of the pump. This means that the churning action of the impeller in breaking up flocculent precipitates is minimized and another disadvantage of the conventional centrifugal pump is overcome.

In sluicing discharge the high pressure water is wanted in large volumes for a short period. The cleaning action is more by reason of the eroding force of the water jets than by washing off by clean water. In consequence it is good practice to run the sluicings into a settling tank and

INDUSTRIAL FILTRATION.

re-use the supernatant for sluicing water supply. Nicely designed centrifugal pumps of close clearance, often of multiple stage, are the most convenient for this work. An adequate strainer is, however, necessary to catch any material likely to scour the pump.

The dry vacuum pump in continuous filters should be oversize. There is never any serious regret from having too high a vacuum pressure, while there is a serious loss if too low pressure is obtained. The vacuum pump displacement will vary with the size of the filter and the readiness with which cake cracking occurs when dewatering the solids. On clays a




Courtesy The LaBoar Company

FIG. 54.—LaBoar Centrifugal-Eductor Pump.

The open impeller, large clearances ($\frac{3}{16}$ of an inch being the minimum), the eductor principle, whereby $\frac{1}{2}$ of the throw of the pump is discharged without traversing the periphery of the pump, together with the high heads and good efficiency combine to make this an excellent slurry pump. It can be built of lead, aluminum, bronze, etc., as well as of cast iron, giving it a wide application.


fraction of one cubic foot of free air per square foot of filter surface is sufficient to maintain vacuum pressures in excess of twenty inches of mercury, while on starch, magnesia and other free cracking products 6 to 10 cubic feet per square foot are necessary to hold the same pressure. The caution against carrying over vapors that will condense in the vacuum pump, sweeping out the lubrication and even endangering the cylinder head, are pretty well observed. Condensers or coolers are advisable in order to precipitate and catch steam or other condensable volatiles before entering the pump.

Wet vacuum pumps of the Nash Hytor design are the most practical to handle both liquid and air. The liquid must fall to a lower level than the pump, but otherwise this pump operates efficiently so long as high vacuum pressures are not necessary.



Courtesy The Nash Engineering Company

FIG. 24.—Nash Hytor—Wet or Dry Vacuum Pump.
Evacuation and compression of surging liquid will handle gas or liquid with facility. The liquid discharged from pump cannot be raised without auxiliary



Courtesy The Nash Engineering Company

FIG. 25.—Nash Hytor—Wet or Dry Vacuum Pump.
Using only one rotating part at relatively low speeds, together with large areas, makes this machine unique for the work accomplished.

The dry vacuum system is generally used instead of wet vacuum pumps by reason of the fact that the air volume far exceeds the liquid volume. It is more economical, therefore, to install the dry vacuum pump with its higher efficiency and to classify the filtrate and air in vacuum receivers. There remains the problem of exhausting the filtrate from these tanks.



Courtesy The LaBour Company

FIG. 27.—LaBour Self-Priming Pump.

To a standard LaBour pump a specially designed separating chamber is attached to the discharge throat. The self-priming feature allows this pump to pass air through the pump so that in addition to its use for exhausting sumps, pumping over the top of closed bottom tanks, unloading tank cars, etc., it is capable of exhausting filtrate from vacuum receivers without a check valve or an equalizing line, irrespective of the amount of vacuum.

Barometric legs or piping which extends below the tanks for a distance greater than the suction lift of the vacuum pressure obtainable offer the simplest means of draining the filtrate from the receivers. Foot valves to seal the boot of the barometric legs are not as reliable as sealing wells. The latter are simple containers, or barrels, holding a volume of liquid in excess of the critical contents of the piping from the boot to the receiver. Whenever the elevation is insufficient to install a barometric leg, pumps must exhaust the filtrate. Centrifugal pumps are best adapted for this work but must be installed properly.

First, the receiving tank must be located above the pump so that the filtrate drains freely into the pump. Second, when using a pump that is not of itself self-priming, a check valve should be located on the discharge line at its highest point. If this check valve is located near the pump and a head of liquor rests upon it, air can trap in the pump and discharge line below the valve so that in effect a pump must compress the air to a sufficient pressure to open the check. With these pumps it is necessary to install also an equalizing line. The latter has for its function the elimination of air binding in the pump and can be located from either the suction or discharge side of the pump back to a high point on the receiver. The LaLabour self-priming centrifugal pump, model "PL," is a radical advance in exhaust pumps for draining filtrates from vacuum receivers. This pump is non-air binding and being self-priming it does not require a check valve nor an equalizing line. It must, however, be located below the receiving tank and be of a capacity in excess of the filtrate flow. With this pump the receiver can be very much smaller, as it is continuously maintained free of filtrate, the pump acting as a small dry vacuum pump helping out the main pump. The performance of these pumps proves that all difficulties in exhausting filtrates are no longer necessary.

When a filter is used both to clarify a liquor and to wash the cake, the main filtrate must be kept separate from the washed filtrate. If the filtering cycle is carried on at one vacuum pressure and the washing and dewatering cycle at another, separate receiving tanks must be used for the filtrate in either case. Using a stabilizing valve to control the vacuum on the low pressure side obviates the need of using two vacuum pumps. If the two filtrates are not required to be separated, but a high and a low pressure is necessary, a stabilizing valve that will work on liquid as well as on air can be used and installed in the low pressure piping.


The auxiliaries to industrial filters are the mechanical means of controlling those factors in the plant which are so easily fixed in the laboratory.

The subject of auxiliaries can be discussed here only suggestively, but, as practical success of many installations has failed because of improper accessory equipment, the value of this chapter lies less in its suggestions than in its insistence on this fact: *auxiliary equipment is of such vital importance that it is a bad mistake to regard it as a matter of mere minor emphasis.*



PART II.

MECHANICS OF FILTRATION.



Chapter I.

Theory and Mechanics as Related to Practice.

When we speak of *industrial filtration* we have in mind its distinction from *municipal water filtration*, *boiler feed water filtration*, etc. It is not that the clarification required is different, nor that the work of clarifying differs, but in industrial work the percentage of solids suspended per gallon of liquid is relatively so excessive as compared with that in water filtration, that the problem of *handling solids* is the essence of all mechanical devices developed for industrial use.

The progress made in industrial filtration is best told by a strict adherence to the chronological development of filtering machines with a description of the mechanics of each. In this way the growth is seen to be rational and ever with one goal,—a more efficient machine. In filtration, progress has been most rapid within the space of two decades, and is still going on. Some of the machines discussed in the following chapters, while now in everyday operation and doing excellent work, are nevertheless fast becoming obsolescent because even while they operate well, better machines are taking their place. Though they are passing, knowledge of their development, construction and applications has value. Any one endeavoring to cover the subject of industrial filtration either as an operator or as a student will learn from them tricks of the trade that may have application in some particular problem which he may meet, or he may be guided from falling into practices that have been found inadequate in the past. Thus, their historical value may be discounted in favor of their practical value even when obsolete. Knowledge of the mechanics of all filters developed for industrial work enables one to make a nicely in choice of new machines to be installed. Understanding of the fundamentals governing the design in each machine often enables one to better the operation of existing machines.

Patentable and unpatentable features will here be discussed with no reference to the points of letters patent, information regarding which is set forth in the catalogues of the manufacturers, since this aspect is not the subject of discussion here where our interest lies rather in their academic and operative values. Likewise, no effort shall be made to describe other than the distinctive features of each machine, since detailed information is never up-to-date save through current circulars issued from the manufacturers.

In previous chapters we have focused upon the importance of the Theory of Filtration,—giving weight to the value of conditioning the

INDUSTRIAL FILTRATION

material to be filtered; the importance of controlling the factors of temperature, density, pressure, etc.,—emphasizing this more than we have the type of machine employed. And rightly so, for, given the best filter ever made but fail to control these factors and the results are miserable, while any old machine will give good results if these vital factors are well taken care of. No one is familiar with filtration who is not well advised on both the Theory of Filtration and its Mechanics. The foregoing chapters have outlined the theory. The following chapters are subdivisions of the general topic,—Mechanics. For the convenience of the reader, attention is called to the fact that each of these next chapters follows the same form so that comparisons and references may be readily made by turning to parallel paragraphs and corresponding sections in each. This chapter outline is as follows:

1. History and development of particular filter.
2. Its design.
3. Operation (cake building; washing; drying; discharging).
4. Layout.
5. Advantages.
6. Drawbacks.
7. Applications.
8. Summary of its Characteristics that led to Development of next machine.

Chapter II.

Bag Filters.

Undoubtedly the oldest and certainly the simplest of all filters is the Bag Filter. Its principle of operation is familiar to a who has been in his mother's kitchen at jelly-making time. There seen a cheese cloth or muslin bag serving as the filter, or strainer which the pulp is poured, while the clear juice is strained out the cloth leaving the solids behind, in the bag. This is an example using the filtering terms: "internal filtration" or "filtration from side out," because the liquid penetrates from the inside of the bag outside while the solids remain on the inside. To clean this filter it is turned inside out when the solids are easily removed. This is small scale, exactly the bag filter of industrial use.

While bag filters are interesting historically and as household pertinences, it must also be remembered that there are still numbers them in everyday commercial operation in large industrial plants. refineries still have some, and until a few years ago every refinery filtered sugar juices through these simple filters. Sugar technologists for many years tried to get more economic devices, but the filtering characteristics of sugar liquors resisted the application of more modern. In clarifying sugar liquors it is standard practice to aid filtration agglomerating the solids of suspension by means of a flocculent precipitate. This precipitate will not hold its form under heavy pressure and quantity a bag filter with its low operating head does the work with a portable efficiency.

Design.—Industrial bag filters are necessarily somewhat more complex than the home-made household affairs. Added filter area per obtained by folding lengthwise wide bags into open mesh enveloping. The open ends of the bag and envelope are attached to a special fitting known as a "bottle." The latter has a coarse thread at the truding end so that the assembled bag can be screwed to a receiver in the bag filter cover. This is simply a heavy cast-iron pan with a number of holes (256 in standard refinery filters), the under side carrying receiving fittings. The filter cover rests on supports, generally cast plates enclosing the bags so as to retain the heat. The filtrate, from the bag, drains to a low point on the floor and is delivered separate piping to a liquor gallery. The latter is in reality an observation station where an experienced hand periodically tests the clarity from individual filters by means of a small sampling glass on a wooden

He is responsible for the clarity and is in close communication with the filter operator.

Operation.—Every filter, when first started up, delivers cloudy filtrate. This may be due to the porosity of the cloth being too open, or it may be due to faulty binding of the cloth to the bottles, or to the bottles not being screwed up tight, or, perhaps, to faulty coagulation. In consequence, the filtrate man at the liquor gallery admits all the filtrate to a re-filtration tank until the clarity becomes satisfactory. By experience it can be judged when a filter should clear up but the time will vary with



Courtesy Warner Paper Refining Company

FIG. 28.—Sugar Refinery—Bag Filter Station.

In outer appearance the bag filters are a series of closed chambers abutting one another with large doors through which the operators are enabled to take out bags needing discharging and to replace cleaned bags. One set of filters are located at one side of the room facing a second set at the opposite side. The filters are fed from tanks overhead through feed troughs which extend along the row of filters, one for each set.

the quality of sugar handled. When a filter takes decidedly longer than expected to clear up, the filter operator is signaled to find the defect on the new filter. Here again experience on the part of the operator is necessary, for the defective bag is picked out by noting the greater flow of the unclarified liquor through one or more holes in the cover. Wooden tapered plugs are driven into these holes to shut off the particular bags that are leaking. The liquor gallery man continues inspecting filtrate at stated intervals from a filter even after it has been running clear filtrate and its delivery switched to the clear liquor reservoirs. This is necessary for under the load of the heavy sugar liquors the wrapping of the filter cloth to the bottles may slip and finally give way so that it allows muddy liquor to pass through. Also, the internal pressure on a bag will often open up a weak point and cause it to leak. Promptly, upon advice from

the liquor gallery man, the filter feed man shuts off the defective bag as explained before.

The working force in bag filtration is obviously gravity and it is a variable according to the head of liquor in the bags. Naturally, at no time can this be great without entailing an excessively strong filter medium. A thin fabric will not stand either the bursting force of the weight of the liquor or the wear and tear of repeated cleaning. A strong yarn twill weave is the popular fabric for this work. The enveloping bag is an open mesh weave of hose duck or an open netting variety, and must



Courtesy Warner Sugar Refining Company

FIG. 29.—Liquor Gallery—In Sugar Refinery.

All filtrate from all the filters is piped to one central station—the liquor gallery—where the operators periodically test the liquor for clarity and report to the filter station any change occurring in the quality of flow from any filter.

have, for its first essential, great strength. A fine mesh fish-net makes an ideal envelope.

When first starting up a new filter the material to be filtered is fed upon the top of the filter cover and drained into the individual bags. Naturally, it takes some time before a filter is full, for as the head in the bags develops, filtrate is obtained, the total flow of which acts as a leakage of the incoming liquor. As the deposit accumulates in the bags, the flow decreases, and after the bags are full the operator must adjust the amount of incoming liquor so as not to overflow the filter and lose material.

Filtration continues until the flow is small. Filtration time (measuring the time of actual delivery of filtrate) varies with the material in hand, but in sugar refineries it will average 30 hours. It is understood that the flow per square foot of filter surface per hour is very small, but the tremendous area (7,500 sq. ft. in a filter of 250 bottles) enables

the plant to handle big tonnages. This size filter will handle 50,000 gallons of sugar syrup in 30 hours filtration time. This is the equivalent of 25,000 gallons in 24 hours including time out for cleaning, washing and relaying the filter. This represents the clarification of about 150,000 lbs. of sugar per day. From this an idea is obtained of the capacity of one of these machines.

After filtration there are several different methods of operation. In one, the liquor is allowed to drain until the bag is nearly empty. In another, filters drain for an hour or so; and in still another, the "sweetening off" process starts immediately.

Washing.—"Sweetening off," or washing, the sugar out of the mud in the bag is done by diluting the bag's contents with hot water and



Courtesy: Farnam Sugar Refining Company

FIG. 30.—Bag Filters—Door Open.

The bags are suspended from ceiling attachments—bottles—on close centers so that for a given floor space a tremendous filter area is obtained.

filtering this weakened syrup out of the bag. The hot water is applied from perforated pipes which are inserted into the bag and extend to the bottom. This is known as "sticking the bags" and is a very trying job.

Discharging.—After the bags have been sweetened off and drained practically dry, progressive refiners open up the filters and blow cool air through the bags. As soon as the filter cloth is cool enough to handle, each bag with its bottle is unscrewed from the filter cover and taken over to the washers. The bottle is untied from the bag and the enveloping bag withdrawn. The main bag is then thrown into the first of a series of tub washes. The operator at this station, by clever manipulation, turns the bag inside out, and after slight rinsing passes it through power-driven wringers into a second tub. The operator here rinses the bag and feeds it through another power wringer to another tub. Some refineries have 4 of these tubs in series,—others, less, but there is usually fresh water supplied to the last of the tubs and a constant overflow from it to each lower tub, so that in the tub of muddiest water there is a constant over-

flow into a scum-receiving tank. This mud is handled in a filter press and such sugar as present is required.

Re-laying.—The washed cloths are then ready for re-fitting in the filters. The first step of folding the bags is done by manual labor, highly skilled in the deft handling of these unwieldy, heavy, wet bags. The open end of the folded bag is then ready for the bottle which is inserted and the cloth tied to it. The enveloping bag is next put on by means of an ingenious use of pneumatic tubes. These tubes (like the cash box tubes in department stores) first suck up the bag. Then the laborer holds the envelope around the mouth of the tube and by throwing a lever-handled valve, drops the bag into its envelope. This envelope is then tied around the bottle and the whole unit is ready to be inserted into the filter.

Advantage and Application of Bag Filters.

The dominant advantage of the bag filter lies in the low pressures used as the filtering force, thus enabling flocculent precipitates to be handled within their critical pressure limits.

Bag filters are still in use, but their operating cost is excessive in comparison with more modern types. Their use signifies inability to better time-worn methods and they stand as a challenge to American ingenuity. They are fast going out of date, and prediction is made that within a very few years they will be history only.

Bag filters are rightly industrial filters by reason of the great tonnages they handle. They are effective means of getting large filter areas in small floor spaces, but they entail much hand labor and their operation was extensive only when labor was cheap. They are not economical or efficient in light of present-day automatic devices, though they do get certain work done when other machines, so far, fail to handle it.

The obvious need for quicker and more efficient apparatus led to the development of the *filter press* which we will take up next.

Chapter III.

Plate and Frame Presses.

Plate and frame presses and recessed presses have been the standard industrial filters for more than a century. Their supremacy in American practice is now on the decline, but for "safety first" machines capable of handling any material under any condition they are not yet surpassed. Their interest is therefore more than historical for they are necessary machines with a big application throughout the chemical field.

Before the advent of plate and frame presses filtration required large floor areas and the filtering force limited to low pressures. The filter press is still an economizer of floor space and capable of withstanding higher pressures than any other type. In plate and frame presses the cakes are built on parallel vertical surfaces placed at $\frac{3}{4}$ in. to 2 in. centers so that the area for filtration is many times the area of the floor taken up by the machine. Pressures of 150 lbs. per sq. in. are often obtained in the presses extracting paraffin from petroleum distillate. Such pressures were unthought of in the filtering machines prior to the filter press and are not obtainable, with equal safety, in any of the modern filters.

If the features of large areas per unit floor space and high pressures for filtering force are the outstanding advantages of plate and frame presses today, it must be remembered that in light of previous practices these machines were labor savers, economical in filter cloth, and afforded a maximum accessibility.

Plate and frame presses enable many chemical processes to be established as commercial successes, probably none more striking than the dye industry, which would have been doubtful projects if bag or false bottom filters had been the only machines for clarifying the liquors. Every student of filtration must respect the progress in chemical manufacture due to the plate and frame press.


In comparison with modern filters there are some weaknesses but for dewatering cakes for subsequent drying plate and frame machines deliver the driest cakes. For small scale production, especially where the same machine is to be used for different materials, the plate and frames are still standard. This machine is worthy, then, of earnest endeavor to obtain and maintain highest possible filter efficiency with it.

Filter press has long been the name given to these machines, but they are rightfully pressure filters only and should not be confused with hydraulic or pneumatic presses where the force is way beyond that used in filter presses. Hereafter, plate and frame presses will be used to include recessed plate presses unless specifically designated otherwise.

Carter T. Shuster & Company

FIG. 31.—Plate and Frame Press.

The plate and frames in a storage section rest on the horizontal side arms and are clamped together by the clamping mechanism shown in open position on the right. In the plate with the corrugated drainage surfaces in the left foreground, the eye for feeding the liquor is on the left and the eye with port openings for the wash water on the right. The machined surfaces surrounding the drainage areas are necessarily machined surfaces forming the plates' surface by abutting similarly machined surfaces on the frames shown beside it.



Design.—It would be expected that with any machine so long the premier type of industrial filter that the modifications in design would be enormous. The variations range from simple, almost insignificant points to major features of closing mechanism, drainage, etc.

Fundamentally, the filter press, whether of the flush plate and frame or the recessed plate design, is a frame on which rests a series of loose plates covered with filter cloth so arranged that they may be clamped together to form a series of chambers the side walls of which are filter cloth. The calcining chamber is provided by the frame in the plate and frame type and by the depression of the drainage member from the rim forming one half of the space in the recessed plate type. The conventional practice of calling these machines frame and chamber presses, respectively is obviously a natural short cut.

In its elements every filter has a filter cloth, or medium, a drainage of the clarified liquor to an outlet and a space for the collection of the solid filtered out of the slurry fed under pressure to this space. Any study of design must cover these points. It is well, however, to have always in mind that in filter press operation the object is to obtain a uniform, even hard cake and with different materials these can be obtained with different designs.

The filter cloth functions both as a filter medium and as a gasket material. In practice the latter feature predominates and is the reason for heavy fabrics being required.

The drainage of the filtrate is by means of paths or channels in the corrugated or ribbed surfaces on the plates under the filter cloth. The outlet is a cast or bored opening to which a cock or plug is attached.

The calcining space is provided by the frame, which is in reality a spacer between the plates, in the plate and frame and by the depressed surfaces on the recessed plate type.

The method of feeding the liquor to be filtered into the separate chambers is probably one of the greatest variables in the design of these filters. In recessed plate machines a hole through each plate at the center, at a corner or any other position makes each chamber communicative with the adjoining chambers. In these cases the filter cloth is sewn together or clamped together through the opening. In plate and frame the feed channel is carried in the rim so that the filter cloth acts as a gasket for the connecting joints of the feed conduit as it does for the sealing of the calcining chamber.

The recessed plates or the alternate plates and frames rest, by side arms or lugs cast on each, upon the long side bars of the frame of the press. In order to seal the joints between the adjacent members of clamping arrangement or locking mechanism is provided. This mechanism pushes against the last plate, exerting a clamping pressure on each of the elements.

The frame of the machine terminates at one end in a stationary head which has its inner face corrugated to act as one side of the plate. To this head are connected the feed piping and other lines, such as wash water, steam, etc. The other end of the frame accommodates the closing device.

Inasmuch as 24 in. to 36 in. are required as the opening for cleaning the filter, or for replacing a frame or plate, the assembled plates and frames do not extend the full length of the machine. A closing bar, or piston, which transmits the pressure from the locking mechanism to the last plate, or movable head as it is generally known, closes up the distance from the assembled elements and closing device.

Elementarily, then, the filter press is a series of slabs covered with filter cloth and clamped together to form a tight container.

From an elementary construction we pass to a consideration of the present day design. This construction is based on the same fundamental principle of plate and frame operation, namely,—the formation of a good cake. Provision for washing the cake, better mechanics for drainage and delivery of filtrate, better machining of gasket surfaces, and better locking devices.

In order to obtain good hard cakes it is necessary to obtain as near as possible uniform cake building in the individual chambers. This is secured by a more generous design of inlet conduit and port areas and by a more exact determination of the width of the caking chamber for the material in hand. Plenty of opening area guards against a clogging of the feed passages so that the liquor enters the frames without obstructions cutting off the flow. By reducing the width of the frame for slow filtering slurries and by widening them for rapidly filtered materials uniform cake building with the minimum classification is obtained.

The necessity for good hard cakes of uniform density is appreciated on realizing the method of washing the cakes. In the diagram for washing filter press cakes there is depicted the formation of the cakes upon the filter surfaces of the plates. When starting filtration, independent cakes form on the surfaces. As filtration progresses the thickness of the independent cakes increases until adjacent cakes join together. When the cakes are even, so that the junction takes place simultaneously throughout the frames, conditions are correct for good washing.

Washing requires that an additional channel be provided in the design and construction of the press for the distribution of the wash water. This means that a conduit similar to the feed conduit shown in the diagram for washing cakes is provided, save that openings from it enter the even numbered plates. On operating the press, when filtration is completed, the operator closes the outlet cocks on the even numbered plates and turns on the wash water. The water then transverses the cloth on the plates and through the cakes as depicted by the arrows at "B" which represent the wash water stream line travel.

If the cakes are hard and even, the resistance to the flow of water is equal and the percolation of the wash constant throughout the press. Unequal resistance due to unevenly packed cakes, due to greater porosity of a part of a cake made up of settled coarse materials, or due to poor operation, such as failure to filter long enough to form solid cakes, etc., is sure to result in poorer washing. The latter must not be taken to mean that the soluble cannot be extracted but that it requires uneconomical amounts of wash water and time to obtain the result.

It will be noticed that the first travel of the wash water through every cake is counter current to the stream lines of the filtrate which deposited the cake. Any opportunity for movement of the particles comprising the cake surely means a new cake formation. It is physically impossible to have this movement uniform throughout the entire press, so unequal paths for the passage of the wash water result and the paths of least resistance are quickest washed.




FIG. 3a.—Alternate Plate Washing—Plate and Frame Press.

Filtration progresses by depositing a cake on the filter cloths that line each frame, continuing to build up until the two cakes meet in the center of each frame. When the press is full the sludge is turned off and every other plate outlet shut off. Wash water is fed through a washing conduit that distributes to each shut off plate. The pressure forces the water through the filter cloth on those plates, through the cake, and discharges from the open plate outlets.

Again, the wash water travels through a double cake, whereas the filtrate traveled through a single cake only. If there is any rearrangement of the particles of the cake there is bound to be a closer formation and a consequent reduction in volume. Any shrinkage in volume opens up a path for wash water of much lower resistance and a bad short circuit. The demand for a good hard cake of uniform resistance is, therefore, paramount in obtaining good washing of the cake.

Better determinations of the widths of frames is another step for the better production of good hard cakes. This requires simply that pre-

liminary knowledge be obtained of the filtrability of the material to be handled. If a cake one inch thick can be built up the frame can safely be made two inches thick. If a cake of only one-quarter inch can be built up the width of the frame here would best be a seven sixteenths inch. The reasoning here is quite obvious, as it is appreciated that in the latter case the resistance to the flow of liquid through the cake increases per increment of thickness much faster than in the former case.


Basing the width of frame upon the filtrability of the material is modified only by a consideration of the total cycle of operation. If the shortened time for good cake building and good washing is more than offset by increased work of cleansing the greater number of frames and the renewals on filter cloth, etc., a balance between the two must determine the width of frame.

The wide application of the filter press has resulted in cases where drainage of the filtrate has proven to be an important factor in the success of the press. The filtrate flow from the average industrial liquor is the accumulation of drops of filtrate issuing through the pores of the filter fabric. In order to carry away this flow any simple, corrugated, pyramidal or other channeled surface is generally sufficient. The design contemplates that the back pressure from the internal resistance is proportional to the amount of flow. Consequently, drainage of filtrate is seldom serious for the average liquor. When using the press as a clarifier handling relatively small quantities of solids and large quantities of liquors the internal friction assumes importance. In such cases the more direct the required path for the flow of the filtrate to the outlet, the better. Coincident with handling large volumes of filtrate comes consideration of port areas for its collecting from each plate. The accepted method of caring for this is multiple ports rather than one large opening. The drainage should be first designed for collection of filtrate and secondly for the physical strain on filter cloth. The points of support for the cloth must be rounded and on sufficiently close centers to insure against the cloth failing in bridging across to adjacent supports. The most successful drainage is obtained when the pyramidal or channeled surface is covered with a close mesh wire screen. The latter provides maximum support for the cloth and free passage for the filtrate into the channels. Protecting the edges of recessed plates to prevent a cutting action on the cloth is a similar improvement provided in a press of modern construction.

A filter press is designed to be a tight container when in closed position. It is as tight as the loosest joint. Consequently, a press will be made up with excessive pressures at some joints unless every gasket surface is accurately machined and the cloth laid without wrinkles or adhering cake. Machining far more accurate than that obtainable in a lathe, planer or shaper is obtained in the best produced presses now being manufactured. Accurately ground surfaces tested to within .003 of an inch is standard today. Such practice is reflected in the quicker closing of the filter, less strain on filter cloth, thus increasing its life, and the elimination of unequal strains through the locked press.

Improved locking devices are varied enough to be the subject of an

exhaustive study, inasmuch as closing the press is time-taking and arduous. Automatic or semi-automatic means have been the goal of a great many designers. Eastick's translation of Buhler's "Filters and Filter Presses" goes into this subject thoroughly. Let it suffice here to point out that a closed press should be locked. If the pressure on closing the plates is obtained by toggle design, or by big step reductions, the locking is automatic. If the pressure is by direct pneumatic or hydraulic



Courtesy T. Shewer & Company

FIG. 33.—Typical Head Locking Mechanism in Plate and Frame Press.

The movable head carries its own thrust block shown in horizontal position. When rotated to the right so that the projection centers with the threaded shaft the thrust block really becomes an extension of the movable head and reduces the necessary turning of the threaded shaft. Obviously as the shaft is threaded toward the press the locking force is exerted centrally and equally against the plates and frames. Numerous devices have been designed to effect the maximum leverage on the turning of the shaft, but the key to the design is the thrust block shown here.

pressure, additional locking is required. When locked, no damage can occur if the hydraulic pump shuts down without warning.

The standard filter press is open delivery type. This means that each plate delivers its filtrate into an open collecting trough or pan. Most machines have individual shut-off cocks of a quick closing design. Every open delivery washing press must have the shut-off cocks in order to carry out the washing operation. The cocks are indispensable when positive clarity is required or else one leaky cloth will nullify the work of the entire press. Plug cocks are simple and positive shut-offs and the small saving in first cost obtained by cutting off the cocks is poor economy.

Filter presses for corrosive liquids can be made of resistant metals if good castings, easily machined, can be made. The brittleness of high

silicon irons, the softness of hard lead and the excessive cost of illum prevent their use, but brass, bronze and aluminum are quite satisfactory. Happily, in most acid liquors encountered in filtration wood withstands the action fairly well.

Wooden plate and frame filter presses are the pivotal point in the manufacture of many materials including dyes. Their use insures freedom from metallic contamination and maintains color and purity of product. Wood presses are designed with less variety but with full adherence to the principles of operation.

Being weaker under compression strains than iron or other metals, wood presses are generally limited to a maximum working pressure seldom over forty pounds per square inch. Also, much greater thick-



Courtesy T. Shriver & Company

FIG. 34.—Wooden Plate and Frame Press.

For liquors corrosive to iron or cakes contaminated by iron rust, a wooden plate and frame press is particularly applicable. Mechanical strength is obtained by the proper selection of the wood used, by reinforcing tie rods, and by judiciously designing the thickness of both the plates and the frames. The greatest surfaces are usually greatly in excess of those required in metal presses.

nesses are required for width of plate or frame and wider surfaces are necessary to provide strength to carry washing conduits, etc. Rigidity is obtained by bracing with iron rods or exterior frames.

The biggest advance in wood presses has been in the drainage, for while the filtrate channeling by cutting grooves is all right while the press is new, it is a constant annoyance after being in service awhile as the pyramids soften, flatten out or break off. The simpler, cheaper and equally effective means is to fasten five layers of open hose duck or burlap to the plate. The openings in the successive layers of this material provide ample paths for the exit of the filtrate.

Many modifications of design have been devised, some for better washing and some for better discharge. Among the latter are the Merrill and Atkins-Shriver presses which are described under special filters.

To emulate pressure leaf filter washing has been the theme of those endeavoring to better filter press washing. The physical work of washing by displacement method is simple with plate and frame presses, but the attendant difficulties of poor drying effect, of difficulty of draining excess unfiltered liquor, and the greater difficulty of discharging the cake, nullify the advantage of the better washing obtained.

Operation.—Contrasting the operation of the plate and frame press with the industrial filters that preceded its introduction, we find it far less arduous work. Reflecting on the increase of production by means of the greater pressure, the vast area per unit floor space and the easier operation, it is natural that this machine was exceedingly popular.

Even today there are instances where its operating costs are less than those necessary with the more modern machines. Small capacity units, materials on which the cloths must be frequently changed or renewed, and for those materials on which the press is opened only at long intervals, are examples.

As is true of any other machine, if the filter press is operated correctly it is easy work and the team play possible when a crew of operators is required makes it interesting work.

Step number one is opening the ports and feed inlets. This is followed by laying the cloths. This, in the plate and frame type, is the simple folding of the cloth over the plates and centering the eyes over the conduit openings. In the recessed plate type one half of the cloth must be rolled up and fed through the feed eye. In either case it should be considered wilful negligence not to straighten out all the wrinkles or not to scrape off any adhering cake. A wrinkle or an obstruction is sure to be a point of leakage unless abnormal pressure is used in closing the press. The latter weakens the cloth at the wrinkle, so that in either case it is poor operation.

The press should be closed with as little pressure as possible. Straining on the closing device is significant of defective design or operation.

With the press closed, actual filtration can take place. With clean cloths it is generally the practice to open the feed valve and pay no attention to exhausting the air in the frames. The air leaks out through the cloth readily enough to let it escape that way.

Unless the pressure has to be regulated in excess of the regulation which occurs with the increase of pressure with decrease of flow, the operator needs but to make sure all plates are delivering clear liquor and then pass on to another press or job.

Filtration continues until the flow is practically stopped from all the plates. At this time the press is assumed full and all frames equally packed. If washing is desired the operator shuts off the feed line and every other outlet cock on the plates. The wash water is then admitted.


The limit of the washing cycle may be determined by sampling average filtrate, until density is down to a given minimum, by taking samples of filtrate from end of frames and stopping when they have reached the allotted minimum or by working on a time basis.

After washing, most plants dewater the cakes by compressed air or steam. To obviate the need of forcing the wash water in the washing plates through the cakes good operators open the cocks on these plates shutting them again when the air rushes out. Never should the plates be drained without the air line on, for the water can only release if replaced by air, and, if this is not provided purposely, it will be supplied

Courtesy T. Shatto & Company

FIG. 35.—Hydraulically Closed Plate and Frame Press.

A hydraulic cylinder is incorporated in standards of the press so that the piston is centered with the frame block. The counterweights serve to bring the platen back into the cylinder when pressure is released in cylinder and press is to be opened.



from the caking chamber and disturb the cake formation. Such a displacement is sure to be followed by a short circuit when drying.

Blowing the press to dewater the cake operates to deliver both a drier cake and one more positively washed. The less the moisture content of the discharged cake, the less the soluble in the cake. It is seldom practical to attempt to wash the cakes to a fraction of one per cent in a plate and frame press. It is more economical to drop the soluble content to 5 or 10 per cent soluble, depending upon the material in hand. By "washing" is meant the added effect of washing and blowing operations. The discharged cake should then be re-puddled with weak wash water or fresh water and re-filtered. This second filtration is generally a simple matter, especially as the slurry can be confined to one high in solid content. By the double operation the residual solid in the cakes can be economically attained as low as $\frac{1}{10}$ of 1 per cent.

Blowing the press with steam is questionable practice for the condensation of steam means water in the cake. High temperatures shorten the life of the filter cloth. These are drawbacks but the main difficulty of steaming the press is this—that the plates are too hot for comfortable handling.

After blowing the press the locking mechanism is released and the movable head brought back to its extreme position. The press is now ready for discharging.

If the cakes are to be dried, pans or trays are slipped under a frame containing the cake and by tipping a frame, jerking it, or otherwise dislodging the cake, it lands in the tray and then is placed on trucks for drying. In handling small machines, some operators prefer lifting the frame with cake out of the press and depositing the cake on a tray placed on a table or across wooden horses. In either case, the idea is to rack the cake in its compact form.

If the cake is a waste product a hopper is located below the press and the cakes dumped into it. In such installations a lattice work over the hopper is a safety protection to the men and to the scroll conveyor in the hopper.

After the last cake is dropped, the plates and frames are reassembled against the stationary head. Now is the time that the efficient operator will make sure that his feed openings are all clear and his cloth un wrinkled on the gasket surface.

The operation of plate and frame presses is thus seen to be cyclic. Handling the press one or two times is generally sufficient to enable the average workman to master the job. There is no simultaneous shutting off of one valve and opening another, there is no nicely of timing. Discharging the cakes takes place clearly before his eyes.

Layout.—The layout for a filter press is simple as compared with that necessary for more modern machines.

On setting up the press sufficient foundations are necessary. It is important that the side arms should be level. The reason for this lies in the fact that the closing device works at right angles to the face of the movable head. Each plate and frame as well as the movable head has a

normal position at right angles to the line of the closing pressure, that pressure will be distributed more evenly and result in quicker closing of the filter when the side arms are level.

Piping layout requires the three pressure lines, liquor, water and air brought to the stationary head and connected to their respective inlets with conveniently placed shut-off cocks. The filtrate trough, when using



Courtesy D. R. Sperry & Company

FIG. 31.—Characteristic Installation of Plate and Frame Press.

Accessibility to the filter cloth is a pronounced feature of plate and frame presses. Team work developed by the operators straightening and inspecting cloths is a simple job.

open delivery type machines, should be equipped with three outlets. One for cloudy filtrate, one for clear liquid and the other for wash water. Two cone plugs make the most convenient shut-off for such openings. It is also good practice to provide a hinged cover for the trough. Such a cover closes the trough when discharging the cake and prevents any spillage into the trough.

Closed outlet machines require more complicated layouts but the

installations of these in America are very special and in no sense standard practice.

Advantages.—The advantages of this type of filter were many when it was first introduced. At the present time its drawbacks weigh heavier than its advantages and its use is on a decline. It has, however, very positive advantages today and these merit consideration.

There is no industrial filter as simple as a plate and frame press. Its design and construction is so well standardized that it is familiar to practically every chemical operator. Its operation requires none of the idiosyncrasy incident to the operation of pressure leaf filters or to the setting of continuous filters. Operators can be broken in and become competent with far less effort than necessary with the improved type of machines.

Any material can be handled in a plate and frame press. There may be more economical means of handling certain liquors but the plate and frame press is a safety first machine whenever a new process is installed, or whenever there are wide variations in the filtrability of a product, the reasons for which are obscure. Any material will build up a cake if sufficient time is given for filtration and a good hard cake is the only essential necessary for filter press operation.

Plate and frame presses can be designed for any pressure. In such work as extracting paraffin wax from oil distillate pressures beyond the limit practical for modern filters are used.

Accessibility to the filter surface is an advantage in any filter. In plate and frame filter presses the ease of inspection of the filter cloth is greater than in any other machine. Also, in no other machine is the work of replacing the filter cloth quite as simple and easy.

The work of preparing the filter cloth for the filter press is the least complicated of all the filters. No sewing of cloth, no binding down of the cloth with wire, and no permanent clamping of it between adjacent elements. The cloth is purchased by the roll, lengths are cut off sufficient to surround the plate and eyes pinched in at the location of the feed, wash water, etc., conduits.

Acid Liquors are filtered in wood presses with less contamination, corrosion and annoyance than in any of our modern filters. For this work plate presses are still supreme.

Drawbacks.—When handling large tonnages the labor cost for operating plate and frame presses is excessive. There are installations of modern filters which have been substituted for a previous installation of plate and frame presses where two men per shift are doing the work of nine men formerly needed. A daily production maintained by six men formerly taking 27 men is representative of the increased productivity per man obtainable with modern filters.

The filter cloth on plate and frame presses must be selected for its mechanical strength as well as its filtrability. This requires heavier and therefore less desirable filter fabrics. Also, the mechanical wear shortens the life of the cloth in filter presses, making the filter cloth renewals excessive in comparison with those necessary with modern filters. In one large plant \$13,200.00 was the annual filter cloth expense with filter

presses as against a present cost of \$1,400.00. Costs differing like this are surely a drawback to filter presses.

Washing solubles from the cakes in filter presses is not a success. It is physically impractical to evenly and completely pack the chambers so that there are no short circuits. There always are paths of lesser resistance and the fact that more monetary savings have been effected by the better wash in modern filters than in any other saving made by them is proof that the washing method in plate and frame presses is poor. The principle of displacement wash is not practical in chamber presses and alternate plate wash is proven an inferior principle for washing.

The cycle of operations on chamber presses varies in proportion to the time necessary for cake building. If the cake deposition is slow it is necessary to continue at the slow rate until the press is full. This, therefore, means that there is lack of flexibility in this machine. This drawback becomes of vital importance when handling a product obtained from a crude ore, the gauge of which varies considerably.

Chemical plants are fast eliminating the stigma, so popularly fixed to them in the past, of being "dirty holes." The sloppy conditions so often prevailing around filter press stations has been corrected in numbers of plants by substituting non-leaking filters. Theoretically, such conditions should not obtain with plate press operation, practically, it does occur and only in the best operated stations is it reduced. Noisome conditions are proverbial with plate and frame installations and constitute a very valid drawback to their operation.

There are additional minor drawbacks which are pointed out in succeeding chapters. Specific mention of disadvantages is held to be good engineering for unless constructive criticism is constantly brought to bear, progress is arrested. Evidence of the value of such criticism is seen in the improvements in filter press design as developed by Merrill in his slushing filter and the Atkins Brothers in their Atkins-Shriver self-discharge press. These machines are discussed in a succeeding chapter headed—Special Filters.

Applications.—For materials requiring subsequent drying the low moisture content in the cake makes plate and frame presses the preferred machines. For color work, especially where the same filter is used for different materials, no machine is as convenient as the plate and frame press. Wooden presses are free from the metallic contact always found in any other type of filter and, therefore, for materials requiring absence of metals it is the best machine. For new process and for materials as extremely contrary as raw cane sugar liquors, the filter press is the safe and sure filter.

Summary.—The greatest epoch marker in filter history is the filter press. Advancing from box and bag filters to high pressure, large area filter presses was the greatest boon to industrial chemical manufacture ever experienced in filtration. No greater memorial is possible than the fact that the filter press remained supreme for over a century. It might still be the leader were it not that American standards of living require

INDUSTRIAL FILTRATION

cheaper processes of production and greater productivity of labor. Labor saving was then the initial incentive for filter improvement and was first obtained by George Moore in his vacuum leaf filter, the first of our modern filters. Moore's work is, therefore, the subject of our next chapter.



Chapter IV.

Suction Leaf Filters.

When the recovery of gold values received a big boom by the introduction of the cyanide process of dissolving the gold and silver present in ore, the mining industry as a whole was given an impetus such as has never been paralleled. All machinery involved in milling operations seemed to undergo a rapid transformation at that time to make them better. In the several processes necessary in the recovery of gold and silver from ore, filtration was the one that lagged most.

History.—At the time of the introduction of cyanidation of gold ores, plate and frame, or chamber, presses were the conventional machines for the filtering processes. The difficulties were that irrespective of the pressure employed, the solids were so slimy and fine that it took inordinately long to fill the frames with cake sufficient for anything approaching good washing results. In fact, filtration was "the neck of the bottle" in cyanidation, due to this trouble. Consequently when George Moore brought out his suction leaf filter, he opened up this throttle on the industry and made it the big success it has been for so many years.

George Moore, as a young graduate of Massachusetts Institute of Technology, went into the gold mining game via the assay chemist's laboratory. He climbed the ladder until he became superintendent of a mill which had started on high grade ore but soon had to handle a run of mine that assayed much lower. Soon after he took hold of the mill, the company went into receivership and the problem became acute,—could the mill be run at a profit on that quality of ore? As Moore saw it, the biggest costs and greatest losses were in extracting the gold values from the fines treated with cyanide. Moore scented a way out if he could build and handle thinner cakes. Instead of attempting any changes in his big Perrin plate and frame presses, he made a small square filter element with filter cloth on one side and an outlet pipe on the other. Putting suction on the plate and immersing it in a pail of alluvia, he got encouragement right from the start which led him to perfect his process and his machine. In inventing this machine, Moore proved himself no dreamer. He was an observer of the first magnitude, and he capitalized his observations by working out his new filter with simple mechanics.

Development of the Scheme.—Moore's filter experience had been with plate and frame presses and he noted in their operation that until the cakes in any frame had joined together they were individual and separate deposits. If they could be washed and discharged independently,


Cutting Natural Fibers Corporation

FIG. 37.—Moore Section Leaf Filter.

The simplicity of the design of this filter makes possible filters containing thousands of square feet of filter area. Multiple batches of large leaves carried on 1 beam and lifted by a crane make it convenient for one man to handle this tremendous filter area easily.

it would not be necessary to prolong the filtering cycle until the separate cakes did meet, but rather filtration could cease as the rate of flow became uneconomical. Again, being able to wash through one thickness of cake instead of two thicknesses would decrease the time for washing and in this way increase output.

Here, then, was his point of attack. He had in mind, also, bag filters in which the solids build up on the inside walls of the bag and are washed



SECTION ON $\frac{1}{2}$ OF FILTER.

Courtesy Industrial Filtration Corporation

Fig. 31.—Moore Stationary Leaf Type Filter—Better Known as Butters Filter.

Instead of moving the leaves from a liquor tank to a wash water tank and to a discharge hopper, the leaves remain stationary and the liquor is drained from the tank; wash water is pumped into the tank and, before discharging, is drained from the tank. The washed solids are shifted from the tank as a fluid mixture.

through one thickness of cake. If he could get away from the tremendous work of cleaning the bags, this would be the solution. How rational, therefore, to make the cake deposit on the outside of the bag instead of on the inside, so that a reverse current would disengage the cake from the filter medium and thus effect its discharge. He therefore enlarged on the laboratory Buchner funnel by applying suction power to the interior of the bags.

In brief, this summarizes the work of Moore that led to his originating the *suction leaf filter*. His discovery made practical the handling of ore slimes, the treatment of low grade ores, and the re-treatment of slimes piles, for the first time in history.

Launching a company for the exploitation of his patents was one exasperating trial after another. Intra-company dissensions marred what should have been one of the greatest propositions of the time. Over a period of years, the energies of the company were directed toward control of the company rather than the exploitation of the scheme, so that the Butters, Ltd., a consulting engineering concern of prominence, were quick to take advantage of a variation of the Moore idea.

The Butters Filter.—The filter known in the industries as the Butters Filter was devised by a Mr. Cassel who was at one time associated with Mr. Moore in the early development of the Moore filter. The Cassel patent was assigned to the Butters company and exploited by them under their own name. This machine, now obsolete because of its infringement of the Moore patents, was fundamentally identical with the Moore filter, but in operation the Moore filter leaves are transferable from the liquor to the wash waters, while the Butters leaves remained stationary and the liquor and wash waters were successively pumped into and drained from the one tank. This was the only difference between the two machines. In the Butters filter it was not feasible to obtain dry discharge, as the cakes fell off into the hopper bottom of the tank and were there puddled to a slurry and pumped to waste. It is indeed curious that one should put out a machine as original and new on the sole basis that, though identical with a patented machine in all other respects, its leaves were stationary instead of movable! The Butters filter was a cheaper machine to install, since its tank requirements were one instead of several and no crane was needed to transfer the leaves. It offered, however, the disadvantages of not being fool-proof so that instances occurred where valuable gold solutions were pumped to waste dumps; leaky valves enriched the wash solutions, and dry discharge was never practiced.

Aggressive exploitation of this machine, however, netted the expected results. Claiming infringement, Moore started litigation.


Importance of Court Decision in Moore vs. Butters.

Butters won out in the lower courts, but on appeal the Moore claim was upheld. On delivering this decision, the Court made a point which is of importance not only to filtration but to every inventor at large. It was defined that:

whenever a discovery is made of something already existing in everyday operation and put into new use whereby industry is benefited so as to increase its resources and output, that discoverer is entitled to patent protection.

This decision sets at rest any argument that equil-resistant cakes have always been and always are formed in plate and frame presses prior to the joining together of the cakes, and that therefore Moore made no invention. In his process, Moore was a *discoverer*, in the *mechanics of his machine*, Moore was an *inventor*, and his contribution to filtration will ever stand as monumental.

The claim which is the essence of the Moore process and on which the suit was won is: "The process of filtering slimes and the like consisting in immersing filter in a bath containing slimes and a fluid in which they are suspended, forcing said fluid through said filter by difference of pressure between opposite sides thereof, whereby slimes are deposited thereon in a layer of requisite character, removing said filter from said bath while maintaining a superior pressure on outside thereof, intro-



Courtesy Industrial Filtration Corporation

FIG. 30.—Moore Filter Leaf.

The design is founded on the prevention of the filter cloth collapsing so as to have free drainage when suction is applied to the leaf. Wooden sticks threaded into pockets between vertical rows of stitching provide ample drainage from many liquors. The frame is made of perforated pipe terminating in the outlet pipe. The top of the leaf is clamped between wooden bars which are attached to I beams from which each leaf is individually suspended.

ducing same into another bath and impoverishing the slimes by forcing another fluid therethrough as aforesaid, removing filter from said bath and subsequently cleaning it by air pressure applied to the back of said filter."

Design of the Suction Leaf Filter.

The principle of the Moore leaf design is that a bag of filtering medium shall envelop a drainage member having an outlet. The function of the drainage member is to prevent collapse of the bag and to provide channels for passage of the filtrate to the outlet. Collapse of the bag

tends to occur whenever there is a difference in pressure between the outside and inside of the bag, but is prevented by the drainage member which can be made of cocoa matting, or corrugated or grooved wooden slats, or of crimped wire screen, etc. Note, therefore, that the filter cloth has to be internally supported whether used for Moore's suction filter or for any of our present day pressure leaf filters.


In practice, the frame is rectangular and is made of fabricated and perforated pipe. The drainage member is either corrugated screen secured to the frame or formed by wooden slats slipped into pockets sewed in the bag. These pockets are formed of vertical rows of stitching spaced approximately two inches apart.

The suction leaf filter as used in mining plants and the chemical industry consists of a number of individual leaves hung from a frame to form a basket, successively immersed in a series of open tanks filled with the muddy liquor, weak liquor wash and wash water respectively. A manifold pipe connects each leaf with a common source of vacuum pressure or a source of compressed air which is used in discharging the cake. The filter leaves are spaced 4 or more inches apart, depending upon the cake thickness to be built up, and are made in sizes from 2 ft. x 3 ft. to 8 ft. x 10 ft., or greater. It is practical to design these filters with surface areas of 10,000 sq. ft. Each leaf is hung from I beams, or similar supporting frames, and is rigidly held in alignment. The outlet from each leaf may connect with one or two manifold pipes, the latter also being securely fixed to the frame. The connections from the manifold pipes to the filtrate receiving tanks must be flexible hose of a length to carry to the farthest tank. The vacuum is produced by a dry vacuum pump exhausting from receiving tanks and the filtrate is removed from them by means of a barometric leg, centrifugal or other types of pumps. Wet vacuum pumps, unless of the Nash Hytor design, do not have sufficient air capacity to make them practical for this work.

The leaves, source of suction, and the open tanks are the essential equipment for suction leaf filters; but convenient means of transporting the leaves from tank to tank is equally essential when handling large tonnages. Assuming a cake deposit of only 3 lbs. per sq. ft. of surface, a filter with 667 sq. ft. has a load of a ton of cake in excess of the weight of the leaves and frame. The weight of the latter varies, depending upon the construction, but the load to be handled will range from $\frac{1}{4}$ ton to 18 tons, so that the crane or hoist employed is a sturdy affair. The leaves must move up and down, as nearly vertically as possible, and with minimum swaying, or else cake will be dislodged. It is a simple matter to move a single leaf with cake so long as the suction pressure is maintained within the leaf. This pressure holds the cake to the filter cloth and prevents discharge of the cake, but in a large practical unit even though the suction pressure is correctly maintained the hazard of partial discharge of the cakes is greater, due to the greater load of cake, and the possibility of jarring the leaves when transporting them. For this reason the pick-up by the crane is always from a 4-point suspension with the length of chain gauged so that the crane pulls directly over the center of gravity. Sway-

ing is obviously dangerous for the reason pointed above, and abrupt stopping is equally bad, either in the vertical rise or in moving horizontally over one tank to the next position. Some of the crane manufacturers therefore developed special cranes for this purpose which proved quite efficient as long as the operator exercised reasonable care.

The tanks for these filters are rectangular with sloping or cone bottoms, and are best when provided with some means of agitation. This can either be by means of perforated pipes through which compressed



Courtesy Industrial Filtration Corporation

FIG. 40.—Experimental Moore Filter.

The application of a leaf filter can be determined by the results obtained with a single leaf, but the plant operation is best determined by a small machine complete with its crane, tanks, etc.

air is fed, so that the liquor is maintained at an even density by the uprising air bubbles, or a circulating pump can be used forcing the liquor in at the bottom and overflowing at the top, or vice versa.

One of the main essentials for operating efficiency is that the liquor level in the tanks shall never fall below the top of the leaves. If all the leaves are not fully submerged all of the time, cake thickness, and permeability of cake to wash water, will vary and consequently defeat the first principle of the Moore leaf design. Constant submersion is best obtained by constant liquor level. There is no simpler means of providing this than to have an overflow connection at the desired liquor level and always feed into the tank more than the filter leaves exhaust from the tank, so that there is some overflow all the time.

Operation.

The operation of suction leaf, and pressure leaf filters, is cyclic in nature, so that the operation works on a schedule of leaf transfer and valve manipulation. None of the work is laborious, and all of it is so simple that the operation of any one filter takes but a part of one man's time. The number of filters one operator can handle depends upon the length of the several cycles. For instance, if the filtration is $\frac{1}{2}$ hour only, the weak liquor wash 20 minutes; the water wash 15 minutes; and the discharge 12 minutes; the intervals of the latter operations are too short to warrant attempting to operate one more unit. If, on the other hand, filtration takes 2 hours; weak liquor wash 1 hour; water wash 45 minutes; and discharge 12 minutes, one operator can conveniently handle at least 3 units and not be overworked.

The initial operation is lowering the leaves into position in the filtering tank and filling the tank with muddy liquor. As soon as the operator turns on the vacuum connection, filtration commences. Preferably the operator should know in advance how long filtration should continue before starting the washing operation. This information may be gained by previous experiment or by data supplied by making previous experimental runs on the material in hand. If this information is lacking, the operator must watch the filtrate flow. This will constantly decrease in volume, unless the vacuum pressure is low at the start, due to the dry vacuum pump or centrifugal exhausting pump being too small to exhaust fast enough the volume of filtrate flow obtained at the start of filtration. In this case the vacuum pressure will rise while the flow remains constant until a maximum pressure is reached, when the flow will start to fall off. Noting the decrease in flow can serve only as a guide as to when washing should commence, for the prime consideration is that there shall be sufficient cake on the cloths to be easily discharged. Cakes $\frac{1}{4}$ in. thick are too thin for automatic discharge by reverse current, since the air will blow out through small patches and will not disengage the bulk of the cake from the filter leaves. A minimum cake thickness should be $\frac{1}{2}$ in. and even this is small with materials of low specific gravity. If the material in hand is relatively free-filtering so that cakes greater than $\frac{1}{2}$ in. can be built up, the operator can be guided by the filtrate flow. What constitutes the economical limit depends in a large degree upon the succeeding operation. If washing is not necessary the flow can drop off to a much lower limit than if the cakes must be washed, for then the flow must be great enough to get the wash liquor through in a reasonable time. In many applications the flow on washing increases due to the decreasing gravity of the entrained liquor in the voids of the cake. In consequence, the flow at the end of the filtration is a minimum flow for the entire cycle, and, with this in mind, the limit of filtration can be gauged accordingly.

Washing.

To change from filtration to washing is simply to transfer the leaves from the filtration tank to the wash liquor tank. This is wholly a matter

of operating the crane or hoist in order to lift the leaves out of the slurry and drop them into the wash tank. If this transfer is conveniently and quickly done, the vacuum supply is not changed but maintained at the limit reached by the end of the filtering cycle. If the transfer takes longer than 5 minutes it is best to reduce the vacuum pressure to a lower limit (10 to 15 in. mercury).


Washing continues until the filtrate reaches the desired specific gravity. If the first wash is a weak liquor, this point will be somewhat in excess of the specific gravity of this weak liquor and is determined in relation to the plant requirements. Where evaporation can be lessened by mixing the first strong wash filtrate with the original strong filtrate this limit will be higher than is the practice in mining work. Here the intermediate wash liquor is barren cyanide solution, this being the equivalent of a mother liquor in chemical plant operations and is the cyanide solution from which all the precious metals (gold and silver) have been extracted. The object of the barren solution wash is to regain the valuable gold and silver cyanides in the minimum dilution, and, by using barren cyanide solution, the strength of the cyanide is maintained. The succeeding wash with water is in order to recover the cyanide, the weakened strength of which is brought up by adding fresh material, or by concentration. The final wash filtrate should approach actual water and if the washing has been efficient the volume obtained should not be excessive.

Drying.

Washing the cakes is generally followed by drying them. The term "drying" is largely a misnomer as 35 per cent moisture is a low limit for dryness of cake obtained with this type of machine and "dewatering" would seem to be more explanatory. Even if the discharged cakes are to be mixed with water and pumped to waste dumps so that the moisture content is of no moment as such, it is of value to dewater since imperfect washing is bettered when the least moisture remains in the cakes.

Drying consists simply in raising the leaves out of the water tanks and pulling the atmospheric air through the deposited cakes. Depending upon the class of material in hand the cakes will become dry enough to become pitted with openings or honeycombed with cracks through which the air short circuits, decreasing the pressure at which the vacuum pump can handle the volume of the air. It is waste energy to continue drying after the vacuum pressure has dropped under 50 per cent of the limiting pressure maintained during the washing operation. The gain in decreased moisture content is slight and pumping the big volume of air through the dry vacuum pump takes power far out-balancing the moisture reduction. The drying operation will vary from 5 to 20 minutes depending upon the material and cake thickness. Leaves that drain from the bottom will exhaust more of the entrained filtrate than those that have the outlet at the top. Draining from the bottom is usually obtained by perforating the bottom pipe of the filter frame so that all of the filtrate is collected at the bottom and sucked up through the frame.

Fig. 41.—Ready for Discharging.
With each square inch of fiber cloth loaded with a cake of $\frac{1}{4}$ inch or more thickness, weighing two pounds per square foot, it is easy to understand that these machines can handle tons of solid per cycle.



Discharging.

The drying operation usually takes place while the leaves are in position over the discharge hopper. Consequently, to change from drying to discharging is simply a matter of shutting off the suction connection.

Discharging is effected by one of a number of methods: reverse current of compressed air; steam blow-back; by combining either of the above with hosing off the cake; or by submerging the leaves and then by using either of the above reverse currents or reverse current of water.

Reverse compressed air is most generally used. This is done by connecting the compressed air with the filtrate manifold, the air penetrating through the filter cloth on each leaf from the inside of the leaf. As the air pushes against the cake, it lifts the cake away from the surface of the cloth, so that gravity makes it fall. It is often necessary to turn on the compressed air alternately as tenacious cakes are seldom dislodged with one rush of air. Again, some parts of the cake will often hang up indefinitely and rather than prolong the time and waste of compressed air, a long paddle is used to disengage these. This brings hand labor into the operation and while not strenuous, is not strictly automatic discharge and takes time. Badly cracked cakes discharge less readily than un-cracked cakes and if the material being handled is at best difficult to disengage from the cloth, drying must be shortened to prevent cracking and leave as much mass weight to the cake as possible.

Steam is never used unless compressed air is ineffective and its use must be guarded lest its high temperature weaken the filter cloth. In either case, of steam or compressed air, the pressure must be limited so that the cloths will not burst and a safe pressure is under 10 lbs. per sq. in. Reverse water or reverse compressed air, while the leaves are submerged, is often effective in dislodging thin cakes, but this method will be seldom found in practice today as such materials should be handled in different machines.

Advantages.—The outstanding advantage of the suction leaf filter is the high washing efficiency obtainable by displacement wash, and while there are other advantages of note this is undoubtedly the factor on which most of its installations were made.

The most spectacular advantage is the reduction of labor necessary in the operation of these filters. Often one man can do the work of ten necessary in plate and frame filter presses and with less energy than is expended by any one of the ten.

An operating advantage making for high capacity and economy is the ability to shut off filtration as soon as the economical cake thickness has been reached, rather than having to continue filtration at a low rate of flow until the cake is compacted, as in plate and frame discharge.

An economical advantage lies in the fact that filter cloth is not subjected to mechanical injury and wear, by being used as the gasket between abutting plates and frames or in handling it and washing it in tumbling washing-machines, so that the life of the cloth is much lengthened over bag filters or plate and frame operation. This factor makes possible the




FIG. 42.—Layout of Moore Filter.

In addition to the tanks, cones, feed and drain lines, vacuum pump, receiver, and filters certain mechanisms are required.

use of thinner fabrics and means that there can be a choice of filter cloth for a particular material.

The piping layout and valve manipulation is a minimum with this type of filter, especially if the barometric leg is used for the removal of the filtrate from the receivers.

Suction leaf filters were, when first developed, the finest filter obtainable, but improvements in continuous filters and in pressure leaf filters have decreased their importance to a large extent. Today, suction leaf filters stand out as economical in the first cost whenever huge tonnages must be handled, since their construction is so simple as to allow large areas to be operated in one machine. Also, the simple construction makes it possible to protect these machines against acid attack. Whenever lead is the only permissible metal to be used, these filters are in a class by themselves. Many installations have been made wherein the collecting pipes are made of lead, or are lead-covered; the filtrate manifolds are lead and the receiving tanks lead-lined or wooden; the drainage member made of wooden slats and the filter cloth of wool or other acid-resisting material. In any other type of machine there are wearing parts or heavy castings requiring lead lining which have proved costly in maintenance.

The acid-proof suction leaf filter has only one filter competitor, i.e., the wooden plate and frame press, but where applicable the suction leaf filter is preferable.

Drawbacks.—One of the early disadvantages of this type of machine was the limitation of the filtering force, i.e., atmospheric pressure. At sea level this pressure can be utilized nearly to its maximum of 14.7 lbs. per sq. in. (or 30 in. of mercury). In higher altitudes there is a drop often amounting to as much as 25 per cent of that obtainable at sea level. These low pressures often require excessive filter area in comparison with machines capable of working at 50 to 60 lbs. per sq. in. Large areas mean large filter leaves which are cumbersome to handle and to re-cover.

Applications.—More of these machines have been installed in the mining industry than in any other. Ability to handle large tonnages per cycle made them especially adaptable to this work. With the advance of automatic and continuous decantation systems, by which the solids to be filtered are concentrated in smaller volumes of liquids, continuous filters have taken their place.

In chemical plants the tonnages to be treated per day are far less than in the mining field and here pressure leaf filters are preferred.

The acid-proofed filter is, however, a most practical unit for acid filtrations in which wool or other fabric can be used. It offers by far the best proposition wherever an exacting wash is required and automatic discharge is desirable.

Summary.—In summing up the development of filters as outlined thus far we see first: that the crudeness of the bag filters paved the way for the long reign of the filter presses (nearly 100 years); secondly: filter presses were almost entirely limited to products running up to a maximum of 100 tons a day. But, while the labor involved in their operation, the inefficient washing of cakes and high filter cloth consumption were draw-

backs, it was not until the introduction of cyanidation with its requirements of handling several hundreds of tons per day, as well as exact washing of the cakes, that there was felt a decided need for a better filter. This brought on, thirdly: the development of the suction leaf filter with its characteristic high washing efficiency and its advantage of low labor and small filter cloth maintenance cost. Weakness in handling hot liquors, and the limitation of atmospheric pressure as the maximum filtering force, predestined it to give way to the pressure leaf filter, which is next described.

Chapter V.

Pressure Leaf Filters.

Pressure leaf filters comprise a type of modern filter familiarly known as the "filter press." This is, however, a misnomer, since they do not do any pressing of the cake as is the practice in the hydraulic presses used to squeeze oils from seeds, like cotton or flax seed, or to squeeze juices from fruit as in the case of grape juice. They do not even press the cake by the compression of filtration as in the operation of plate and frame filter presses. They are simply filters in which the filtering force is greater than atmospheric pressure, supplied by pump, gravity head, etc., and in which the filtering elements are filter leaves in principle exactly like suction filter leaves. In lay language, the liquor is drawn or sucked through the leaf by vacuum in a suction leaf filter, and in a pressure leaf filter it is forced through by pump.

The three most prominent filters of the pressure type are:

The Kelly
The Sweetland
The Vallez.

The first two were developed at about the same time, although the Kelly first appeared on the market. The inventor of each of these machines was thoroughly familiar with the suction leaf filters and their operation and in each case was prompted by the same desire,—to increase the filtering force above that of atmospheric pressure,—pursuit of which led to the respective filters. The Vallez filter is a later development designed to overcome some disadvantages found with both of the others in beet sugar work.

While increased force of filtration dominated the reasons for developing pressure leaf filters, other reasons well demand their use. When handling liquors heated close to the boiling point at atmospheric pressure, suction filters are generally inapplicable, since under reduced pressure evaporation is induced and the vapor produced either adds a duty on the vacuum pump or must be condensed by condensers of the surface or jet type. Such auxiliaries complicate filter operation beyond practical limits. Again, when handling hot supersaturated liquors, pressures above atmospheric pressure are above the critical pressure at which crystallization or precipitation starts, but reduced pressures corresponding to 20 in. of mercury almost always induce rapid deposition of the crystals blocking up pipe lines, drainage members, etc. Consequently, in chemical plants

these pressure leaf filters are far more popular and numerous than suction leaf filters.

"Pressure leaf filter" is quite descriptive in itself of this type of machine. It is a filter in which leaves are encased in a container capable of withstanding internal pressure, the outlets of the leaves extending through the casing and open to atmospheric pressure. Filtration is obtained by feeding the muddy liquor into the shell or casing at a pressure in excess of atmospheric, when the filtrate drains out at atmospheric pressure.

There have been instances where the outlets did not drain to the atmosphere but were linked up to suction receivers. Such practice is time-worn as the only advantage gained was the additional filtering force obtained. This effect is more simply obtained by increasing the pressure of the pump. Where gravity feed pressure is inadequate, the only possible excuse for using suction is where the muddy liquor scour the pump and where clear filtrate is easily pumped. Such cases are too few for consideration.

The three prominent filters of this type vary only in mechanical construction, as each of them employs the same principles of operation as obtained in suction leaf filters. The mechanics employed in each are, however, ingenious in themselves, and differ widely from one another. They can be designated and differentiated quite positively by the design of leaf used in each case. The Kelly filter employs a rectangular movable leaf; the Sweetland, a circular, stationary leaf, and the Valox, a rotary circular leaf.

These will be discussed in succeeding chapters in order of their appearance on the market. Sufficient details of construction will be included to acquaint the reader thoroughly not only with the design of these machines but with the principles underlying the design. No attempt will be made to carry description to a point of discussion covering strength of material, choices of materials of construction to withstand corrosion, etc., information on which is specific for a particular material and best obtained from manufacturers' catalogues.

Chapter V.

Section I.—The Kelly Filter.

The Kelly filter was one of the early modern filters, and the first of the pressure leaf filters to come into the market. It is best described as a shell containing filter leaves locked in a closed pressure cylinder, one end of which unlocks and slides along from the cylinder carrying the filter leaves with it. The most distinctive features of the Kelly filter are that:

- (1) All the leaves are rectangular, and
- (2) parallel to each other and to the longitudinal axis of the cylinder, and
- (3) leaves are carried outside the machine before the cake is discharged from them.

History.—The Kelly Filter was invented and developed by David J. Kelly of Salt Lake City, Utah, and appeared first in 1907. Kelly had been associated with George Moore in his work with vacuum filters but was dissatisfied with the limitations of vacuum as the working pressure for filtration. He was most impressed with this shortcoming when working with a vacuum installation at a gold mine located at a high altitude where the maximum pressure developed was only 20 in. or 10 lbs. per sq. in. If he could encase the leaves in a container capable of withstanding internal pressure he could force the liquor through the filter cloth by pump pressure and work at 50 lbs. per sq. in. The ore he was working on at that time was particularly amenable to an increased filtering force and his early work resulted in the right encouragement to increase his enthusiasm to continue the work.

Development.—It is well to note that Kelly in his filter sought to, and did, maintain all the advantages of vacuum leaf filters, but with the increased capacity could eliminate the tremendous area necessary in the vacuum installations. In addition to the obvious advantages of greater filtering force, there is the ability to handle boiling hot liquors without providing for the condensation of large volumes of steam. These factors make Kelly's contribution to the advance of filtration truly prominent and entitled to just recognition. In his filter he sacrificed none of the advantages of leaf filtration, although accessibility to the filter leaves and ease of observation of cake building would seem to be somewhat lessened.

Design.—The starting point of the design of the Kelly filter is probably the filter leaf. These filter leaves do not differ in essential principle


from vacuum filter leaves employed in suction filters. Kelly did work some modifications in mechanical details and materials of construction, but these can be best dealt with later.

The outstanding point in the design of Kelly filters is the locking device. Any one starting in on a work as Kelly did, would naturally employ a cylindrical container to withstand internal pressure. The next point is one at which considerable difference would arise: how to open the cylinder in order to discharge the solids from the filter leaf? Notice that if the cylinder were placed vertically with a removable top head, such that the leaves could be drawn upward and out of the tank, double head room would be necessary and a travelling crane required, quite similar to that used in the Moore filter. If the cylinder were placed horizontally, with one end open, then the leaves must be carried on a supporting frame capable of rolling out from the shell. Friction plays a big part, for the leaves are loaded with the weight of deposited cake when the leaves are to be discharged, and this load, of course, increases the friction. In consequence, Kelly placed the cylinder on an incline so that gravity would assist in overcoming this frictional resistance.

Having thus defined the placing of the cylinder, at the same time Kelly defined that it would be open at one end only and the locking and unlocking of this is the interesting feature of his early work.

Locking Device.—In closing the head of the cylinder, hand swing bolts readily suggest themselves as the simplest means of locking the head to form a water-tight joint. The number required increases with increased diameter, and the labor required is likewise increased. Modern filters are, however, distinctly labor savers, and such hand labor, therefore, could not be permitted. One is struck with the genius and simplicity of the idea of adopting the mechanics, familiar to all of us in opening an umbrella, to supplant these swing bolts. Kelly's locking mechanism is therefore refined umbrella-opening. U-bolts are secured to the shell and are of such a length that when the radial arms on the movable head engage them they bind on an inclined surface until the head is secured to the shell. These radial arms are analogous to the spokes of an umbrella and are actuated by a revolvable shaft through a toggle arrangement, so that small pressure applied to the rotation of the shaft exerts a greatly magnified pressure on the radial arms. This scheme of closing has been maintained to the present day, and in the smaller units requires a simple turning of the lever handle shown at R in Fig. 43 through 180° to the position shown dotted. The shaft is clearly shown at right angles to the fixed central shaft carrying the radial locking arms and a bearing through which the revolvable shaft extends. The toggles are secured to the revolving shaft and the movement of the shaft through the toggles propels the locking arms along the central shaft. The outer ends of the arms rest on the rim of the movable head, and this inward motion propels the arms radially when they engage the U-bolts. The reverse operation brings the radial arms out of engagement with the U-bolts and unlocks the head. The lever handle operation is supplemented by either automatic hand head locker or air operated device, both of which operate through

sprockets and chains which are shown attached to the rigid cross member in Fig. 44. This member is shown as two pieces of flat iron expanded at the center so as to surround the central shaft. At the ends it is connected by two links to the carriage carrying the filter leaves. When the leaves are in their discharging position, these links are extended to lie in a straight line so that when the filter is to be closed the chains, pulling on the cross member through the links, push upon the carriage. When the filter is closed and ready for locking, the links have engaged lugs at the side of the shell and are thrown out of the straight line into a broken line position. A further pull on the cross member now acts on the ring



Courtesy United Filters Corporation

FIG. 43.—Kelly Filter—Layout Showing Filter in Locked Position.

Note that the lever R, which is the locking lever, needs but to be rotated 180° to the dotted position to fully unlock the filter preparatory to withdrawing the leaves to discharge the cake.

connected to the radial arms. As this ring moves toward the arms move outward. Obviously, this scheme of locking duplicates that which we have discussed in the hand-operated scheme.

When operating the twin unit the variation from this is simply that a long steel flat is substituted for part of the chain and slots are provided in it so that a pin may be dropped in which will operate one filter or operate the other.

If the locking mechanism on the Kelly filter is the most striking part of its design, there are other individual features in this machine that merit attention:

- (1) the automatic air-regulating device which is, in effect, a provision for positive pressure within the filter when the machine is in operation;
- (2) the disposition of the leaves to give the maximum area;

- (3) the tandem, or twin, arrangement whereby two filters are placed facing each other, thereby reducing floor space required; and,
- (4) filtrate outlet connections with provisions for reversed compressed air for discharge.

Air-Regulator.—The need of positive pressure on the cakes during draining of excess liquor was the incentive that led to the development of the air regulator. It is founded on the motion of a rising or falling float riding on the liquor in the filter. When the filter is operating on the clarification, or washing, cycle the liquor enters the air chamber and



Courtesy United Filter Corporation


FIG. 44.—Typical Installation of Twin Unit Kelly Filters.

The two filters face each other with sufficient space between them for the leaves of one filter to be discharged at a time. The hopper is located under the floor with side boards extending above the floor. This is the economical use of floor space for installing Kelly Filters.

lifts the float to a high position. Here the lever has pushed the valve upward, closed the valve and cut off the compressed air. When the liquor is being drained from the filter the float falls to its low position, when the lever pulls down on the valve stem and opens up the compressed air to hold the cake in place.

The automatic introduction of compressed air and automatic shut-off, reduced the possibility of the operator's letting the pressure off on the filter while draining. It is unnecessary, however, where trained workmen operate these machines; and its interest lies more in the simple mechanics of the device than in its operating advantages.


Disposition of the Leaves.—Referring to Figs. 46 and 47, a quick outline of the disposition of the leaves used in the Kelly filter is obtained. The filter leaves are spaced apart from each other at a distance dependent upon the cake to be formed; close together for thin cakes,—



Courtesy United Filters Corporation

FIG. 43.—Kelly Air Regulator.

This device insures positive pressure on the filter leaves, for after the press is filled and all the air vented from the shell, compressed air is admitted through the "Air Inlet." If the liquor level falls the "Float" is in the position shown and the valve is open, thus admitting compressed air to the filter. If the liquor level is high the float rises until the lever in its raised position closes the valve and compressed air is shut off. Consequently any stopping of the pump feeding the filter does not require the operator to switch any valves to hold the cakes in place. The regulator does this automatically.




Courtesy United Filter Corporation

FIG. 46.—Longitudinal View of Kelly Filter.

The leaves are seen to be rectangular and of equal length. The ends of the filter are dihed to give maximum strength. The delivery of the filtrate in this particular machine is from the bottom of the leaves through blind-off ports. The major arms of the closing mechanism are seen to be in a straight line, thus insuring that the press is in locked position.

wider apart for thick ones. Disposing the leaves in planes parallel to the longitudinal axis of the cylinder naturally requires that the width of the leaves vary as the distance from the center increases. By so doing, however, the maximum filter area is obtainable and each leaf is maintained as a flat rectangle. This latter is a feature in reducing filter cloth wastage as is always the case with circular leaves. The leaves will be seen mounted on a rack carrying the rollers facilitating the movement



Courtesy United Filter Corporation


FIG. 47.—Transverse View of Kelly Filter.

The leaves are constructed of different widths to better fit the circular shell. The individual outlets from the top of the leaves carry individual outlet cocks in order to shut off leaky leaves.

in and out of the entire set of filter leaves. The customary construction of the filter leaf is shown in Fig. 48. It will be seen that though the filtrate outlet be taken at one point only, the filtrate can drain through the corrugated filter screen either at the top or bottom of the leaves. This insures adequate drainage from even long, large leaves, and makes a very strong construction for filter leaves.

Filtrate Outlet Construction.—The filtrate outlets are simple extensions through the cast-iron head of the filter. These can be made open-delivery by which each individual leaf spills into a collecting trough, a shut-off cock being provided on each outlet so that if any filter leaf fails to produce clear filtrate it can be shut off to prevent contaminating the

rest of the product. Open-delivery, while it is the simplest form of construction, is frequently less applicable than a closed-delivery construction. This varies from the above in that all the filtrate pipes are rigidly connected to a main filtrate manifold. Shut-off cocks are pro-



Courtesy United Filters Corporation

FIG. 48.—Kelly Filter Leaf with Cake.

The drainage frame consists of flattened pipe which surrounds the drainage screen of heavy crimped wire screen. The upper part of the leaf is covered with a metal guard which prevents cake bridging over the top of the leaf.

vided as before and either test cocks or gauge glasses are used to detect quality of filtrate flowing from each outlet. This manifold is usually supplied with a T-connection, one outlet with a valve for draining into the filtrate tank and the other with valve connected by flexible hose to a compressed air or steam line. The closed-delivery, therefore, permits

Courtesy United Filter Corporation



Fig. 40.—Kelly Filter—Large Twin Unit.
Large machines require heavy filter units for construction, I beams, etc. The guards over the top of filter bases are machined in the large as well as small machines. In order to move the carriage with the large and to lock the filter heads, the synchronous motor is used.

use of reverse current which is not convenient or feasible with the open-delivery construction. The flexible connection should always be shut off until discharging the machine, as it is there under pressure and for only a short period in the entire cycle of operation. When the filter is thus connected, no trouble is encountered with the flexible connection although, obviously, any design is better that does not use such connection.

Twin Unit Arrangement.—This is a novel arrangement of two Kelly filters whereby a saving of 20 per cent in floor space is effected and in which the locking mechanism of both filters is controlled by one air motor. It is confined to the larger sizes and makes the operation of the two filters a much simpler job for the operator, especially if the total cycle is short.

The secret of the success of this arrangement lies in the modification of the standard air locking mechanism. The one air motor, chains and sets of sprockets is used to open and close each filter. By incorporating a slotted bar as a substitute for several links in each chain and providing on each filter a coupling pin that can be slipped into one of the slots in this bar, quite similar to the principle of the Gould Coupler on railway cars, the forward or backward motion of the air motor opens or closes a filter. Only one filter can be opened and discharged at a time and each unit is generally operated alternately, although when half capacity is desired one filter only may be used. If the cakes are waste materials and may be mixed, separate materials may be handled in each machine. This flexibility is desirable and advantageous. The slotted bar used as a link in the chain is coupled by means of the coupling pin to a rigid cross bar. This cross bar is the same as used in the standard machine or to which the chains are attached in the single unit. Consequently, with this scheme of operating first the cross bar on one filter, removing its coupling pin and engaging the coupling pin of the other filter, the closing of each filter is a duplication of the locking and opening of the standard filter.

Operation.—The operation of the Kelly filter which is a typical pressure leaf machine, will be found to differ greatly from the operation of suction leaf filters. The primary difference lies in the method of handling the slurry to be filtered. In suction leaf filters this is pumped only as local conditions require from one elevation to another, or in order to provide circulation in the filter tank. But in pressure filters, the liquor must always be pumped, or be under static pressure or its equivalent, so as to provide the force necessary to do the work of filtration. The other marked difference is the requiring of control of the pressure in the filter so that it shall never equal atmospheric pressure during any part of the filtering cycle (including washing and dewatering) until the cycle is completed. This means that after filtration, when the excess unfiltered liquor is drained from the machine, compressed air must be admitted to take the place of the excess liquor, and similarly after washing. This necessitates a valve manipulation that is not necessary in suction filters, or in plate and frame practice. The complication of operating the valves is simple routine after one or two runs, so that unskilled operators have no trouble in handling Kelly filters. There is

quite a similarity in the matter of discharging Kelly filters and Moore suction leaf filters. In both cases the leaves are conveyed over a hopper or receiving tank and there discharged. In Kelly filters this requires simply the moving of the carriage supporting the filter leaves out of the shell of the machine.

In operation of the Kelly filter the first step is to lock the filter in its closed position and admit the material to be filtered. During the filling operation an air vent located at the top of the machine must be open, unless the filter is equipped with an air regulating device with blow-off connections, in which case the air escapes through the blow-off. When the filter is filled, the liquor issues from the air vent or the float in the air regulating device operates and closes the blow-off. The air vent is then shut and the pressure from the pump, montejas, or gravity feed, forces the liquid through the pores of the filter fabric to the interior of the filter leaves which is at atmospheric pressure. The amount of pressure to be employed varies with the material handled, but since the filter is designed to withstand a pressure of 75 lbs. per sq in., any pressure can be used with safety up to 60 lbs. per sq. in. Twenty-two inches of vacuum or 11 lbs. per sq. in. is the average pressure in the operation of vacuum filters. The difference therefore between 11 lbs. and 60 lbs. per sq. in. represents the cardinal difference in the two types of filters—suction and pressure.

Filtration progresses with the cakes building upon the filter cloths, in most instances in an even thickness. If the slurry contains coarse materials which tend to settle readily, it is often necessary to pipe an overflow line from the top of the filter at the end opposite to the inlet connection, or from outlet tappings evenly spaced at the top of the filter. By piping the overflow line back to the source of supply any amount of circulation can be obtained in the filter by controlling the shut-off valve on the overflow line. This circulation, which is in reality an uprising current of the liquor between the leaves, tends to distribute evenly the coarse particles throughout the mass of the cake. In most instances it is a very successful means of producing even thicknesses of cake even with otherwise granular material. As in the case of suction filters, in the Kelly and all pressure leaf filters, the leaves must be so placed apart that the cakes built up on the leaves will not touch cakes on adjoining leaves. Obviously leaf spacing is determined by experience either from small scale laboratory tests or from plant practice on the same material manufactured under the same conditions. The leaf spacing is not made for the possible cake that can be built up, but for the economical cake. Economical means in this case that thickness at which the flow has decreased to an economical minimum determined both by the actual flow produced at that time and with consideration of the time required for the subsequent operations of washing and dewatering. The spacing is considered correct when there remains a $\frac{3}{8}$ in. clear passage for wash water, etc., after the economical cake has been produced. This is equivalent to that considered best practice in suction leaf filters and differs from that practical in the self-discharge plate and

frame filters of the Atkins-Shriver and Merrill type. In these machines a much smaller spacing is required between the deposited cakes.

Granting that the spacing has been made to comply with tests conducted on a true average of the material, there must still be left to the operator's discretion the exact economical limit for each run. This is because the materials handled in the industries are variables. This variation should, however, be confined entirely to the material itself and not be due to changes in temperature and density of the materials fed to the filter. These are controllable and should be maintained constant, one run after another. The variation that will occur, however, is in the material itself, and is due to a change in the impurities that different batches contain. There is, consequently, no guide quite as informative as the experience gained by observing the cake formation after each run. In an endeavor to assist the operators of Kelly filters, especially in the beet sugar field, a cake tester was installed on machines in several different plants. The original cake tester consisted of a simple revolvable shaft placed between two leaves at the locking end of the machine. On the inside this shaft was turned at right angles and carried a sheet metal disc so that the operator could turn the revolvable shaft and determine by the stopping point the size of the cake built up. Another scheme of cake testing was to provide a sliding rod perpendicular to the surface of one end of the leaves. On the inside this sliding rod was provided with a sheet metal disc. This disc was set away from the filter leaf $\frac{1}{4}$ in. less than the desired cake thickness. When the cake had built up so as to touch the disc, the disc started then to move in toward the filter cloth and thus give signal to the operator by contact of electrical circuit with bell or light. These devices were soon found not infallible and, from the nature of industrial filtration, it would be hard to make them more than mere indications to help the operator. For instance, if the filter cloth at the point of application of the cake tester is not thoroughly cleaned it is not representative of the rest of the filter area and the cake at that point is less than throughout the machine. It must not be inferred that it is difficult to gauge the economical thickness of cake in Kelly filters, as one needs but to remember that the Kelly filter enjoyed a wide popularity, especially in the beet sugar industry, and its operation proved it a tremendous advance over plate and frame presses and suction leaf filters. The operation is entirely a matter of the efficiency of the man operating the machine, and it is surprising how quickly the lowest class of unskilled labor can perfect the operation of the machine if properly instructed in the initial operation.

Draining the Filter.—When the filtration cycle is completed, it is necessary to drain the filter of the excess unfiltered liquor lying about the filter leaves, whether the cake is to be washed free of the entrained solubles or whether it is to be dewatered and discharged without washing. Draining the excess from the filter is preferably done by opening a drain connection feeding into a sump or receiving tank located below the filter. Having a gravity flow to the sump requires the minimum air pressure within the filter. Excessive pressures are to be avoided. Consequently,

when draining the excess from the filter, the first operation is to close the inlet line and, if the filter is not equipped with an air regulating device, open a compressed air line feeding to the top of the filter (usually a T from the same tapping for the air vent). If the filter is equipped with the air regulating device the compressed air is admitted automatically. As we have seen, the use of compressed air is to make the cakes adhere to the filter leaf, since any positive difference in pressure between the outside of the filter cake and the interior of the filter leaf of at least 3 lbs. per sq. in. will hold the cakes in place, it is advisable to make sure the air is on as quickly as possible after shutting off the inlet line. A precaution about admitting low pressure compressed air too soon is needless, for if the compressed air line is equipped with a check valve, irrespective of the pressure in the filter, the sludge cannot then fill the compressed air line. Difficulty on this score is only found when the check valve is omitted, and the inlet valve does not completely shut off. Leaky valves have no place in economical filtration, and it is a positive part of the operator's work to maintain his valves in good condition. Low pressure compressed air is used for draining the excess and it is best when maintained not over 10 lbs. per sq. in. nor under 5 lbs. per sq. in. As the excess sludge drains from the filter, the upper part of the cakes are subjected to the partial drying effect of the compressed air. In consequence, the draining should be accomplished as quickly as possible and oversize pipe lines are the practical means of making the transfer quickly. The diameter of the drain line should average at least 50 per cent greater than the diameter of the inlet line. The latter is determined by the size of the filter, both in respect to the filter capacity and the time required to fill the filter at the start of the operation. Therefore, with a drain line of 50 per cent greater diameter, and with an unfiltered liquor excess that should average less than half the liquor required to fill the filter at the start of operation, the draining time should not be over 1½ to 2 minutes. Promptly upon air issuing from the draining valve, the drain should be closed and wash water admitted. The wash water is generally at a pressure in excess of that maintained at the close of the filtering cycle and the compressed air should be vented fast enough so that the pressure is held between 5 and 10 lbs. per sq. in. until the filter is filled with wash water.

The need of draining out the excess unfiltered liquor before admitting the wash water has been the subject of much discussion. The control and operation of the filter would be far simpler if it were possible to eliminate the draining and re-filling operations. Irrespective of this advantage, it is the economical means of operating Kelly filters. With the excess unfiltered liquor in the filter, the wash water becomes enriched, so that instead of washing with water or weak liquor, as the case may be, in reality it is washing with diluted strong liquor. This is not good practice, but worse yet, is the fact that the enriching effect is not constant, being very much more prolonged at the sides of the small leaves than in between the larger leaves at the center. If it were that this enrichment added to the time necessary for washing or in the amount of weak filtrate

produced, this might be enough to condemn its practice, but it is impractical to wash the cakes completely free of soluble, since there is no adequate test by which the operator can judge when the cakes are washed. In some instances, especially where there has been sedimentation in the bottom of the shell, before admitting the wash water, the bottom of the shell is flushed out, the idea being to remove this material with the strong liquor in it, to prevent enrichment of the wash water by sediment, similar to that discussed above.

If the excess unfiltered liquor has been drained quickly and positive pressure maintained in the machine throughout this operation; if the wash water has been admitted and the air vented so as to maintain a positive but relatively low pressure, then the filter cakes will be in approximately the same condition as they were at the end of the filtering cycle. Displacement washing will result in the high washing efficiency of which this filter is capable. It is, of course, assumed that the cakes on the leaves have not touched each other at any point, so that each of them is completely submerged with free passage for wash water.

Washing.—There is undoubtedly no greater factor contributing to the fall in popularity of the Kelly filters than the failure of operators to obtain true displacement wash in actual operation. This is not hard to understand, for, let the compressed air be turned off, or in any other way the pressure be dropped during draining, and some of the cake is liable to be pulled off the leaves. This manifestly destroys the very foundation of displacement washing, for now there are paths where the water can penetrate faster than at other points. Or, let the transfer and re-filling with wash water be prolonged, the top of the cake will be found to be partially dried and possibly cracked. This, too, defeats displacement washing.

It was therefore hailed with considerable enthusiasm when the suggestion was first made that there could be a fool-proof scheme of washing by displacement any cake built in Kelly or other leaf filters. The scheme is simplicity itself, for it substitutes a muddy wash water for clear wash water. The mud is usually washed cake from a previous run, and while it requires a separate tank equipped with agitators, it is surely a trivial item compared with better washing results. It is safe to say that many a faulty Kelly filter installation would still be in good repute had this scheme been applied. The mud of suspension in wash water fills up the cracks, open spaces, and other points of low resistance, until the resistance of the surface throughout the filter again becomes uniform. From that point on, washing is really a continuation of filtration. It is thus seen that if anything short of wilful misoperation occurs, this scheme will still guarantee complete washing and a close approximation of displacement wash.

The amount of mud to put into the wash water is very largely a consideration of the material being handled. With a free filtering solid it is even possible to use inert clays, or other slow filtering materials, to better advantage than unwashed cake of previous runs. In washing

slow filtering materials, the solids present can be very much reduced from those necessary in washing the cakes from free filtering materials.

It is always difficult to lay down general laws for the operation of any industrial filter, and, at best, such laws are only applicable to a majority of installations. Consequently, when it is stated that the wash water should be fed in with an initial pressure slightly in excess of the limiting pressure during filtration, it is an adage for the majority of applications, but bound to have a large number of exceptions. However, if the wash water is muddled this law will be found to be largely applicable. The reasons favoring this higher pressure are not hard to find. It is assumed, of course, that the filtering operation was confined to a pressure within the limits of the critical pressure for the material in hand, and that the pressure during washing does not exceed critical pressure. Then the higher pressure tends to compress the cake, which means decreasing the voids and thereby lessening the requirements of the displacing wash water and also insures maximum rate of flow during the washing cycle. The latter is not generally a big factor, as the strong liquor to be washed out of the cake has, in most instances, a specific gravity well in excess of the wash water so that its viscosity is also greater than the wash water. However, if the wash water is a clear liquid, this increased rate of flow jeopardizes complete washing of the cake, for it often means washing out parts of the leaves in advance of the remainder, whereas if the water carries solids of suspension, the more water filtered, the more solids deposited, and the more even washing obtained. This idea of using a higher pressure during the washing cycle is a reversion back to the laws governing the operation of plate and frame presses where the same idea was used. In many installations the higher pressure did not help, and so confidence was lost in the old law, but the number of instances where it has not been applicable has been grossly exaggerated.

There seems to be a rather unique repetition in the different steps of the cycle of filter operation preparatory to the next step. For instance, in filtration the uniformity of cake building plays an important part in the washing operation and now we find that the compressing effect on the cake during washing aids in the drying operation.

Drying.—The drying operation follows the washing, the initial step in which is to remove the excess unfiltered wash water. This is drained back to the wash water supply tank, which is preferably located below the filter so as to require no head for its removal. Pressure must be maintained in the shell, as in the case of washing, or otherwise some cake will slough off the leaves. Therefore, the pressure during the withdrawal must be positive, but it is best when maintained between 5 and 10 lbs. per sq. in. As soon as the wash water is cut, which is indicated by a chattering of the drain valve, the drying commences and the drain valve is closed.

Drying these cakes is removing the excess moisture from the voids of the cake. In effect, it is the filtration of compressed air through the cakes. The one big drawback is in the early cracking of the cake, there-

fore every means that will delay this cracking is an advantage. This is the prime reason for maintaining a pressure not too high at the start of the drying operation. The limit for the initial pressure is one of the most variable factors in connection with industrial filtration. It depends upon the material, even though the material itself is common to all. It is produced in the manufacture of another product and is dependent entirely upon the particle size and density of the cake built up. The pressure can be higher with cakes from free-filtering liquors than it can with those with finer particles of suspension.

At best, however, the drying operation is the weak spot of leaf filters. The Kelly filter, by means of bottom outlets, will often deliver better cakes than can be obtained in some of the other types of leaf filter. Excessively long leaves do not give much advantage on this point.

To prolong the drying cycle after the pressure drops to one-half the limiting filtering pressure is generally a wasteful procedure. It requires more horsepower to compress air, and the volumes required when the pressure has cracked open will always be found to be excessive.

Discharging.—As soon as the compressed air is released, the material is ready to be discharged. The first step is to unlock and open the discharge valve. If the delivery from the filtrate manifold has been into open troughs, the valve must be closed or a flexible hose connection must be attached so as to feed reversed compressed air into the interior of the filter leaves so that the cakes may be discharged without hand labor.

The carriage containing the leaves should move out of the filter house with as smooth a motion as possible. A jerky motion will dislodge parts of the cake and tend to lessen the efficiency of the reverse current charging. The compressed air in the interior of the leaves in the filter filters out through the filter cloth and impinges the cake. Naturally if the cake has been dislodged, the air penetrates through at this point with less resistance.

The reverse air should have for its function the lifting of the cake away from the surface of the filter cloth. It is not an air blast. The pressure of the reverse air should be maintained under a maximum of 10 lbs. per sq. in. so as not to harm the cloth. If the filter cloth is unsupported, save at the edge of the leaves, there is danger that the reverse current will balloon the cloth and distend it so that the air will disengage the cake, must lift it almost vertically. This condition does not exist in practice for with the leaves on close centers, as filter leaves are designed, this means pushing adjacent cakes together. In itself, this is possibly not a disadvantage, but in falling, this cake jams between the leaves and holds up further discharge. There are therefore, very few instances where ballooning of the cloth is not a practical consideration. There are many schemes for reducing this and they are dependent largely upon the type of drainage member used, but one of the most popular methods is to secure the cloth every six inches with half eyelet rivets.

Compressed air typifies the reverse current agents used in discarding Kelly filters, but low pressure steam is often used and is in

instances a better agent than compressed air. Steam, of course, should never be used save in the handling of hot liquors.

Great hopes were once held that an automatic sluicing arrangement would be perfected for Kelly filters. The elements of good discharge by this method would seem to be in the fact that the sluicing streams would need to throw but a short distance and that the sluicing nozzles could be fixed in position and the leaves rolled in and out against them. The sluicing discharge, coupled with reverse steam, made an excellent means of cleaning the Kelly filters tried out on raw cane sugar. However, sluicing discharge is confined to those materials which build up cakes of small thicknesses, and, for these liquors, closer leaf-spacing is obtainable in Sweetland filters than in the Kelly, and therefore greater filter area per square foot of floor space is secured.

An interesting method of discharge, although not presented as an acceptable method of discharging Kelly filters, is the high pressure air blast systems. In this the operator plays the nozzle of an air hose, pressure usually being around 75 lbs. per sq. in., at the top of the leaves. The cake discharged is then blown across until it hits the other leaf, rebounding back and hitting the original leaf and repeating until it blows out at the bottom. After the air leaves the hose, it becomes no longer compressed air, but a veritable air blast, and will clean cloths that have been gummed up with organic waxes, so thorough is the cleaning action. Filter cloth is, of course, never constructed to withstand such treatment and its life is short. The factor of the baffled current cleaning the leaves is beautifully demonstrated here and has led to the application of this principle in the sluicing discharge of Sweetland filters.

Any method of discharge from Kelly filters is primarily a sloppy operation in that the cake falls and is never completely firm and is liable to splash so that some of it flies all over. It is, therefore, good practice to house in the discharge hopper by side plates (as shown in Fig. 44) which will reduce this condition so that it becomes negligible as a drawback. In sluicing discharge, these side plates on the hopper should be supplemented with a sheet covering to prevent splashing in all directions.

Discharge from the leaves is often incomplete, even if the surface of the cloths be quite clean. The cloths will be found clogged beneath the surface with scale formation, or entrapped solids. These impediments must be removed or the capacity of the filter drops. But extraordinary methods must be applied—the scale material must be dissolved out of the cloth and generally the dissolving action is quickest when using weak hydrochloric acid. This weak acid is corrosive, not only to the filter cloth, but even more so to the materials of construction and its use is hazardous at best and requires careful watching and control, or more harm than good results. The concentration of the acid, the temperature of the solution, and the time of contact with the scaled cloth are all dependent upon the amount of scale present and whether it is a carbonate or sulphate. Experience is the only judge for the local plant. In some installations the weak acid is pumped into the filter and the cloths stand immersed in it. In others, reversed compressed air is forced through the cloths

to hasten the dissolving action. Steam has also been used as a substitute for the compressed air. One plant obtained excellent results by first thoroughly cleaning the filter leaves and filter proper and then pumping the acid through the cloths in a reverse direction, re-pumping the overflow from the top of the machine as a circulation. This is undoubtedly the best method provided the acid stays clean so that a deposit does not form on the inner side of the filter cloth. When the impediment is a solid of suspension, especially from organic liquors, filling the filter with hot water and to reverse steam through the filter cloths gives the desired result.

The cycle of operations on the Kelly filter is complete with the closing of the machine. This has been outlined before, but so many operators are negligent of proper care of the gasket that the caution is advisable that the gasket and the impinging metal surfaces be kept clean, when leaks will be avoided and the gasket will hold out for a life of 6 to 18 months.


Layout.—The location of the Kelly filter in the plant is often attempted with the idea of using available space and with insufficient regard for its location with respect to feed tanks, pumps, filtrate delivery and accessibility for control of valves. This has led to more than one installation turning out to be but a partial success instead of a complete success. *Convenience of operation* is not a fad, lessening the work of the operator, but a necessity enabling the operator to obtain best results. In the Kelly filter there is considerable piping and transferring of the liquors and the easier the valve control, the shorter the time not used for actual filtration, and the more positively can pressure be maintained at all times. No layout can be made standard for every installation, but the correct layout should be made the goal, and present installations not conforming to such correct layout, as shown in Fig. 50, can well be changed. Note that the filter is best set into the floor, with center line at the floor level.

Advantages.—Of all pressure leaf filters, the Kelly is the simplest in design and cheapest in cost of manufacture. Using the cylindrical shape with one end closed makes the casing on this filter a straight boiler shop job. The movable head, made of cast iron, with the cast iron ring for gasket service, comprises the only heavy casting work required.

The Kelly filter early proved that for many materials handled in industrial chemical plants, the capacity per unit filter surface is greater than that obtainable in suction leaf filter and plate and frame filter presses. Compared with the Sweetland and Valley filters, the capacity during filtration is equal, but the output per day, including time out for transferring liquors, etc., will generally be found to be under other continuous filters.

Making the Kelly filter leaves rectangular preserves a feature found in the square type plate and frame presses and in suction leaf filters, of requiring no circular cutting or loss of filter cloth. Different widths of cloth are required, of course, if the narrow side leaves, the intermediate and center leaves, be covered without cutting wide cloths to waste.

The actual floor space required by the Kelly filter is not excessive



Courtesy United Filters Corporation

FIG. 50.—Kelly Filter Layout.

Whether for inclined or horizontal types the use of angle valves to form a manifold is the convenient arrangement for controlling the operation of the filter. Cone plugs are the simplest means of switching from cloudy to clear liquor in the filtrate launder. The outstanding feature of the Kelly Filter Layout is the accessibility of all valves within easy reach of the operator.

even in single units, but the space is long and narrow. With the twin unit, however, the floor space required is a minimum for pressure leaf filters maintaining accessibility of filter leaves. The headroom likewise is small in Kelly filters, since there is no need of hoisting any part of the machine above its stationary position, nor are there any movable counterweights that travel above it.

The displacement washing obtainable in suction leaf filters is maintained in Kelly filters, and if wash water is muddled, washing the cakes is positive and efficient.

The Kelly filter has but one main gasket joint, circular in shape, and by far the simplest gasket found in any pressure filter, including plate and frame presses. It is simple to maintain this joint leak-proof at all times.

The stationary cylinder with its unobstructed surface is admirably adapted for heat insulation by asbestos or magnesia covering.

Drawbacks.—There has been a mistaken idea that the filter area in Kelly filters is most accessible. The filter leaves on the sides are most positively so, but the leaves at the center can be observed only from a position at one end, or, in the case of twin units, from a point above the filter leaves. It is self-evident that the cloth, viewed from a distance, cannot be properly inspected. Accessibility for observing the condition of the filter surface is not vital, but is valuable if the operator desires to get the best possible work out of this type of machine.

Dividing the cylinder with square leaves placed parallel to the axis necessitates a large part of the space being left unutilized. This excess space becomes filled with excess liquor and adds to the time required for transference of residual liquors, and so hinders the operator's work. This is emphasized when having to pre-coat the cloths before starting filtration.

In machines of large diameter, individual filter leaves become heavy and cumbersome and require additional labor for their removal and recovering. Having different sized leaves, any one leaf is not interchangeable with every other, so if spares are kept on hand, one of each size is required.

The filter leaves are supported at the two ends and, as the length of the filter is best proportioned at twice the diameter of the shell, the span between supports is large. Consequently, if the machine is overcharged with cake, the damage done by warping the leaves is heavy and requires that the warped leaves be removed and straightened outside of the machine.

Flexible connections are always makeshifts in plant practice, as they are necessarily weaker and often become troublesome when the attaching threads or flanges become worn. The Kelly filter, requiring a flexible connection on filtrate discharge, is therefore weak in this detail.

As in the case of suction leaf filters, drying the cakes by filtering air through them is not a satisfactory means of dewatering filter cakes.

The I-beams or channel irons on which the carriage, carrying the leaves, rolls, become shelves on which the solids of suspension deposit and soon eliminate rolling contact of the rollers so that the carriage slides through the mud on these supports.

This movement of the filter leaf carriage on the side supports condemns lead lining or other protective coatings in this filter, as lead and other coatings will not stand the abrasive effect of the loaded carriage on the supports.

The Kelly, as well as the suction leaf and other pressure leaf filters, is intermittent in operation and, as such, its efficiency is dependent upon the skill of the operator. The work required of the operator in handling this type of machine is not great, but careless operation can result in both low efficiency and big losses.

Applications.—The Kelly, being the first pressure leaf filter on the market, was introduced into a large number of industries. Its advent was heralded as "a filter press that embodies all the advantages of leaf filters, and shows economies of operation over plate and frame presses that can net an annual return of 100 per cent on cost of installation." The Kelly, therefore, was applied as a substitute for existing filter presses. These replacements took place in oil refining; in starch plants; in causticizing; aluminum hydrate; intermediate dyes, and other general chemical manufacturing plants. The one industry where more plate and frame presses went out and Kelly filters went in, is the best sugar industry. Here the Kelly was used very successfully, for first and second carbonation juices; filtering calcium carbonate from the sugar liquor, and washing the sugar from the cake.

In general, the Kelly is applicable to any filtration liquor, hot or cold, small or heavy concentration of solids in feed where the solids are desired free of soluble.

These filters are not adapted to acid liquors, nor for those materials in which hard, dry cakes are required, and they have not been developed for slushing discharge.

Summary.—The Kelly filter, as the first pressure leaf filter, has earned an enviable reputation. The economics effected by its installation, replacing plate and frame filter presses and making applicable leaf filters to those materials not handled with suction leaf filters, represents a large amount of capital.

The drawbacks to the Kelly filter are in most instances overcome in the Sweetland filter, the design of which has been developed through a decade, and the Sweetland machine will therefore be taken up next.

Chapter V.

Section II—The Sweetland Filter.

The Sweetland Filter, earlier known as the "Clam Shell" filter, has for its basic principle, leaf filtration under pressure, identical with that of the Kelly, from which it differs only in the mechanics of design. It is, perhaps, the leading filter working on this principle, as evidenced by the great numbers found in the industries today.

History and Development.—This filter has had a considerable development from Ernest J. Sweetland's first machine. Sweetland was a mill superintendent for a gold mining company when he first applied himself to filtration. There were installed in his plant a battery of Butters' filters which began to fall off in capacity due to a change in the character of the ore being worked. Trying every known "trick of the trade," but still failing to get sufficient output, he decided that the vacuum pressure was not great enough for his slimes. Greater pressure meant using plate presses, until he thought of the scheme of inserting filter leaves in the frames of a conventional plate press and eliminating the plates. This he attempted to do, but found that there were considerable modifications necessary and therewith he worked out a new design and built his first filter.


Design of First Sweetland Filter.—The starting point in his design was to provide gaskets between abutting frames, since the removal of the plates and conventional filter cloth left him without a gasket. This he worked out by machining a groove in one side of each frame and inserting in it a square rubber gasket with $\frac{3}{4}$ in. protruding. The groove in the frames was usually $\frac{3}{4}$ in. wide by $\frac{3}{4}$ in. deep, so that a $\frac{3}{4}$ in. square gasket fitted and left the $\frac{3}{4}$ in. protrusion desired. Joining the ends of this gasket was at first a nice splicing job, but later butt-joints proved equally effective, provided a slight excess of gasket was forced into the groove so that there was positive pressure against the butting joints.

The second modification in the design was to make the frames thick enough to allow outlet pipes for the leaves to be inserted through them. At first thought this would seem to indicate that less filter area could be provided for a given length of filter, since fewer thick frames can be placed in the filter. It is true that the filter leaves are thus placed further apart,—and must be, if the principle of leaf filtration be maintained. One of the primary requisites is that the fully formed cakes on adjacent leaves shall not touch each other, and here is one of the reasons for this extra spacing. It must be remembered that the plates were eliminated and this

left room to allow the same number of leaves as filter plates in the conventional filter.

The method of attaching the leaves consisted of threading a small pipe nipple into a tapped opening in the frame leading to a filtrate outlet. A similar short nipple extending from the filter leaf was connected with the nipple in the frame with a conventional pipe union. Clips at the other three corners aligned and supported the weight of the leaf.

A further modification was necessary in order to provide space for the discharged cake. This consisted simply in making the lower part of



Courtesy United Filters Corporation

FIG. 51.—Harfast Type of Sweetland Filter.


Each frame carries a filter leaf suspended by a nipple and union from a cored filtrate outlet and aligned at the lower corners by clips. The bottom of the frame is V shape to accommodate the cake when discharged from the leaf to be inclined from the filter.

the frame of a V-like trough section. As the filter leaf was not allowed to extend to this part of the frame, an open trough was formed the full length of the press. Sweetland was quick to realize that if the cake fell into this trough, he would have trouble in removing it unless there were a decided pitch to the trough. Here lies the secret of the inclined position of his early filters. This is shown in Fig. 52.

At first, one is bewildered at the perpendicular position of the leaves as compared with the inclined position of the frames. On second thought, however, it is evident that the frames must be perpendicular to the side arms and to the locking screw, or else the closing pressure would not clamp the frames evenly together. On the other hand, the leaves must

be vertical or else the cakes could not be discharged by reversed current from the upper side of the leaves.

Sweetland's genius for mechanics stood out in this first of his filters. Note the T-rail cross section of the frame,—the same principle underlying the design of I-beams—was incorporated in the design of these frames. This had an economic value of no small importance. We must remember



Courtesy United Filter Corporation

FIG. 5a.—Earliest Type of Sweetland Filter.


The filter is an assembly of separate frames, each carrying its own leaf, on inclined side arms. The leaves being vertically with plenty of clear space below to insure thorough discharge of cake. Each frame is constructed on the T rail principle to obtain maximum strength and to allow high internal pressures—the dominating feature of the first Sweetland Filter.

that he had in mind increasing production by using high pressure. To withstand internal pressure, such as this design of frame can successfully resist, ordinary frames would have to be made of semi-steel or else have metal extremely thick, and weighing many times more than this.

The idea of inserting square rubber packing as a gasket met with considerable skepticism from many quarters. It was thought that the bearing area was too small and would permit leakage past this gasket. In point of fact, a pure gum rubber strip was used, which has sufficient resiliency to make a tight joint with a relatively low closing pressure. Exposing only

$\frac{3}{8}$ in. of the gasket beyond the surface of the frame insured very small pressure against the gasket, even when the filtering pressure rose to 150 lbs. per sq. in.

Five eyes were provided in the frame (shown in Fig. 53) which made continuous passageways through the filter when a press was assembled. That marked 1 provided for the collection of cloudy filtrate, in case any one leaf became fouled and leaked. Eye 2 was used for clear filtrate. The test cock shown at the extreme upper left corner served to detect leaky leaves. A 3-way valve located on the branch piping to the eyes 1 and



Courtesy United Filter Corporation

FIG. 53.—Harfrost Sweetland Filter Frame.

Several conduits formed by adjacent eyes in each frame are, No. 1, cloudy filtrate; No. 2, clear filtrate; No. 3 and No. 4, water jets to scour cake from corners; and No. 5, slushing water to discharge cakes from leaves.

a served as quick switching valve to direct the filtrate flowing into eye 2, into eye 1. Obviously, conduit 2 provides means for introducing a reverse current (of steam water, or compressed air) to discharge the cake from the leaves. Eyes 3 and 4 were provided to project jets of water to clean out any cake that might hang up in the corners of the trough. Eye 5 was the spray water conduit by which water was fed into the spray pipes located between each pair of leaves. The water from these pipes functioned in assisting the discharge of the cake and washing down the filter cloths. Note the shut-off cock provided on each pipe. By shutting off all save one of these pipes, the entire pressure of the pump could be centered on the one open pipe, thus increasing the force of the stream playing upon the cake or cloth.

Operation of Early Filter.—The operation of this first Sweetland filter was a cross between that of the plate and frame press and the operation of suction leaf filters. In filling the machine with liquor, it parallels plate and frame operation, but filtration in the Sweetland was stopped before the cakes on adjacent leaves touched each other,—which is like suction leaf work. After filtration was completed, the excess unfiltered material was drained from the filter exactly as in the operation of the Kelly filter. Re-filling with wash water and washing the soluble from the cakes was again a point of likeness. Discharging was a point of difference, for the leaves were stationary and could not be drawn out so as to discharge the cake over a hopper, but the cake, dropped down into the open space at the bottom of the filter, could be sliced out, and the filter was operated in this manner exclusively. The difficulty of obtaining adequate discharge and the confining of the filter to shulcing methods, was its paramount weakness, and as a means of correcting this shortcoming, Sweetland designed and developed his more familiar filter,—the "Clam Shell."

Design of the Clam Shell Filter.—The mechanics of this filter have been, in a sense, a series of developments originating with the first hand-tightened unit. In this machine, each swing-bolt, front and back, had to be tightened with a socket wrench, and in addition to the labor involved, one had to be sure that the tension on the swing bolts was approximately equal or else the gasket would be squeezed too much at one point and leak at another.

What characterizes the clam shell filter is its cylindrical shell, split into two halves longitudinally. The upper half is stationary, and the lower half is hinged to the upper so as to swing at least 90 degrees. Dividing the shell longitudinally necessitates a joint that is practically impossible to obtain with boiler plate construction so that this machine must be cast. In consequence the ends of the cylinder are heavily ribbed to withstand internal pressure. The greater part of the shell is a true cylinder, but a distributing, or drainage channel is provided in the lower half and a cavity is located in the upper half into which a shulcing pipe, or overflow pipe, may be located. The filter leaves are all located in the upper half of the machine and are inserted individually in openings which have been drilled through a boss located at the zenith of the machine. By drilling these filtrate outlet openings of the machine, any desired spacing of the filter leaves can be obtained, and each filter leaf be equi-distant from the adjacent leaf throughout the entire machine.

Genius of design is disclosed by the arrangement whereby the liquor is fed to the clam shell filter. Note that the lower half is movable and carries the distributing channel and yet there are no flexible connections on this machine. The feed enters the upper half of the stationary member and a cord passageway connects at the joint of the two halves with a corresponding cored opening which leads to the distributing channel.

The upper half is rigidly bolted to the filter supports, which are preferably long enough so that the joint of the shell shall be eye-high from floor or operating platform. To save these supports from becoming




Fig. 34.—Modern Sand Filter (Cluny Shell Design, Longitudinal Section).

The slanted inlet (No. 1) is on the stationary half but communicates through the cored passage to distribute water evenly along bottom half. A distributing plate, over the drainage channel, has openings between adjacent leaves so that liquor and wash water are admitted evenly throughout the section. Distributing openings (No. 2) for admitting liquor or wash water are located at both ends of the machine, one at the inlet end being located at the base of a U-shaped well to insure complete withdrawal of the liquor. The leaves (No. 3) are vertical and equidistant, and the drains (No. 4) are built up without any sharp turning so adjacent one, time having free passage for wash water.

unduly heavy, they are often of a length less than required for the position of the joint and are then mounted on concrete bases, rail filter to the desirable height.

The lower body is counterweighted to facilitate easy moves this half. The curved counterweight arms are necessary in order the half be balanced by the weights in any position, as the weight



Courtesy United Filter Corporation

FIG. 55.—Sweetland Filter—Open.

The lower half is movable and counterweighted to balance in any position. In full open position all the cake falls clear of the shell into a hopper or located below. The simple turning of the pilot wheel, without any handles, turns a gear keyed to the shaft on which all the swing bolts are located. This enables the operator to easily lock or unlock the filter.

be so located that their center of gravity is on the extension of the line drawn from the center of gravity of the lower half through the center of the back hinge.

The joint between the two halves is made by the compression of a pure gum strip (or similar material) gasket carried in an accurately machined gasket groove. No gasket is carried on the lower half, as the joint forming surface of it is again accurately machined. Note that the surface of the joint on the lower half is not grooved, but is

with the principle of the joint in the early Sweetland filter. These machines have been built 12 feet long by 4 foot diameter, positively leak proof at all times. This would at first seem remarkable, but the design contemplates a squeezing of the gasket along the rear side in advance of any compression of the gasket in front. Consequently, if the front is tightened up to be leak proof, the back and sides are bound to be water tight.

With the smaller sizes counterbalancing, the lower half is sufficient to enable the machine to be opened and shut in a fraction of a minute. But with the larger sizes, especially if any of the cake falls into the



Courtesy, United Filters Corporation

FIG. 56.—Sweetland Filter—Closed—Back View.


The counterweights are carried on an extra heavy angle iron attached to curved arms so that the line through the center of gravity of the filter and the hinge passes through the center of gravity of the counterweights. The rear hinges consist of small shafts carried in individual hinge bolts, each of which is adjustable. A hydraulic or pneumatic cylinder supported from the floor and connected to one of the counterweight arms facilitates the movement of the lower half.

lower half when opening for discharging, a pneumatic or hydraulic cylinder is attached to one of the counterweight arms. This cylinder is equipped with a 4-way valve so that the pressure can be applied on its piston to move it up or down and the exhaust line is throttled so that the movement is never excessively fast. This cylinder makes it possible to swing a lower half weighing 8,000 lbs. by the press of a finger.

To align the leaves in perpendicular position and so that each leaf will be parallel to each other, the filtrate openings are counterbored to receive a washer which rests around the outlet pipe at the top of the leaf. Additional aligners are fastened to the sides of the upper half, inside, so that the leaves are held in position by 3 points: the counterbore on top and the two side aligning lugs. These aligning lugs appear as No. 7 in the cross sectional view of the filters shown in Fig. 57.

When the base is drilled to receive the outlet nipples, it is drilled and

tapped on the front side at right angles to the center line of each vertical drilling in order to provide outlet connections to the filtrate fold. From each of these drillings are assembled the outlet fittings.



Courtesy United Filter Corporation

FIG. 57.—Swestrand Filter—Transverse Cross Section.

List of Parts:

- | | |
|--------------------------|---------------------------------|
| 1—Internal manifold | 11—Lead washer |
| 2—Filtrate manifold | 12—Rubber washer |
| 3—Sight glass | 13—Nordic |
| 4—Filter leaf | 14—Swing bolt caustic nut |
| 5—Distributing plate | 15—Yoke hinge bolt |
| 6—Hinge | 16—Yoke hinge bolt caustic nut |
| 7—Side leaf spacers | 17—Hinge pin |
| 8—Swing bolt | 18—Plain hinge bolt caustic nut |
| 9—Filtrate shut-off cock | 19—Plain hinge bolt |
| 10—Cap nut | 20—T outlet fitting |

The circular filter leaves closely fit the curvature of the shell. Each is supported by the cap nut (No. 10) from above and aligned by the leaf (No. 7). The filtrate drains from the leaves into the individual outlet cones (No. 9, 3, 20 and 8, respectively). Each leaf is thus replaceable without disconnecting any of the outlet connections. The large swing bolts hang on the common and when loosened are pushed out of line by the engagement of pins on the with lugs on the bolts.

consist of a shut-off cock, sight gauge glass and pipe connection into filtrate manifold. These are shown in Fig. 57 as No. 9, No. 3, No. 20 respectively. This scheme of filtrate delivery is very clever,

requires simply that the outlet pipe of the filter leaf shall be drilled at a point registering with the center line of the side drilling of the boss, so that the liquid from each leaf flows into those outlet fittings.

Each leaf is held in place by an exterior cap nut. The filtrate nipple on the leaves is proportioned so that a full thread extends above the boss, when the leaf is inserted in the filter. On top of the metal washer used to align the leaf is placed a rubber washer and under the cap nut is placed a fibre or lead washer, so that when the cap nut is screwed up tight the rubber gasket is compressed and the cap nut bears solidly on the fibre washer. By this, a simple and most effective means of preventing leaks is obtained.

The hinge on the Sweetland filter has undergone considerable development and that now used is not only the best but the simplest. Lugs are cast on the back of both upper and lower halves and drillings are made through each boss on the upper half to receive a special forked bolt. Between the forks is placed the upper end of a special hinge bolt fitted into the drillings of the lower bosses. Through the forks and through the hinge end of the bolt extend small lengths of shafting. By adjusting the castle nuts on the bolts, the lower half can be raised or lowered in relation to the upper half and the amount of compression on the gasket at the rear regulated. As the gasket wears down, sometimes every week and sometimes twice a year, the compression has to be increased and this scheme of adjusting the hinges is positive and takes care of any spring in the cast-iron over a twelve foot length. Of course, there is a possible weakness in this construction should the operator excessively tighten one bolt more than the others for then the pressure, when closing the filter, might be sufficient to crack the lug or strain the shell itself. This is a possibility not yet experienced in practice. Fig. 57 shows the hinge construction.

Locking the two halves pressure tight is a simple process—turning an eccentric shaft through 180° —but the mechanics involved are as original and effective as have been developed in connection with filtering apparatus.

The locking mechanism supplanted the original hand tightened swing bolts used on the first models. It represented a big advance, as it not only cuts down the time for opening and closing a filter, but makes the work easier and free from the danger of unequally tightening each bolt. The locking mechanism represented to the Sweetland Filter what the self-starter means to the automobile today.

In getting a good perspective of the locking mechanism, the specifications must be realized. The hydraulic cylinder almost closes the lower half, so that the front gasket surface nearly touches the gasket in the upper half. It cannot close the shell entirely, as the compression of the back gasket must be in advance of the front gasket and it would be foolish to put on a hydraulic cylinder of sufficient power to fully compress it. The gap in front never should be greater than $\frac{3}{16}$ in. The locking mechanism, therefore, must first fully close the machine and then uniformly tighten the joint so as to be completely leak proof. The idea of stringing the swing bolts on a shaft so that all are operated simultane-

ously is the starting point of the mechanism. Making this shaft eccentric in the bearings is the cardinal feature of the tightening arrangement, for then the simple rotation of the shaft tightens or loosens all the swing bolts depending upon the direction of rotation. The swing bolts when loosened must, however, be lifted out of the way so that the lower half can swing back. Steel pins threaded into the shaft impinge upon lugs on the bolts and the continued rotation of shaft lifts each bolt out of the way. The amount of eccentricity in the shaft is usually a maximum at $\frac{1}{8}$ in., so that some auxiliary means is required to close the gap at the front. This is taken care of by a king bolt in the center. This bolt does not hang on the shaft like the others but rides on cams secured to the shaft. The design of these cams allows the king bolt greater play than any of the other bolts and is sufficient for it to engage the lower half. Therefore, in opening the filter all the others unloosen and are lifted away from the shell, while the king bolt holds the weight of the lower half and is still in place. The load of the lower half is then taken up by the hydraulic cylinder before the king bolt is swung out of position. This is effected by the engagement of a pin on one of the cams with a lug on the bolt. The special curvature of the cams takes care of the action of the king bolt when all of the other bolts are released from holding the lower half, but when the bolts are in engagement the cam curve is a circle. Then, it operates in unison with the others and helps tighten the joint. Simultaneously pulling on thirteen bolts so as to compress the gum-strip gasket requires considerable power, but by back gearing the shaft to the rotation of a pilot wheel plenty of leverage is provided, so that one man can comfortably tighten the joint.


Internal Manifold Pipe.—Outside of the Merrill Filter Press the Sweetland Filter was the first to incorporate sluicing discharge. The internal manifold pipe is primarily a sluicing pipe and is the basis of the sluicing mechanism in Sweetland Filters.

In many installations this internal manifold is also the overflow pipe, collecting liquor evenly through each nozzle located between the leaves. For this work the internal manifold is ideal for agitation within the filter.

The pipe is generally a standard extra heavy pipe and is located in the longitudinal cavity of the upper half. It projects through the casting and is carried through external stuffing boxes. Generally the sluicing water is fed through both ends, although when used for overflowing only one end may be capped. The sluicing nozzles are short nipples threaded into the pipe and should be of a size so that the total area of the nozzles is less than the combined area of the sluicing feed lines. When used for overflowing, especially when fibrous material is present in the liquor, the sluicing nozzles may be removed so as to reduce plugging up the holes.

The pipe being carried through stuffing boxes is rotatable and likewise capable of longitudinal motion. To facilitate the sluicing operation a self-reversing mechanism has been perfected. This is shown in Fig. 59.

Filter Leaf.—The design and construction of Sweetland leaves are probably more varied and distinctive than that of any other filter. The specifications call for a rugged construction, light weight, sufficient drainage, and uniformity so as to be positively interchangeable. Ruggedness in terms of that capable of handling and transporting is the ruggedness referred to, for to endeavor to make leaves capable of withstanding the warping action of an over-charged press would be like making a



Courtesy United Filter Corporation

FIG. 51.—Sweetland Filter—Automatic Sliding Mechanism.

Key to Parts: A.—Transversing screw fastened to pipe. B.—Screw housing carrying flanged Ratchet M and friction rim L. C.—Spacer Plate. D.—Double Ratchet Pawl. E.—Dog clamped to pipe. F.—End of pipe projecting into expansion joint. G.—End of pipe running through filter body. H.—Sliding handle fastened to pipe. J.—Friction Bar held against rim L by springs in head of arm S. K.—Projection on end of friction bar to trip T. L.—Changeable friction rim. M.—Flanged ratchet. S.—Arm carrying friction bar J which is forced against rim L by springs in head of arm. T.—Reversing Lever. U.—Stuffing box plate which holds directly against end of filter.

The mechanism operates to give a definite longitudinal travel of a fraction of an inch either side of the center of each leaf until the nozzles reach a set maximum position, when the direction is automatically reversed by tripping the double ratchet pawl "D."

bumper on an automobile that would not bend if the car collided with a large tree. Light weight is a factor in handling the leaves, especially when putting them in and removing them from a filter. Sufficient drainage is obtained in double crimped screen and providing adequate outlet to the delivery pipe. Interchangeability of leaves is paramount and a feature of Sweetland Filters and, consequently, each leaf is made to template and will vary from another in thirty seconds of an inch only.

The start of Sweetland leaf manufacture is the U sectioned rim. This is made from steel flats, which are made into U shapes and then

formed into true circles. The drainage member, generally crimped wire screen, is cut to size and fitted into the rims, fixed by riveting through sides of U shapes, or spot welding points around the periphery. The leaves are now ready for fitting. This is a combination of cast-iron spud and sheet metal welded together, the whole being attached to the leaf by spot



Courtesy United Filter Corporation

FIG. 30.—Sweetland Filter—Open.


When filter is mounted on concrete supports so that the greatest "high" every square inch of the filter surface is easily inspected. Stiffening pipe is located on top of the filter behind the leaf cap nuts and at the ends of the shell through stiffening boxes.

This construction is all done on automatic machinery, saving time and welding, so that each part is capable of quantity production and interchangeability.

The standard type of leaf is that described above but in a leaf from which all the filtrate could be drained, a bottom outlet was designed. This has a flattened tube extending to the bottom of the leaf. The exit for the filtrate is up through this tube. The rest of the leaf is otherwise like the standard leaf.

One of the clever details of design of the Sweetland filter

Outlet nipples. This is a standard pipe threading into the outlet spud and terminating in another standard thread onto which the top cap nut is screwed. Having the outlet nipple replaceable means that a crossed thread, or otherwise damaged thread, does not mean a discarded leaf. The unique part of the design, however, lies in the outlet for the filtrate. Holes are drilled through the pipe at a point opposite the outlet fittings of



Courtesy United Filters Corporation

FIG. 6a.—Sweetland Filter Leaf with Cake—Cross-section.

Each Sweetland leaf is light and easy to handle. The metal U-shaped periphery provides both drainage and stiffening to the crimped wire screen drainage member. The outlet nipple threads into the outlet casting which is secured to drainage screen and to the U shape by spot welding. The filter cloth envelopes the assembled leaf and by reason of the free drainage through the screen even cakes are built up which are easily washed and discharged.

the machine when the leaf is in the filter. This is surely a simple means of getting the filtrate out of the leaf and into the collecting manifold and yet most positive.

Putting the filter cloth on the leaves has never been improved from that used in the early stages. The bag is sewn halfway round by machine, turned inside out and the leaf inserted. The upper half of the bag is hand sewn but the sewers get as proficient as the old time sail makers and cover a leaf in less than 10 minutes. When the leaves are to be used

in machines requiring dry discharge by reverse current of compressed air, hollow cycles are riveted through the leaves on 6 or 8 inch centers so as to prevent excess ballooning of the cloth.

Operation.—The principle of operation for Sweetland filters is practically identical with Kelly filters and similar to suction leaf filters.

Leaf filtration is well defined as the reverse of bag filtration. With the latter the muddy liquor is applied to the interior of the bag and the filtering force drives the liquid to the outside, the solids accumulating on the inside. In other words, bag filtration is from the inside out. In leaf filtration the liquor surrounds the outside, the filtrate is forced into the inside and the solids accumulate on the outside. In truth, filtration is here, "from the outside, in."

It has also been pointed out that pressure leaf filtration is a modification of plate and frame press operation. If the filtration in plate presses is arrested before the cakes touch each other, the cake formation is identical with that obtained in pressure leaf filters. Leaf filters are in this sense mechanical modifications of plate and frame presses.

If the leaf is the fundamental of Sweetland filters, cake formation is the vital factor in their operation. Sufficient cake must be formed to insure complete discharge. Too much cake must not be formed or washing and discharging are jeopardized.

In cake forming the initial operation is to fill the filter with liquor and to vent the air contained in the pipe lines and machine. It is positively poor practice not to release this air, for then the air must be vented through the filter cloth, which means a back pressure so that filtration starts on the submerged parts of the leaf in advance of the upper sections. Also, it is physically impossible to vent all of the air through the leaves so that cake formation at the top of the leaf may be further retarded. Uneven cake formation is bad practice in Sweetland filters.

If uniform thickness of cake is required, it may be found necessary to provide agitation within the filter during the cake building when handling Liquors, the solids of which tend to quickly classify. This is conveniently obtained by overflowing some of the Liquor through the internal manifold.

Cake building progresses until the cake thickness reaches the economical limit. This is determined by previous experimentation or by past plant experience. In brief, it is the point beyond which the amount of filtrate obtained in the time expended is less than that obtainable by running more cycles through per day. Not having to form hard cakes, as in plate and frame press operation, makes this phase of the Sweetland filter operation distinctly advantageous.

Cake building is followed generally by withdrawing the excess unfiltered liquor lying about the cakes in the drainage channel and overflow cavity. It is possible in some installations to follow cake building with cake washing without withdrawing the excess, but such cases are exceptions rather than the rule.

The excess must be withdrawn quickly, but there must always be

Conway United Filter Corporation

FIG. 6.—Strained Filter Leaves.

Top Draining, Uncovered. Bottom Draining, Uncovered.

The Right, sturdy character of Strained leaves are prominent features. When necessary to reduce the filtrate lying within the leaf at time of the filtering or washing cycle, the bottom draining leaf is used. A flattened tube extends to the bottom of the leaf and has an opening at its base only. When reverse compressed air balloons the filter cloth sufficiently, the cloth is secured to the drainage member on 6-inch centers by hollow rivets which extend through the screen and hold both sides of the cloth.

positive pressure within the machine so as to hold the cake on the leaves. In consequence, coincident with closing the liquor valve, compressed air should be admitted to the shell and the drain valve opened.

Promptly after the liquor is drained from the machine, the filter is ready for the next operation. This may be to dry the cake or to discharge it, but more often it will be to wash the cakes free of the entrained solubles. Therefore, simultaneous with closing the drain valve the wash water valve is opened, the compressed air valve closed, and the air vent cracked. The operator now watches his pressure gauge and vents the air so that the pressure is maintained at 5 to 10 lbs. per sq. in. The wash water should be fed at a rate so that a maximum of 3 minutes is required to fill the filter with water. When water issues from the air vent the operator knows his filter is filled with wash water and can now close the air vent.

Until very recently the practice has been to use clear water for washing the cake. The idea has been that clean water assured against any enrichment or contamination and when washing to neutrality, or to low percentages, the water must be neutral or pure, or as much soluble will be entering the cake as is being extracted.

The writer has proved, however, and without a single exception, that clear water is poor practice. Clean water muddled with some washed solids from a previous run, or with some inert solid, will wash the cakes better in every respect than plain clear water. The theory is positively sound and cannot fail to work. The whole secret of displacement wash is the equi-resistant surface of the cakes. It is physically impossible to make a transfer of unfiltered liquor from a Sweetland, or any other pressure leaf filter, and maintain an absolutely equi-resistant surface on all the cakes. Partial drying, or cooling of the unsubmerged parts, changes the filtering resistance to those parts longer submerged. Where clear water passes through such cases paths of unequal resistance to its passage are set up and excess wash water and time are required if the discharged cake is to contain only the allowable soluble content. The solids of the muddled wash waters are filtered out and offer a resistance to the flow. As more water penetrates the cake more solid accumulates, more resistance is set up until the positively equi-resistant surface is regained. The amount of solid is determined locally and largely in relation to the rate of flow during washing. If this is high, the solid content can be greater than if it is low. In the majority of installations the rate of flow on washing increases as it progresses, due to the extraction of a viscous or dense liquor and substituting a more fluid wash water whereby the cake resistance decreases. This means, therefore, that the time extension required with a muddled wash water is trivial and negligible.

It is interesting to note the attendant advantages of the muddled wash water. Drying cakes in leaf filters is primarily dependent on the volume of the voids in the cake. If the cake is dense and the voids low the compressed air can effectively remove much of the liquid. Compacting the cake is obtained only by higher pressures than employed during cake

building. Without muddying the wash water, increasing the pressure of washing intensifies unequal washing so that better drying is obtained at a sacrifice of the washing efficiency. With solids suspended in the water the pressure can be increased with absolute freedom, as irrespective of the pressure the *equi-resistant* surface is maintained. Also, it was found that when handling an organic liquor, a $\frac{3}{4}$ in. cake was an economical maximum, but by having washed solids in the wash water, a cake $\frac{5}{8}$ in. could be built up easily and the latter offered no trouble in automatic dry discharge, while sluicing was the only way to get rid of the $\frac{3}{4}$ in. cake. The scheme, simultaneously, aids washing, drying and discharging, to a greater or less degree with every installation.

Washing the cake is completed when the operator finds his wash filtrate tests to the limit set for him. This may mean hydrometer readings, neutrality with litmus or other indicator titration, or by color. Time control on washing is practiced in some plants but generally because excess sweet water can be handled without evaporation. Leaving the matter of shutting off the wash water to test by the operator is, of course, putting the control directly in the hands of the operator, but it is significant how the average operator feels this responsibility and lives up to it. Some plants have put the filter foreman in charge of mixing the batches and evaporating or handling the filtrate and inaugurated a system of bonus and demerits on cake analysis. Such an arrangement insures the right sort of control and high filter efficiency.

When washing is concluded, the excess water must be drained from the machine and the same care is required as when draining the excess unfiltered liquor.

Washing is usually succeeded by drying. Even where the cake is run to waste it is good practice to dry it for a few minutes, as this tends to force out all liquor within the leaves and outlet pipes, the soluble content in which will often more than pay for this work.

Drying in Sweetland filters is accomplished by filtering compressed air through the cake and displacing the liquid in the cake. Substituting a gas for the liquid in the voids of the cake allows the particles of the cake to assume new positions and, as the tendency is toward closer formation, the contraction in volume produces cracks in the cake. At this point further drying is waste of compressed air. Good drying effect is, therefore, dependent upon delayed cracking of the cake. Cracks are delayed when the voids of the cake are small, due to good compacting of the previous cake building and washing operations.

It is essential that the withdrawal of the excess wash water be as quick as possible so that the cakes maintain as near an *equi-resistant* surface as possible. The pressure during withdrawal should not be higher than necessary to keep cakes on the leaves.

Discharging follows the drying operation. Experience has proved that discharging during cake building, with the idea that discharged cake will fall to the bottom of the filter and leave cleaned filter cloth for further filtration, is impractical. Only complete discharging is effective and

FIG. 6.




FIG. 6a.—Layout Scratched Filter—Dry Discharge.

1.—Valve controlling supply of pump to be filtered (this turns pump relative to a mixture of solid and liquid). 2.—Valve controlling supply of water for washing solids mixture out of filter cake. 3.—By-pass valve. 4.—Main feed valve to filter. 5.—Drain-off valve to be opened before opening filter. 6.—Compressed air for discharging cake (A. H. pressure). 7.—Closely filtered water for cleaning. 8.—Closely filtered valve. 9.—Valve for admitting compressed air to filter body. 10.—Swing bolt handle (for locking filter). 11.—Vent valve. 12.—Supply of hot or cold water for washing filter cake in contact tubashes. 13.—Trough containing main supply of pump. C.—Centrifugal pump for handling pulp and wash water. (Note that if pump used at this point is capable of exerting more than 30 lbs. pressure per square inch on the filter, a relief valve should be installed in the main feed line between valve 4 and the filter, and this valve should be set for 30 lbs.—the maximum operating pressure of the filter.) D.—Trough for clear filtrate.

A cake hopper is shown beneath the filter, arranged to connect with a chain or suitable conveyor for taking away the cake as it is discharged from the filter. The sludge pipe is capped off at both ends and no sludge pipe handle is used.

The essential of a well-designed layout is the convenience of valves that must be operated simultaneously. Where impractical to locate all valves in a cluster those valves which must be opened coincident with the shutting of another should be close together.

this is practical only when plenty of room is provided for the disengagement of the cake.

The Sweetland filter was the first pressure leaf filter to be operated as a sluicing discharge machine. As such the filter is not opened as the cakes are broken up and flow away as solids suspended in the sluicing water. Sluicing is effected by the projected streams of water under high pressure issuing from the nozzles in the internal manifold. These streams are designed to project at right angles to the manifold and apparently parallel to the surface of the leaves. The streams, however, really baffles from one leaf to the adjacent leaf and have sufficient force to cut the cake. The manifold is rotatable and capable of longitudinal motion so the streams are made to sweep across every square inch of filter surface. With some materials, discharge is aided by putting reverse compressed air into the leaves while sluicing. Steam is seldom used nowadays as the sluicing water condenses it too freely. Different plants hold different views as to the value of pinning the cloths to prevent ballooning. Some claim that the baffled streams chatter an unsecured cloth and that this helps disengage the cake. Others hold that the purging action of reverse compressed air is too valuable to lose and pinning the cloths prevents ballooning that would otherwise block the sluicing streams from reaching the lower sections of the leaves.

Dry discharge from the Sweetland filter is more positively obtained than with any other pressure leaf machine. First, by having the leaves stationary and the lower half swinging from a longitudinal axis, prematurely discharged cake does not harm the leaves. Second, by opening the filter so that every square inch is observable, there is but little excuse for a filter being but partly cleaned. The operator is to blame for a poorly discharged filter.

Reverse current of compressed air is the standard means of discharge. Steam can be substituted for materials that are difficult to disengage from the leaves as the condensed steam often lubricates the surface of the leaves and aids discharge. Reverse water is seldom effective unless the filter is closed and the water level allowed to rise. This, of course, is no longer dry discharge and if such measures seem necessary it is a good indication that the filter cloth used is too dense.

It will often happen that the bulk of the cake is discharged but parts of the cake refuse to fall off. Time is saved by taking a long handled paddle and dislodging these by hand.

The time required for discharging varies with the material, but with good operation it should not exceed 5 minutes. It is, however, time poorly saved to restart the filter without first inspecting and making sure all the cake has fallen.

Layout.—The proper set up of filter piping layout and arrangement of valves has been given the consideration worthy of this detail.

The factors resulting in success or failure of an installation are many times small and presumed inconsequential. The matter of a leaky inlet valve has been known to cost a plant more than a hundred tons of coal in the evaporation of excess sweet water. Failing to mount the

filter on high enough foundations prevented the operator from conveniently inspecting the filter after discharging and inadequate discharge accumulated until the leaves were warped out of shape, when washing results were very poor and discharging worse. Convenience of valves for simultaneous operation is always imperative in handling pressure leaf filters, and if some of the control valves are out of reach, the cleverest operator in the world could not get the best out of the machine.

In light of the above, the layout recommended by the manufacturers is not an ideal arrangement furthered by them but the correct set up as found by years of experience. It should be followed with as little deviation as possible.

The cardinal essentials in erecting a Sweetland filter installation are (1) To mount the filter so that the joint of the two halves is "eye" high from the floor or operating platform; (2) that pipe lines be amply large especially drain lines; (3) that valves and gauges shall be convenient to the operator; and, (4) that the operator shall be able to observe filtrate discharge and, where practical, the levels in receiving tanks, so as to prevent overflowing the tanks.

Advantages.—As a leaf filter, the Sweetland Clam Shell Filter embraces all the advantages of the leaf system and by reason of the mechanics employed obtains these advantages to a greater extent than is obtainable in any other leaf filter. The general mechanical arrangement is, therefore, the leading advantage of Sweetland filters. In no other machine are the details of convenience for the operator so well worked out. This is the ground work on which so many attendant advantages are dependent and are made possible.

The paramount advantage of leaf filters is the washing of the cake by displacement although the popular advantage is the labor saving. The even distribution of wash water with the minimizing of excess space accounts for the better washing results obtainable on the Sweetland filters.

The equal area of the filter leaves, and the consequent even distribution of the reverse compressed air largely accounts for the automatic discharge of the solids with the minimum hand labor. Shucking the solids from the leaves is possibly the same of automatic discharge from this type of filter and a distinct advantage this machine holds over all others.

Their wide adaptability and convertibility is another feature of Sweetland filters. Ability to cease filtration at the economical limit of flow, rather than having to wait for the cakes to build solid and the ease of discharging the cake, make the Sweetland a well-nigh universal filter. Taking out intermediate leaves and plugging up the openings with stop-off bolts converts a Sweetland filter from a small caking machine to one adapted to handle heavy cakes.

Having all the leaves of the same size and interchangeable means that any spare can be substituted for any faulty leaf. There are more leaves for a given filter area than is required in a Kelly filter, so that each leaf is light and easily handled by one man. The ease of removing and replacing the leaves makes it practical to substitute a spare for an




FIG. 68

Courtesy United States Corporation

FIG. 6a.—Layout Standard Filter—Straining Discharge.

L.—Valve controlling filter after filter. 2.—Valve controlling heavy filter and filter valve to filter. 4.—Straining water valve—water pressure 70 to 80 pounds per square inch. 5.—Drain valve for unfiltered material and bottom. 6.—Strainer basket. 7.—Clean filter valve. 8.—Strainer basket. 9.—Vent valve. 10.—Compressed air valve (5 lb. pressure). 11.—Swing hot draft bundle (for loading filter). 12.—By-pass valve for returning excess unfiltered material. 13.—Suspension joint. Note that ca. 17' and 18' allows no expansion joint is required for both end of the filter as shown on the drawing, as a special fitting is supplied with the filter. 14.—Compressed air valve to admit in cleaning filter bags (pressure 5 lb. per square inch). 15.—A-shower. 16.—Baffled connection used for water inlet in special work where a cone is washed. 17.—Drain (to sewer) for straining.

D.—Pressure gauge.
A.—Tank for holding filter wash with filter all. This tank of the same height as tank B and of such a volume as to accommodate approximately two to three times the amount of filter required to fill the body of the filter. B.—Main portion of filter required to fill the C—Centrifugal pump capable of handling from 30 to 50 pounds pressure per square inch in the filter.

Note that where another style of pump is used care must be taken to see that the normal operating pressure, i.e., 50 lb. per square inch—on the filter body is not exceeded. With direct acting pump pressure, pressure, i.e., 50 lb. per square inch—on the filter body is not exceeded. With direct acting pump pressure, or the like, we would strongly recommend the insertion of a relief valve on the main feed pipe just before filter A, orders for filter body. D.—Tank for clean filtrate. E.—Tank for coarse wash. This tank and the dotted piping are only recommended on large installations. Where several filters are operated and a common tank, it can be used to take the excess from the whole station, a pump or other means of taking material from tank E to tank B must be provided. Where several filters are handled in a battery the piping and arrangement of tanks, etc., can be considerably simplified.

The electric arrangement (details, valves, etc.) is omitted so that only wash filters are drawn to the writer.

imperfect one and an easy job to remove all the leaves when they need removing.

With the gasket joint elevated "eye high," the opened filter can be inspected most conveniently by walking along the machine. Every square inch of filter cloth can be searched to make sure all cake has fallen and with a long handled paddle any remaining is easily dislodged. This accessibility to the filter cloth is a practical advantage of far-reaching importance.

Having the leaves fit comparatively snugly to the shape of the filter, and otherwise reducing the excess space within the filter, makes the transfer of unfiltered liquor a short operation reducing the hazard of losing the equi-resistant condition of the cake. Where uniform cakes can be counted on run after run, this reduced excess liquor makes possible the simplest washing operation of any leaf filter or filter press, by introducing the water without draining.

The quick opening, positive gasket joint, individual control of the filtrate from the leaves and the compact let up of this filter are unsurpassed in any modern filter.

The stationary leaves and the movement of the opening lower half away from the leaves gives the Sweetland a big advantage over the Kelly when handling thick cakes which fall from the leaves when the pressure in the filter is released.

The absence of moving parts makes possible lining the Sweetland with chemical lead to prevent corrosive attack, although this lining is a bigger success when handling cold liquors than with hot materials. This feature is unique in pressure leaf filter design.


Drawbacks.—The operation of the Sweetland is cyclic and therefore intermittent. A machine capable of continuous operation has inherent advantages over intermittent operation. This can be called a drawback to the Sweetland filter, but it must be borne in mind that few continuous filters are now working on more than $\frac{1}{2}$ submergence which means that for $\frac{1}{2}$ of the working time they are not filtering. Thus, it is possible to operate Sweetland filters with the time of filtration greater than $\frac{1}{2}$ of the total cycle when the actual filtering work of each square foot of filter cloth is greater than with continuous filters. Again, pressures in excess of those obtainable with vacuum filters are used in the Sweetland and, with some materials, this gives a greater flow per total cycle than that obtainable in continuous. Offsetting this, however, continuous filters are filtering for a much shorter period and, consequently, within the high points of the rate of flow curve making their production more efficient. Also, for the majority of materials handled in industrial work, 10 lbs. per sq. in., or 20 in. of vacuum, is quite enough filtering force to get a high output.

The actual labor involved in the operation of a Sweetland, or a battery of Sweetland filters, is not a big item per ton of output and does not give a big advantage to continuous filters. However, the operation is dependent upon the personal efficiency of the operator and in this respect continuous filters have an advantage over the Sweetland. This

Courtesy United States Government

FIG. 64.—Battery of Standard Filters.

When substituting Standard Filters for long filters in sugar refineries the cleanliness of the station is in strong contrast with the conditions obtaining with long filters. Each filter is an independent unit with its own control valves, the arrangement of which, however, is similar for each unit.



point is emphasized in each detail of the cycle. Failing to check filtration before the cakes build together depreciates washing and discharging the cakes. Stopping cake building too soon leaves too much excess liquor and the cakes may not have enough mass weight to discharge well. Failing to transfer the liquors properly means losing the equi-resistant cake. Stopping the washing too soon leaves soluble in the cake. Washing too long means excess weak liquor. Discharging should be automatic but, if not followed by thorough investigation and dislodging any cake remaining, succeeding runs show lower results. This control is not required of an operator with continuous filters.

The means of drying the cake in Sweetland filters is not comparable with the cake compression in plate and frame filter presses, or with continuous filters equipped with filter cake compressors. This deficiency is one of the greatest drawbacks to the Sweetland filter tending to narrow its field of application to those cases where the solid does not have to be subsequently dried to a powder.

Applications.—The Sweetland filter has been applied to such a variety of materials and uses as to well deserve the title of the universal modern filter. It has, however, particular usefulness in a few fields where it tops all competitors and where its advantage is likely to be continued.

In handling liquors heated close to the boiling point, or other volatile liquors, the Sweetland is the superior filter now on the market. There are no hot plates and frames to handle as in the case of the plate and frame press on this work and no vaporization troubles as exist in vacuum filters.

For supersaturated, or scale forming liquors the Sweetland filter installed with a back pressure on the leaves cannot be approached. A closed delivery plate and frame press is not comparable to an open delivery press and no progressive plant will use a plate and frame machine where a Sweetland can be installed. Vacuum filters are out of the question for this duty.

Where slaking discharge is permissible the Sweetland is far and beyond all others as a clarifier of those industrial liquors containing a relatively low solid content and resistant so as to preclude long filtering cycles. The ease of discharging by the automatic slaking mechanism is in contrast with the miserable job of cleaning plate and frame presses on this duty. It may develop that vacuum discharge coupled with high submergence may compete with Sweetland filters on this work, but, at this writing, such is not a commercial and demonstrated success.

Sweetland filters still maintain a hold on all fields in which exacting wash of the cake is required. To see so many of these filters failing to hold their own in the beet sugar industry is not encouraging, but in each instance where washing is no longer attempted, the filter being used as a clarifier and thickener only, washing would still be a success if a mud-died wash were used. It is to be expected that muddying the washing liquid will allow these filters to regain their reputation as displacement wash machines and this will not only maintain their fields but increase them as well.

Summary.—The excellent results obtained with Sweetland filters wherever installed in competition with frame presses established the value of pressure leaf filters. In the beet sugar field uneven cake formation became chronic in some regions so that Henri Vallez, as superintendent of a beet sugar plant, hit upon the idea of rotating the leaves during the filtering operation, when the unevenness would be distributed around the periphery of the leaves. Upon this idea he developed the Vallez filter, which is the subject of the coming chapter.

Chapter V.

Section III—The Vallez Filter.

Pressure leaf filters of the Kelly and Sweetland design created a favorable impression when first introduced into the beet sugar industry that was close to being sensational. The opportunity of supplanting plate and frame presses in such quantities has never been equalled.

After the first wave of enthusiasm, weaknesses in their operation crept out and refinements were being suggested from practically every plant. In most cases the improvements were minor changes but Henri Vallez, then Vice-President and Superintendent of the Bay City plant of the German-American Beet Sugar Company, sensed the greatest drawback to these filters. He tried every suggestion to decrease the tapering effect on the cake formation due to inadequate circulation in the filter. He was opposed to overflowing quantities of liquor that seemed to him excessive in order to obtain the necessary agitation. He devised the idea of mounting each leaf on a central rotating shaft whereby the tapering effect would not be localized. Rotatable leaf filters had been invented prior to the Vallez filter but the mechanics employed offered some patentable features protected by Vallez. This idea was the basis upon which Vallez launched into the filter game.


Design.—If the rotatable leaf was the foundation upon which the Vallez filter was built, it is natural that the rotating shaft and leaves are the leading features of the design. The shaft is a piece of very heavy tubing key seated for a length equal to the overall length of the leaves when assembled. Holes are drilled through to allow the filtrate from the leaves to feed into the shaft. The leaves are mounted on cast-iron hubs which slip over shaft and are held rigid to the shaft by being keyed to it. These hubs are made of varying widths corresponding to the leaf spacing and abut one another at companion flanges. The entire set of leaves are clamped together by couplings on each end. Positive alignment is provided by means of four angle irons bolted to the periphery of the leaves at 90 degree intervals.

The leaves, or rather the bare frames, are made extra rigid so as to insure positive plane surfaces and to eliminate any tendency toward warping. Flat surfaces are easier to clean—the secret of the good discharging obtainable from this filter. Instead of using one screen these leaves are made with two perforated plates separated by a coarse screen. This combination gives admirable drainage and a smooth surface over which the filter cloth is laid and clamped to the frame.

Comley Valve Safety Valve

FIGS. 65 and 66.—Valve Filter—Nitrate Manifold and Filter Element.

All the leaves are strong on the nitrate manifold which is drilled to allow free passage of filtrate to the interior. The rigid leaves are separated by flanged collars and aligned by angle from which also act as agitator profiles.



In order that the leaves shall be rotatable the shaft is flanged to extensions which pass through stuffing boxes in the shell and terminate at one end in a male and female expansion joint and at the other in a closed end to which the worm gear is fixed. The stationary member of the expansion joint is fitted with the customary outlet connections and piping for reverse current, etc.

After the filtering element the next distinctive feature is the discharging mechanism. This is principally a screw conveyor located in the bottom of the lower part of the filter, one half of the conveyor being right and the other half left hand, with the rotation such that the cake is carried to the center of the machine. Here a large opening is provided, the cap of which is a modified manhead cover capable of being quickly opened or shut. The trough receiving this conveyor does not sweep up the sides of the machine as the aligning angles are effective feeders of cake to the trough.

The shell of the machine is divided longitudinally on the center axis. Since the machine is not opened for discharging, the gasket joint is made up with standard bolts. The upper half is removable and the lower half stationary. When removing the upper shell a chain fall or other hoist mounted on a mono-rail trolley is brought over the machine and lifts the shell up and away from the filter. This exposes the entire filtering element and with the hoist it can be disconnected and removed.

The observation doors in the upper half are interesting. These consist of two hinged plate covers and are held pressure tight by quick closing swing nuts fitted with circular handles. These are conveniently opened and give the operator a chance to inspect the progress of the discharging operation as effectively as though the whole filter were opened. This is truly a simple scheme but the mechanics are as truly ingenious.


Inasmuch as the leaves rotate the specifications of a sluicing pipe are very simple. The throw of the sluicing water is only one half the diameter of the leaf. The nozzles do not need to move and each side of the leaves can have a separate nozzle playing upon it. The sluicing pipe can be located at the zenith of the travel, so that gravity works in line with the eroding effect of the water jets. For dry discharge compressed air, or steam, dislodges the cake from relatively free filtering material making possible an approximation to dry discharge.

Another simple, but clever detail, is a continuous density tester. When washing sugar juices or other solubles from the cake the progress of the wash is determined by sampling the filtrate in a flask or graduate and reading a hydrometer spindle placed in the liquid. There is danger of breaking a hydrometer just when it is needed most and there are other annoyances that make it worth while to obviate this nuisance. In designing a continuous sample it is necessary that the liquid shall be a true sample of the filtrate flowing at that instant, it being necessary that the velocity of flow shall not affect the buoyancy of the spindle and that the spindle shall not adhere to the side of the receptacle and thus

Cutting Veller Safety Filter

FIG. 67.—Veller Filter—Observation Door Open.

Heavy construction marks the mechanical design of Veller Filters. The filter leaves are rotatable through an external worm and worm gear. The discharge of the cage is observable through the opening provided under the observation door. The discharged cage is propelled to the center of the filter and dropped out of the member at the bottom.



INDUSTRIAL FILTRATION

influence the reading. These specifications have been covered in the Vallex filter by taking a small pipe connection from the under side of the filtrate out to the tester proper. The tester is located with its overflow, which bleeds into the liquor tank, at about one foot under the filtrate shaft, thus providing head for the continuous supply of fresh filtrate. The diameter of the test pipe is of sufficient increased diameter over the diameter of the sampling pipe to reduce the velocity and still of small enough volume that its contents change quickly. The overflow from the internal testing tube is caught in a circular outer trough to which the overflow line is connected.

The cake tester used in the Vallex filter comes closest to being a true indicator of the cake thickness of any ever devised and tried out. Its principle is simplicity itself, i.e., the outward movement of a paddle resting on the cake as the thickness of the cake increases. This movement is magnified by the deflection of an indicating needle located outside the machine. A calibrated scale behind the needle reads directly the cake thickness and is a most convenient guide to the operator. The successful operation of this indicator is in contrast to those tried out in other filters. The secret of success lies in two main factors, first, the paddle truly rides on surface of cake; and second, the filter medium is more representative of total area. With stationary leaves any automatic indicator depends upon the cake growing in excess of the distance between filter cloth and the setting of the indicator's plate. When the cake exceeds this distance there is set up a difference in pressure on the exposed side of the plate and the packed side. This excess pressure forces the plate into the cake and this movement is that used for indicating to the operator the end of the cycle. But this indicates the cake at one point only.

The positiveness and accuracy of such indicators is a function of the resistance set up by the material being filtered and, consequently, works better with some slurries than with others. In the Vallex filter, the paddle is set against the filter leaf and is forced away from it as filtration progresses. This action takes place because the cake is constantly moving under the paddle and pushes the paddle away instead of letting any cake accumulate around it and force it inwardly. Of course, if this indicator is to be equally good for hard and soft cakes, the force necessary for its movement must be slight and this has been taken care of in the design.

The other strong point in the Vallex indicator is the better cleaning of the filter cloth under the indicator paddle. In the other pressure leaf filters the operator had to clean by hand the cloth under his indicator. Depending upon the operator this might mean that the cloth was better cleaned or not as well as that throughout the machine. This variable was the cardinal weakness of these indicators. In the Vallex the indicator is situated near the periphery of a leaf and this part of the leaf is subjected to the strongest action of the slicing nozzles and hence more assuredly cleaned. Of course, there is a possibility that the particular nozzle cleaning this leaf may be plugged, or otherwise in-

Cantley Paper Filter Mill

FIG. 61.—Battery of Valve Filters.

Not having to open the filter to discharge the cake makes it possible to locate the filters on close contact. One overhauled fine shaft serves, by means of separate belts, to rotate the leaves of each filter. Head room over the filter for a hoist suspended from motor-end enables the upper half to be removed when the filter element has to be replaced.



influence the reading. These specifications have been covered in the Vallex filter by taking a small pipe connection from the under side of the filtrate out to the tester proper. The tester is located with its overflow, which bleeds into the liquor tank, at about one foot under the filtrate shaft, thus providing head for the continuous supply of fresh filtrate. The diameter of the test pipe is of sufficient increased diameter over the diameter of the sampling pipe to reduce the velocity and still of small enough volume that its contents change quickly. The overflow from the internal testing tube is caught in a circular outer trough to which the overflow line is connected.

The cake tester used in the Vallex filter comes closest to being a true indicator of the cake thickness of any ever devised and tried out. Its principle is simplicity itself, i.e., the outward movement of a paddle resting on the cake as the thickness of the cake increases. This movement is magnified by the deflection of an indicating needle located outside the machine. A calibrated scale behind the needle reads directly the cake thickness and is a most convenient guide to the operator. The successful operation of this indicator is in contrast to those tried out in other filters. The secret of success lies in two main factors, first, the paddle truly rides on surface of cake; and second, the filter medium is more representative of total area. With stationary leaves any automatic indicator depends upon the cake growing in excess of the distance between filter cloth and the setting of the indicator's plate. When the cake exceeds this distance there is set up a difference in pressure on the exposed side of the plate and the packed side. This excess pressure forces the plate into the cake and this movement is that used for indicating to the operator the end of the cycle. But this indicates the cake at one point only.

The positiveness and accuracy of such indicators is a function of the resistance set up by the material being filtered and, consequently, works better with some slurries than with others. In the Vallex filter, the paddle is set against the filter leaf and is forced away from it as filtration progresses. This action takes place because the cake is constantly moving under the paddle and pushes the paddle away instead of letting any cake accumulate around it and force it inwardly. Of course, if this indicator is to be equally good for hard and soft cakes, the force necessary for its movement must be slight and this has been taken care of in the design.

The other strong point in the Vallex Indicator is the better cleaning of the filter cloth under the indicator paddle. In the other pressure leaf filters the operator had to clean by hand the cloth under his indicator. Depending upon the operator this might mean that the cloth was better cleaned or not as well as that throughout the machine. This variable was the cardinal weakness of these indicators. In the Vallex the indicator is situated near the periphery of a leaf and this part of the leaf is subjected to the strongest action of the sluicing nozzles and hence more surely cleaned. Of course, there is a possibility that the particular nozzle cleaning this leaf may be plugged, or otherwise in-

Courtesy Valley Safety Filter

Fig. 68.—Battery of Valley Filters.

Not having to open the filter to discharge the cake makes it possible to locate the filters on close centers. One overhauled fine shaft serves by means of separate belts, to rotate the leaves of each filter. Head room over the filter for a hoist suspended from motor-end enables the upper half to be removed when the filter element has to be replaced.



capacitated, when the area under the paddle is not equal to the average area in the filter.

Therefore, the Vallex indicator is the best guide devised for determining cake thickness, but for a general rule it should be considered a guide and not an infallible indicator.

Operation.—The distinctive feature of operating the Vallex filter is the rotation of the filter leaves during each step of the cycle. This simple modification has a most interesting influence on the operating features and should be contrasted with the operation of the older Kelly and Sweetland pressure leaf filters.

The initial step in cake building is filling the filter. This should be accompanied by good distribution and in this filter the inlet is a manifold having four openings into the filter evenly spaced. The filter leaves are started rotating, at a speed generally of $1\frac{1}{2}$ revolutions per minute, and the four side angles function as agitator paddles helping to maintain uniform slurry. In especially quick settling materials it is possible to rotate the screw conveyor and underflow the thick material brought to the center.

When the press is full, liquor running from the vent, filtration commences. The leaves continue rotating and the filtrate flows from the central shaft to the receiving tanks.

As soon as the cake has accumulated to the economical thickness determined by experience, with the aid of the cake indicator, filtration ceases by shutting off inlet valve and turning on compressed air to top of filter. Simultaneously, the return drain valve should be opened and closed after the liquor is entirely drained from the filter. The wash water valve is turned on, the compressed air closed and the vent cracked so as to let the air out of the filter.

It is well to note what effect rotation of the leaves has had so far in the operation. First, the side arms as paddles helped agitation and this of itself decreases uneven cake formation. Next, the leaves rotating are constantly passing through such thick slurry as may persist at the bottom and such thin as remain at the top. This alternates travel through thick and thin averages very well with the slurry obtaining at the center so that the cake thickness is practically the same over the entire area. When withdrawing the excess the exposed area is above the liquor level but this continuously moves into the liquor and out again. In consequence, the air drying effect is minimized. This is, of course, equally true as the wash fills the machine.

Therefore, with rotating leaves a more uniform cake is built up and a cake free of air cracks or other paths of short circuit is presented to the wash water. Forming and maintaining equl-resistant cakes is vital to good washing and a feature of the Vallex filter.

Washing is simply the percolation of the wash water through the cake and displacing the soluble in the cake. While the cakes in the Vallex filters approach the condition required in the application of the theory of displacement wash, still, the matter of valve control during draining is one of the individual operator's efficiency. To overcome

any shortcomings on the operator's part the wash water should be muddled with washed cake from previous runs, so that washing becomes the filtration of water from washed suspended solids. This filtration reforms equil-resistant surfaces and insures equal percolation of the wash water and hence uniform displacement of the soluble.

When the filtrate shows the desired limit of soluble, as determined by the hydrometer spindle, washing ceases with shutting off the wash water, turning on the compressed air and opening the wash drain valve. When all the water is out, the compressed air is opened up and the drain closed.

Drying the cakes is, in effect, filtering compressed air through the cake. Note that the rotating leaves are again a feature, for the premature drying effect at the top of the leaves is minimized in that the upper part of the leaves tending to dry first rotate into the draining and are rewetted. This action, combined with the uniform cake and equil-resistance preserved by the muddled wash, enables the drying effect of the compressed air to function better than is the practice with stationary filter leaves.

Discharging the cake from the Vallez filter is undoubtedly the spectacular feature of the operation of this filter. In stationary leaf filters dry discharge by reverse compressed air generally means that the bulk of the cake falls at one instant and often with sufficient force to splash and spatter outside of the hopper. This means that cleanly conditions about the filters are hard to maintain. Only when skiving is used in Sweetland filters is an approach made to the cleanly discharge obtainable from the Vallez filter. The secret of this is the discharge without opening the filter. The cake is dislodged by reverse compressed air, assisted by compressed air streams from the skiving nozzles for dry discharge or water from the nozzles for wet discharge. The cake falls to the bottom of the machine and fills the hopper of the screw conveyor. This scrolls the cake to the center of the machine from which it falls through the large opening into another outside conveyor or refuse pipe. The side arms on the filtering element now act as scrapers pushing the cake into the conveyor, so that it is continuously kept full until all the cake is removed.

It is usual and good practice to open the inspection doors and through them note the progress of the discharge. This has the added merit of letting the operator inspect the cake prior to starting the discharge, so that he can be sure all cloths are filtering uniformly and that the cake tester is properly indicating the cake thickness.

The operation of the Vallez filter is just the same in principle to that of the Kelly and Sweetland filters but, whereas there was some modification in handling the Sweetland over that in working the Kelly, the Vallez offers even more variation. The rotating leaves is the basis of the difference, but the effect of the rotation surely reduces the skill required of the operator and makes uniform results easier to obtain. We must appreciate Vallez's vision in perfecting the mechanics required to make a workmanlike job of making all the leaves rotatable so that

the advantages of rotary leaves could be demonstrated. Successes like this mark true progress in the art of filtration and are forcible examples of the value of relatively simple ideas. If Vallez was not the pioneer in rotary leaf filters he is the sponsor for their successful operation in the beet sugar industry and deserves immense credit for this monument to his ability.

Layout.—The layout for this filter does not vary greatly from the layout for Sweetland filters as regards piping of supply lines and filtrate discharge, save that connections can be made to the bottom half, which in the Vallez filter is not movable. The cake discharge being from the man-hole opening allows the machine to be set up with only a small clearance between floor and bottom of filter.

The feature of the layout is the drive for rotating the leaves during the operation of the filter. This can be a belt drive from a line shaft or through worm and gear reduction direct from motor.

Sufficient headroom must be provided in order to lift the top half off by block and fall or crane carried on a mono-rail. This half has to be removed when the leaves require recovering or renewal.

Advantages.—The rotating leaves decrease tapering cake formation and more uniform cakes are presented for better washing and discharging.

Holding the sluicing nozzles in fixed position and rotating the leaves against the sliding streams is the most positive sluicing arrangement in any filter yet devised.

Scrolling the cake to a central opening makes dry discharge a cleaner operation than is obtained with any other pressure leaf filter.

Discharging the cake, either by wet or dry methods, without opening the press is an advantage, not only in time and labor saving but in maintaining positive leakless gaskets.

The locked filter is, in effect, a closed container so that insulating against heat losses is practical and a true advantage of the Vallez filter.

Drawbacks.—The mechanical complications involved to gain even cake formation, the primary function of the Vallez filter, are drawbacks inherent in the machine.

Inaccessibility to the filter medium for renewals, inspection or repairs is fundamentally a weakness in design appearing as a drawback of real importance when handling difficult filtering materials.

There are too many bolts used in the design of this machine for chemical liquors corrosive to the threads and heads. This is especially true in respect to those bolts used in the rims of the filter leaves.


Stringing the leaves on one central filtrate shaft requires good workmanship in the assembly of the leaves, for any defect cannot be isolated but requires removing the entire filtering element.

The overhead crane, or trolley, requires space and structural supports that add to the complications of this machine.

Applications.—For handling calcium carbonate cakes in beet sugar plants the Vallez filter has established a pronounced success. The character of work required here typifies the class of work to which the Vallez filter is especially applicable. Any liquor which can be modified

Cutting Valve Filter Frame

FIG. 69.—Layout Valler Filter.



to parallel carbonation liquors falls in this class. As a straining filter it has application as a clarifying filter wherever the solids can be discharged wet.

Summary.—The Vallex filter is the latest of pressure leaf filters and represents a development evolved from actual plant operation with older pressure leaf filters that proved weak in practice. It is a striking example of the power of constructive criticism in developing a new filter as well as a challenge to manufacturers who fail to maintain a constant research in order to better their machines.

The cyclic operation of this and all pressure leaf filters is in contrast with the continuous operation of automatic filters. These machines are cyclic in respect to the work done by each filter compartment but, being free from actual valve manipulation by the operator, automatic machines are advances in the art of filtration.

LIBRARY

Chapter VI.

Rotary Vacuum Filters.

In all our preceding discussions, each filter has been intermittent in its operation, requiring an operator to change from filtering to washing, to discharging, etc. Automatic continuous filters, therefore, are a step forward since they require no labor in the operation of valves switching from cake building to washing or drying or discharging. The rotary filter is continuously filtering and, at the same time, continuously washing and discharging, there being no interruption in changing from one operation to another.

Rotary suction filters are not the latest development in the modern filters, for even before George Moore developed his suction leaf and then his rotary filter, rotary continuous filters were working on free-filtering salts. These machines were, however, confined to only the very free-fast filtering material and those filters starting with Moore's rotary; the Oliver; the Portland; and the American continuous, are capable of handling a greater range of material.

The modern rotary continuous filter is designed with the idea of subjecting $\frac{1}{3}$ of the filter area to work of filtration, $\frac{1}{3}$ the filter area to washing and drying, and the balance $\frac{1}{3}$ to discharging. These fractions are of course variable, but in a given rotative speed the time allotted for filtration is seen to be less than half the time required for the total cycle. In consequence, materials capable of building up a cake $\frac{3}{4}$ in., or greater, in thickness in from 1 to 4 minutes' actual filtration, represent materials on which these filters are practical. Where a material will build up a cake greater than $\frac{3}{4}$ in. thick, the rotative speed can be varied so that the time of filtration is confined within the limits of the high filtering rate of the material. Here is one of the decided advantages of this type of filter too often overlooked.

The following chapters will deal with the *single compartment* drum filter; the Moore filter and its descendant, the Zenith filter; the Oliver and the Portland; and American Continuous Filter.

The *single compartment* machine is the old original type and the others,—the *multiple compartment* filters,—are modern filters based on one principle and differing each from each in mechanics only.

The single compartment machine is characterized by the absence of any control valve and by the fact that the scraper never cleans all of the cake from the filter surface. The Moore, and Zenith, resemble the more familiar Oliver and Portland drum type filter, but are made with the

scraper *not* resting on the wire-winding on the drum. The Oliver and Portland filters are equivalent machines, so that each is characterized by the scraper *resting on* the wire-winding of the drum. The American continuous is a sectionated leaf filter, the leaves being mounted at right angles to a central shaft so that filtration takes place on areas distributed transversely to the axis rather than on the periphery of a drum.

It is understood, then, that the following discussions on these respective filters are sub-sections of the general subject—Rotary Vacuum Filters.

Chapter VI.

Section I—The Oliver Filter.

The first continuous drum filter had been long in operation in the alkali industry (handling sodium bicarbonate crystals), even before George Moore developed his design, which was to prove first of the modern filters. Modern filter development may well be dated from Moore, because he first hit upon a scheme truly better than the time-worn plate and frame press.


The early drum filter was too limited in application to be a significant step forward in filter progress, but its differences from earlier presses made it interesting, nevertheless. It was a single compartment drum machine, with a perforated periphery covered with filter cloth. The ends of the drum were made water and air tight, so that a pipe, extending through stuffing boxes in the hollow trunnions of the drum, and leading down to the low point of the drum, was used as the exhaust pipe for air and filtrate. In operation some cake had to remain on the cloth after the drum passed the scraper, or else the suction would violently pull air through until that part was again immersed. Such a filter is limited to only the free filtering material, for the cloth must be completely cleaned where the filter handled anything below crystalline solids. In order to overcome this air short circuit the cleaned part of the filter must be cut off from the vacuum supply. Here, then, is the reason for sectionating the filter area.

Origin.—George Moore, whose vacuum leaf filter marked the advent of the modern filter methods, early realized the limits of intermittent filtration. His first effort to effect a continuous machine was the design of a master mechanism which was a timing device to automatically operate his leaf filter. It was designed to lower the leaves into the tank; throw on the vacuum; after a given length of filtering time, to lift the leaves from the tank; to throw in another cable to bring the leaves over the wash water tank; to lower them, etc., etc., so as to complete the entire cycle. Such a mechanism was at once intricate and too inflexible to be a commercial success. Moore appreciated this sooner than some of his colleagues. He then borrowed from his technical training, and, analyzing the shortcomings of the rotary single compartment filter for fine crystals, set out to sectionate the drum into multiple compartments. Here was his start of a continuous filter embodying the advantages of the free cake formation, which was fundamental in his leaf filter. Moore, however, lost heart in filtration when his company passed into the control of promoters, rather than engineers, so that his filter development was sidetracked in favor of exacting royalties.

INDUSTRIAL FILTRATION

Before the Moore Filter Company passed out of existence, it licensed subsidiary company, the International Filtration Company, later reorganized as the Industrial Filtration Corporation, under the Moore process patents, to manufacture and sell filters to the industrial field. The Moore filter was redesigned and put out as the Zenith filter.

E. L. Oliver was a mining engineer, operating a cyanide mill contemporary with Moore. Oliver appreciated the possibilities of the rotary type machine, and used his ingenuity to effect a simple workable machine. Its control valve and the spiral winding of the drum, to hold down the



Courtesy Oliver Continuous Filter Company

FIG. 70.—OLIVER ACID-PROOF FILTER—CONTINUOUS DRUM FILTER.


For many materials, contact with iron causes contamination requiring a wood and bronze construction. This type of filter can be ruggedly built to meet such conditions.

cloth and to prevent the scraper cutting the cloth, spelled success for his Oliver filter.

Oliver had proven out his filter when a group of engineers at the Portland Mill of another gold cyanidation plant were attracted by Oliver's results. They endeavored to effect a contract to build their own filters under a license arrangement. The two parties could not agree, and the Portland engineers started out for themselves. They developed a better compartment sealing than Oliver had, but needed Oliver's wire winding. The Britters-Moore patent fight had been disastrous to both winding and using company, so that the potential fight between Oliver and the Portland Mill was obviated by an interchange of licenses under their respective

patents. The success of the Oliver and Portland filters demonstrates the wisdom of this arrangement.

For purposes of our discussion, the Oliver Filter is used to typify this group. Specific mention is made of one of the other filters in case of a decided difference from the Oliver. The Oliver is entitled to the position



Courtesy Industrial Filtration Corporation


FIG. 71.—Zenith Rotary Continuous Filter.

Maximum strength of materials of construction, pipe and port areas, etc., is the dominant feature in this design. With free filtering material the submerged part of the drum can be decreased so that the shaft and bearings are above the liquor level and free from contamination.

of leader, not only by the greater number of filters built and operating, but by reason of the greater service rendered in introducing the machine into many diverse fields of application.

Design.—In the Oliver filter the filter area is divided into compartments, each of which is independent and separate from every other. The mechanics employed are those patented and held by the Colorado Iron

Works,—the feature of their Portland Filter. In effect, each compartment is a panel, the filter cloth being secured in the longitudinal division strips by driving a stout rod, or mesh cord, into machined grooves after the filter



Courtesy Oliver Continuous Filter Company

FIG. 7a.—Details of Oliver Continuous Filter—Side View.


List of Parts:

- | | |
|-----------------------------|-------------------------|
| 1—Filter drum | 18—Bevel gears |
| 2—Steel filter tank | 21—Wood staves for drum |
| 3—Tank supports | 22—Division strips |
| 4—Tank memholes | 23—Filter medium |
| 5—Channel steel drum rims | 24—Wire winding |
| 6—Channel steel drum arms | 25—Steel scraper |
| 8—Hollow cast iron trunnion | 26—Scraper adjuster |
| 9—Steel drum shaft | 27—Apron |
| 10—Main bearings | 28—Vacuum and air pipes |
| 12—Worm drive gear | 30—Removable valve seat |
| 13—Worm shaft | 31—Automatic valve |
| 14—Oilwall for worm | 32—Vacuum connections |
| 15—Drive pulleys | 33—Air connection |
| 16—Wiring pulleys | 34—Valve stem |

The filter cloth is bound to the drum by spiral winding, which also prevents bulging of the cloth with reverse compressed air and serves to project the cloth from the scraper. Each compartment has two filtrate-collecting branch pipes leading to a common pipe which feeds through the rotating hub to the control valve.

Cloth has been pushed into the grooves. The compartment strips are tight against the drum, and the filter cloth is tight in the grooves on top of the strips, so that leakage is positively eliminated. The side edges of each compartment are sealed by wiring the cloth to the drum.

Each compartment has its own outlet pipe. In the Oliver, two outlets leave the compartment, but join together in one pipe, passing through the hub of the machine. One of these branches is located on the leading side,



Courtesy Oliver Continuous Filter Company

FIG. 73.—Details of Oliver Continuous Filter—End View.

List of Parts:

35—Wash water sprays	51—Scraper bearings
36—Wash solution sprays	52—Spur gear
37—Drain flange	53—Oscillator shaft bearings
42—Valve adjuster	54—Pulley shaft
43—Wire spacing nut	55—Intermediate shaft
44—Worm shaft bearings	56—Clutch shifter
45—Wiring sprockets	61—Valve pipe plates
46—Oscillator sprocket	62—Drum manhole
49—Shaft coupling	63—Oscillator shaft
50—Agitator crank	64—Connecting rod bracket
51—Agitator crank	65—Overflow weir
52—Wiring feed screw	66—Center spider
53—Jaw clutch	69—Connecting rod
54—Wiring screw bearings	


The ends of the drum are closed to reduce the amount of unfiltered liquor and a manhole is provided for assembly or repair to filtrate pipes. Wash water is sprayed upon the ascending cake from atomizing nozzles located above the drum. An oscillating agitator maintains uniformity of liquor within the container.

and the other on the lagging side of the compartment, so as to facilitate draining, irrespective of the angular position of the compartment.


The main outlet pipe from each compartment passes through the hub of the machine with the outlets of adjacent compartments side by side.

These are arranged in a circle, so that they register with the annular port in the stationary member of the valve.

Inasmuch as the sliding surfaces of the movable and stationary parts of the valve are ground surfaces, and consequently wearing surfaces, it is preferable to have these parts readily accessible and easily removed if in time they have to be replaced. In the Oliver filter this is taken care of by bolting to the rotating hub, or trunnion, a wearing plate in which holes are drilled registering with the outlet holes in the hub. This plate is now



Courtesy Colorado Iron Works Co.



Courtesy Colorado Iron Works Co.

FIG. 74.—Portland Filter—Drainage Compartment Uncovered.

Each compartment of a continuous filter is in effect an independent filter. Drainage of filtrate and means of sealing the filter cloth around the compartment are vital parts of the design of such filters.

FIG. 75.—Portland Filter—Compartments in Section.

Over a drainage member of wood or cast iron, a wire screen "C" is laid. Over the screen some porous fabric "F," as burlap, is often used to cushion the filter cloth "G."


the wearing surface of the filter, and saves deterioration of the filter proper. Before assembly to the filter this plate is ground into positive contact with the stationary member.

The keynotes of the valve is the stationary or outer cover of the valve. This is in reality a universal valve, controlling vacuum or compressed air supply to the individual valves. Its prime feature is the annular port and the blanks or bridges in this port. A hole in the center centralizes it on the shaft extending from the wear plate. The annular groove or port registers with the outlet holes of the wear plate, so that each compartment is in communication with the vacuum or compressed air, according to its position. The dividing member between vacuum and compressed air is a metal blank in this annular groove.

The lug or ear cast on the edge of the stationary member carries a pin

to which an adjustable rod is attached. This rod is bolted to the frame of the filter, or to the floor, and serves to hold the valve stationary. Adjustment is obtained by threading the nut of the rod to the desired position.

Consider the valve assembled so that the exterior of the stationary member, shown in the upper left hand corner of Fig. 76, is facing



Courtesy Oliver Continuous Filter Company

FIG. 76.—Oliver Continuous Filter—Automatic Valve.

The upper right-hand cut shows the under side of the piece shown in the upper left corner. The valve is assembled by bolting the removable wear plate and valve seat to the end of the filter, each hole registering with a filtrate pipe from a compartment. The stationary member is exhausted by the valve stem and held against the wearing plate by the valve spring and nut. Rotation of this member is prevented by the adjusting rod pin.

out. The large hole at the bottom is the filtrate connection. This, it will be seen, opens to the annular port and is designed to carry off all filtrate obtained from the time when the compartment submerges until it emerges from the liquor.

The reason that this outlet does not take any filtrate beyond that point is that the adjustable bridge closes the annular port. Note that the under side of the stationary head, as shown in the right hand corner of the cut, is not a sectional view, but the view seen when the right corner picture is

turned over on its right hand edge. This means that the bridge No. 7 is located to the left of the filtrate connection, as seen in the right hand corner picture. This bridge serves as a separator for the filtrate and for the wash effluent.

The weak filtrate, or wash effluent, is taken off by the large hole at the top. All filtrate obtained from the compartment after emerging, until arrival at the discharging position, is carried away from this opening. The bridge, as well as the other blanks, is ground in when the valve proper is ground so that the bridge is an effective seal. Note that the bridge is movable in the annular slot so that the arc in which the filtrate connection acts may be increased to any desired point above that of emergence. Also, the bridge is removable so that the wash effluent connection may be plugged up and all filtrate drained from the lower outlet. This flexibility of the outlets is a feature that often makes the difference between success and failure.

The entire mechanical arrangement of the Oliver filter is principally for the one function of complete discharge of the cake. This part of the valve is, therefore, the important part of the valve construction. In brief, it is the changing the compartment from vacuum suction to compressed air blow. If the bridge between the filtrate outlets is an effective seal the same construction would seem rational for the dividing member between vacuum and compressed air. The only difference, however, is that this bridge is made longer. The actual blow or reversed current is admitted through either one or all of the blow ports.

The compressed air connection is shown as No. 3 in the cut. A cored opening communicates with the three blow ports and those desired closed off are plugged with solid screw nuts, No. 5 in Fig. 76, easily inserted from the outside. The hollow stop leaves the blow part open but closes the internal cored passage from leakage to the outside.

After the compressed blow and discharge of the cake, the cleaned cloth must be idle until fully submerged. Another blank beyond the blow ports takes care of this.

Ground joints should be lubricated and, in the Oliver, valve grease cups are arranged for the outer and inner rims of the annular port.

Reverse compressed air is not alone an effective means of discharging the cake. First, the compartment is in a position so that gravity cannot assist; and second, the ballooning effect would tend to open up the cloth secured in the compartment division strips, hence a scraper or doctor is also required.

If a scraper is used like that prevailing in the single compartment old type filters its function should not be the same, for in the Oliver it is more of a deflector than a cutting plate; but it does become a true scraper if the cloth balloons out against it. To prevent this belling out of the cloth, E. L. Oliver patented the idea of spirally winding the surface of the drum with piano wire. The wire is spaced as close as $\frac{3}{4}$ in. centers, but can be wound in wider centers if the product being handled is easily discharged. Note that with spiral winding the scraper can be set up against the wire without endangering the cloth and, at the same time,

wear on the plates is uniform across the entire edge without any grooves becoming notched in it.

Since gravity does not assist the reverse air discharging the cake, the angle at which the scraper is set must be greater than the angle of rest of the discharged material. Also, the plane of the scraper should be a tangent to the drum at the point of discharge. These two factors preclude the scraper being set too high above the horizontal axis and in most machines it is located just above the center line of the machine.

If, in leaf filters, the uniform resistance of the cake made possible displacement washing of the cake, we may well expect that the cakes formed on Oliver filters offers a similar opportunity, if an approach can be obtained to the submergence of the leaf filter under the wash water. In addition to applying the water as a complete coating it is necessary not to disturb the cake formation by too forcibly applying the water, or by applying more water than can be wicked through the cake, for then the excess runs down the cake and erodes away the surface of the deposited solids and tends to weaken the strong liquor in the container. This means, then, that the water must be applied as a fine spray or dew directed against the cake. Spray nozzles are, therefore, located on the ascending side of the drum above the container and the amount of water fed to the cake regulated by an ordinary valve.

The time for washing is necessarily limited by the fact that the water application must be a maximum at the zenith of the travel. This would seem to be a limitation but, so long as the wash percolation is greater than the voids of the cake, the wash should approximate true displacement. A wide variation from this amount of wash water is an indication of either too high a vacuum pressure during filtration or else an improper distribution of the wash water. The secret of the excellent record of these filters as washing machines is that only relatively thin cakes are built up and their form preserved until washing is completed.

In continuous filters agitation in the filter tank to prevent settling of the coarse material is a necessary part of the design. Rotating paddles at the bottom of the tank and air lift connections taking the settlings and circulating them to the top of the liquor are not as effective as the oscillating arm agitator now adopted as standard. This device consists of a number of angle irons of equal legs attached to circular arms conforming to the curvature of the container. Side arms attached to the curved member terminate in cradles which hang on the bearing or shaft of the filter. A crank arm on a rotating shaft located behind the filter rocks the agitator back and forth so that the liquor is in constant motion.

Operation.—Being a continuous filter, the operation consists of once setting the valves, liquor level in container, the revolutions per hour of drum, position of the stationary head of the valve, washing sprays, and discharge scraper. In consequence, knowing how to start up the filter is knowing how to operate it at any time.

Mechanical lubrication should receive the first attention. This means oiling of bearings of shafts and of filter and turning down on grease cups,

especially those on filter valve. If a pump feeds the filter this should be oiled and stuffing boxes taken up liquid tight, but not too heavily.

The rotative speed being decided in advance, the driving belt should be located on the center of a cone step pulley and the filter rotated. Wherever the filter is equipped with an agitator attention should be given to clearing the container of bolts or other extraneous material which may have fallen into and could cause trouble by jamming the agitators.

Before starting filtration the drum should make several rotations with the container filled with the slurry. If wooden lagging is used on the drum, or wood construction used throughout, it may be necessary to first swell all the wood by filling container with hot water.

On starting the filtration the full displacement of the vacuum pump should be taken from the filtrate receiver only. After $\frac{1}{4}$ revolution the dry vacuum connection from the wash filtrate receiver can be cracked and after a full revolution opened up full. This procedure lessens the duty of the dry vacuum pump which would otherwise pull too much air through the exposed filter cloth above the liquor.

As soon as filtrate enters the receivers the exhausting pumps should be started. These pumps, especially if they are centrifugals of the usual type, should be piped up with a check valve in the discharge line and an equalizing line back to the receiver. This equalizer is simply a gas relief which insures any liquor in the receiver falling into the pump. The equalizer can be located on the suction line, or on the discharge line, although it is preferable to put it on the suction. The pumps must, of course, be located on a level below the bottom of the receiving tanks.

The dry vacuum line is connected to the top of the receiving tanks; the filtrate inlet is connected to a side opening and the filtrate outlet at the bottom. If the pumps fail to exhaust the filtrate as fast as it enters the receiving tanks, there is danger that the liquid will be drawn over into the dry vacuum pump. This machine is designed with very small clearances and liquid is not expected to be pumped by it, consequently, provision must be made to prevent the liquid rising into the vacuum lines.

In the Oliver tanks a float is provided which closes the vacuum line when the liquor rises to a given point in the tank. This seals the dry vacuum lines from liquid and saves the pump from possible injury.


Unless the material being handled cracks badly when subjected to the drying action, there should be a slightly higher vacuum on the compartment as it leaves the liquor than on the compartment during filtration. This requires, then, that a vacuum gauge be located on each of the two receiving tanks. Having a greater filtering force after the cake is built up, with its consequent resistance, means that more wash water can be pulled through the cake and a better dewatering effect obtained than if the filtering force is held constant throughout the operation.

The actual differential in vacuum is a variable depending upon the material being handled but, on the average, it will be found that a filtering pressure of 15 in. vacuum and a washing or dewatering pressure of 24 in. vacuum will give admirable results.

With those materials that crack quickly this differential is impractical.

It is far better to reverse the pressures, even lowering the dewatering pressure just enough to insure the cake adhering to the drum.

Washing is, in theory, displacement washing, so that effort is made to envelop the cake with a film of water as though the cake were submerged. At the same time, the water must not disturb or erode the cake, as otherwise the uniform resistance is not maintained. Therefore, the spray nozzles must be set close enough for the spray to land on the cake without disrupting it. The volume of spray must be within that which the vacuum pulls through the cake, or otherwise the excess will drain down the cake,



Courtesy Oliver Continuous Filter Company

FIG. 77.—Battery of Oliver Continuous Filters—Washing.

In order to prevent driftage of the starched wash water side plates are provided, the function of which is to prevent draughts reaching the spray and to localise the spray. On large machines it is practical to distribute six sprays through the washing arc to get a long washing cycle.


eroding it and contaminating the strong liquor in the tank. Driftage of spray should be prevented by curtaining against windage or prevailing drafts. Driftage is a nuisance around the machine and represents water that should have been used to wash the soluble from the cake.

Spray nozzles are made of varying designs, but in all a fairly high water pressure is required. If the water pressure is a variable the quality of the spray is not constant and in some plants it is advisable to independently pump the water required for washing. Dirt, scale from piping, rust, etc., should be kept from the nozzles as such matter often partly clogs the nozzle opening and prevents good atomization. If atomizers are continually plugging up it is well to independently filter this water.

Dewatering on Oliver filters is analogous to that of leaf filters and is economic only till crack or pit hole formation makes the air short circuit

too great. Rather than pull needless air through such cracks, it is good practice to blank off the drying port and let the filter run idle till the point of discharge.

Discharging requires that the cake be lifted from the cloth and that the scraper act as a deflector. This means that the reverse compressed air forcibly lift and disengage the cake from the cloth. Since the cloth is spirally wound with wire the reverse pressure can be much higher than practical with leaf filters. As it takes a fraction of a minute for the compartment to pass under the scraper, one blow of compressed air will issue



Courtesy Oliver Continuous Filter Company

FIG. 76.—Oliver Filters—Washing.


The wash water must be played on the surface of the cake completely and mildly—as a dew. Atomizing nozzles dividing the water into fine particles best accomplish this result.

through the cloth before the entire compartment is discharged, consequently, a second blow facilitates discharging the remaining cake. This successive back blowing is also economical in the use of compressed air making the total requirement for even a large filter that of a comparatively small compressor. The third blow hole in the blow back port is often advantageously used to further clean the cloth after the compartment has entirely passed the scraper.

There is an interval between the discharge of the cake and the new cycle of filtration and care should be taken that the blank in the annular port is long enough to allow the entire compartment to be completely submerged before filtration starts. If only part of the compartment is under the liquor the vacuum pump will pull air through the exposed cloth

and the vacuum pressure falls by reason of the added and unnecessary duty on the pump.

If the material being handled varies in its filtering characteristics, or if a new filter is being put into operation, some adjustment is very likely needed in setting the positions of the blanks between the different ports. The blank between filtrate and wash effluent should be fixed so that only strong filtrate drains into it. If a resistant cake is formed this blank can be moved up to a higher position than when a more open cake is deposited. If the cake cracks too much the blank in front of the blow ports should be carried back, although never short of the zenith of the



Courtesy Oliver Continuous Filter Company

FIG. 79.—Oliver Filter Discharging.

The scraper rests against the wire winding and reverse compressed air lifts the cake from the cloth so that the scraper acts as a deflector. The angle of the scraper must be steep enough to insure the cake falling from it.

travel of the drum. Also, with some quickly classifying materials the dead blank prior to filtration can well be extended so that the compartment starts filtering at the lowest point of travel.

There are other points in the operation of Oliver filters such as housing over the drum when hot or volatile liquors are handled, installing condensers on dry vacuum line to save duty on vacuum pump, etc., but after once fixing these conditions the machine operates automatically. Periodic inspection is required only to insure mechanical operation, liquid is flowing to the filter tank, that the clarity is maintained and discharging is complete.

Layout.—The layout for the Oliver filter closely parallels the layout for the vacuum leaf filter, at least in its accessory equipment. The difference in accessory units lies in the fact that there is a continuous load rather

than periodic peaks and slack intervals so that the individual units can be smaller for the same daily or hourly production.

The layout varies with the work being done. There is the simple arrangement for straight dewatering of cold liquors, a moisture trap or condenser for dewatering hot liquors, separate receivers for washing the cake from cold liquors with a moisture trap when handling hot material. Each case is further modified by whether dry or wet vacuum system is employed.

The filter must be set up so as to have a free drain for unfiltered liquor at end of run and for washing down of machine. There should be sufficient headroom provided to lift out the drum should it need overhauling at any time. The location is preferable where sufficient room is provided for the accessories close to the filter, as observation control on these should be convenient when regulating filter.

The material to be filtered must flow freely to the machine with a minimum number of turns, all elbows eliminated and substituted with plugged tees or crosses. A regulating valve, preferably of delicate adjustment, should be handy to filter so that level of liquor is easily maintained.


Agitation is provided in the mechanism of the machine itself and the rocking plow type is generally the most efficient. The liquor level can be maintained at any desired height but the control valve must be adjusted, if the level is low, so that the compartment re-entering the liquor is fully submerged before starting filtration.

For work of dewatering only, when using the dry vacuum system, the layout comprises one vacuum receiving tank, one dry vacuum pump and one exhaust for the filtrate. The latter can be a barometric leg, when the elevation of the vacuum receiving tank is at least 30 feet above the point of discharge of the filtrate, or a centrifugal pump can be used, provided the vacuum receiving tank is placed above the pump so that there is head of 1.5 times the vacuum pressure in excess of 22 in. on the pump. This insures gravity flow to the pump and enables a centrifugal pump to exhaust the filtrate. If a hot liquor is handled, a moisture trap or other means of condensing the steam vapor is placed in the vacuum line so as to prevent any condensate precipitating in the dry vacuum pump and straining or breaking any of its parts.

If the wet vacuum system is used for dewatering only, the filtrate line is piped directly to the wet vacuum pump and the discharge from it is both filtrate and air. The Nash Hytor Pump is especially advantageous for this work, but if the filtrate is to be delivered to a level higher than the pump an auxiliary lifting pump of ordinary centrifugal design is required. If cold filtrate, or, where permissible, cold water, is added to the circulating liquor in the Nash Hytor all steam vapor is condensed even when handling hot liquors. This pump, however, will handle the product even if the vapor is not condensed.

When handling liquors, cake of which must be washed, and it is desired to separate the weak wash filtrate from the strong filtrate, two vacuum receivers and two means of exhausting the liquor are required, when using the dry vacuum system. To one receiver is piped the filtrate obtained

from the main filter outlet on the valve and to the other the wash filtrate obtained from the other outlet which receives the wash only. Only one vacuum pump is necessary and otherwise the system is identical with dewatering cold liquors. When hot liquors are handled, a moisture trap is again necessary in the main dry vacuum line.



Courtesy Oliver Continuous Filter Company

FIGS. 80 and 81.—Layouts of Oliver Filter.

All filtrate, strong and weak, can drain to one receiver, from which it is exhausted by a centrifugal pump, or strong filtrate can be collected in one receiver and the weak filtrate in another, and any condensation in a moisture trap is exhausted at the foot of a barometric leg.

When washing the cake and using the wet vacuum system two wet vacuum pumps are required if the main filtrate and wash effluent are to be separated.

If the exhaust pumps are oversize for the amount of filtrate obtained and are electrically connected or driven from the same motor as the vacuum pump, there is but small danger of liquor being drawn over into the vacuum pump when using the dry vacuum system. As a precaution, however, the vacuum receivers on Oliver filters are provided with automatic floats which cut off the vacuum inlet when the liquor rises above a given limit in the receivers and thus preclude all possibility of liquor entering the vacuum pump.

Advantages.—There are a number of advantages in the continuous filter that are prominent and obvious but probably most important is its fool-proof operation. Its efficiency is almost entirely free of the personal equation of the operator. The lowliest laborer can tighten up grease cups, oil the bearings of a slowly revolving filter and watch that the discharge hopper does not jam. He has nothing to do with the time of filtration, with the extent of the washing cycle, or manipulating valves in order to hold positive pressure during transferences of liquors. The universal valve does everything for him, automatically, so that his personal efficiency is a factor of practically zero importance. Constancy of product is of first importance and fool-proof operation is its best guarantee.

Labor saving, or as it is better called labor productivity, is practically a maximum with Oliver filters. Even a battery of machines requires less than one man's time so that a single operator can filter and discharge immense tonnages. The labor productivity is pretty close to a maximum for it is only when recovering the drum that any real labor is involved. This is required whenever the filter cloth is worn out or plugged up and depends upon the material being handled. It may be necessary to do this once a year or once every two weeks. Relatively, however, recovering the filter is less frequent than with any of the intermittent operating filters.

Washing the cake free of solubles in the Oliver filter is the most uniform of the filters so far discussed. The cake is maintained in its equilibrium condition more positively than in leaf type filters, and the time of washing is fixed by the arc of rotation set for wash filtrate. While it may not be possible to completely free the last trace of soluble, and varying quantities of water are required, depending upon the porosity of the cake, still, on the average, the washing efficiency stands highest in these filters.

Good discharge of the cake is vital to any filter and whenever it is complete for cycle after cycle it can be called an advantage in favor of that filter. This is the case in the Oliver, and more, the discharge is truly automatic. In leaf filters the operator must manipulate the valve for reverse compressed air—in the Oliver, the universal valve admits the reverse pressure without any one handling any valve. Being able to rest the scraper against the wire winding on the drum makes the work of the compressed air simply that of disengaging the cake from the cloth—it does not have to push it away from the leaf as in leaf filters. It is only when the thickness of the cakes is $\frac{3}{4}$ in., or less, that any trouble occurs in discharging and, as the large majority of rotary drum filters work on materials forming cakes at least $\frac{3}{4}$ in. thick, it can be safely stated that discharge is positive at all times. There are instances where the cloth becomes clogged, but these cakes are examples of poor selection of filter cloth rather than faulty operation of the filter.

The above advantages can be considered obvious but in the principle of operation there lies a fundamental advantage of marked importance. The time of filtration is a variable depending on the amount of submergence and the rotative speed. With the submergence constant, the filtering period is lessened with an increase in the rotative speed and conversely. In consequence, there is a balance for each material whereby

maximum production is obtainable. When once set, the filter then operates within the economic part of the filtering curve. This facility makes an efficiency of operation theoretically, but not practically, possible with intermittent filters. This advantage is limited to those materials which will form cakes of sufficient thickness for discharge, but is an essence of the possibilities of this type of machine.

Observation of the work being done is a requirement in any filter. Convenient observation means superiority in any filter and surely this is the case with continuous drum filters. The exposed cake on the ascending



Courtesy Oliver Continuous Filter Company

FIG. 8.—Oliver Filter with Repulping Trough.

Whenever the required wash cannot be obtained in one machine so that it is necessary to mix the cake from one filter with weak liquor or water and treat the mixture on a subsequent filter, it is advantageous to repulp the cake as it falls from the scraper. A repulping trough is also required when a succeeding operation requires the material be again suspended in a liquor—as in paper mills manufacturing direct from wood pulp which is washed on continuous filters.

drum, the discharged cake, the cleaned cloth dropping down below the drum, the discharged cake, the cleaned cloth dropping down below the scraper, and the wash water application are squarely in view and the ease of observation is truly a marked advantage.

Drawbacks.—The greatest weakness in the operation of Oliver filters is in the dryness of cake discharged. Sucking air through the cake in order to displace the entrained moisture is comparable to the drying cycle in pressure leaf filters. Cake cracking opens up paths of short circuit and defeats real dewatering of the cake. In this respect plate and frame filters are a distinct advantage where a compression of the cake is obtainable.

Washing the cakes depends upon the porosity of the cake to a large measure. If the material being handled changes so that an increased resistance is built up the water sprayed upon the cake must be throttled or else the excess will drain back into the container. This condition is

impossible for good results and requires, therefore, a measure of operator's control that should not be necessary with a continuous machine. This same condition of faulty application of washing water can also arise from inadequate pressure on atomizers. This cannot be blamed on the operator or on the design of the machine save only that it is an essential that makes the machine less self-contained.

Applying the wash water upon the cake is by atomization, so as to approach dewing water on the surface of the cake. For many materials this means atomizing to a mist fine enough to be drifted by the draught from an open window. This is a misdirection of the water, giving the cake less water than is needed and wetting the surroundings. Side curtains prevent these draughts but also detract from that important factor of easy observation and are only a make-shift wherever used.

Adequate pressure must be maintained on the atomizers and scale, or rust, or other extraneous dirt often fouls the nozzles spoiling the spray. The dew-like spray becomes a sturdy stream or is stopped up completely, either of which is contrary to the design of the washing method.

Discharging the cake by the joint action of reversed compressed air and scraper is effective wherever the cake is coherent enough for the air to lift it from the filter cloth. Thin cakes are often lacking in this quality and, consequently, the filter must be rotated at a speed enabling a thick cake to form. In these cases the capacity suffers by the reduced speed and, in some cases, becomes too small to admit the application of these filters.

Where difficult discharging materials are encountered the reverse air is admitted at a higher pressure. It is good practice then to spirally wind the wire around the drum on closer centers. The area covered by the wire is, after a short time, dead filter area and hence the effective area on the drum is reduced. This becomes a drawback when comparing this filter with one using less or no wire winding.


Positive clarity of filtrate is often impossible to obtain when the valve is supplied with two outlet ports only,—the usual design. The filter cloth will allow some solid to pass through it at the start of filtration and the first runnings cannot be separated from that obtained later and consequently clarity is a function of the filter cloth.

In industrial work, metal to metal surfaces are subjected to hard wear. Corrosion and erosion make the use of ground disk valves poor practice at best. The flat grinding disk valve in the Oliver filter is a drawback inherent in its design.

Depending on the filtration of air through the cake to displace the moisture in the cake is the conventional means of dewatering the cakes. The moisture content in the discharged cake, therefore, compares favorably with the pressure leaf filters but unfavorably with compressed cakes as obtained on plate and frame presses. Recovering the filter with new cloth requires removing the wire winding on the drum and the old filter cloth, then putting on the new cloth and rewinding the drum. In large filters this is a time taking job, and as such is a weakness in the design of the filter.

In the usual design, the maximum submergence is 35 per cent of the drum. This means that in the cycle only $\frac{1}{3}$ of the time is given for filtration. For most materials this is sufficient, but for others this filter would be more efficient if the submergence were increased.

The area obtainable in the Oliver filter is that of the exterior of the drum. Filter area of 200 sq. ft., or more, requires drums 8 ft. or more,



Courtesy Oliver Continuous Filter Company

FIG. 83.—Oliver Filter—Large Dewatering Unit.

To aid the dewatering effect of filtering air through the exposed cake, it is practical, with a limited number of materials, to mount compressing rolls directly in contact with the cake. A slippage is required, hence the drive on these rolls which are often heated.

in diameter. Floor space and head room are required in excess of those filters wherein the filter area is in the form of filter leaves disposed as cross sections of the drum.

Applications.—The Oliver filter originated as an improved filter for cyanide slimes. It naturally spread to all mining mills and has been particularly successful on ore concentrates. The calcium saccharate in the beet sugar industry is largely handled on this continuous filter. Washing

of wood pulp has been demonstrated a big success in the paper industry. Free filtering solids of all descriptions, save those in highly corrosive, hot or superheated liquors are handled by the Oliver. Difficult materials, when thickened as obtained from Dorr Thickeners, are handled with marked success with these machines.

Summary.—The tremendous success established by the Oliver filter is proof of the adaptability and practicability of vacuum continuous filters. Correction of some mechanical shortcomings in this filter has been made the basis for another vacuum filter, the American Continuous, but in this some of the advantages of the Oliver have been lost, as will be discussed in the following chapter.

Chapter VI.

Section II—American Continuous Filter.

When the United Filters Corporation was formed, it was the consolidation of the two leading pressure leaf filter companies: The Kelly Filter Press Company and the Sweetland Filter Press Company. This combination reduced competition and made possible the better distribution and sales of these filters. The competitor now was the Oliver Continuous Filter Company. The Oliver filter, being a continuous machine, had the grip on the industrial field where continuous filters were applicable. The American Continuous Filter is the continuous filter put out by the United Filters Corporation to compete with the rotary drum continuous filters on the ground of superior design.

The main theme underlying the design of the American Continuous Filter was to obtain large filter areas without necessitating large diameter drums so that a filter area of approximately 2000 square feet can be practically constructed and operated. The sectionated disk type of leaf, mounted transverse to the rotating shaft, was the simplest means of obtaining this desired end.


The advent of the American Continuous Filter on the market ended a long standing controversy on the relative values of vacuum filtration (which is always limited to the theoretical pressure of the barometer) and pressure filtration (which is limited only by the strength of the machine used). The American Continuous Filter became an endorsement of continuous vacuum filtration, and ended this controversy.

Its principle of operation does not vary from that of the original machine invented by Moore, years ago, or the principle used in rotary drum filters. The mechanical arrangement is the only difference, and this we shall take up in detail.

Design.—If the transverse leaf made up of pie-shaped, or sector sections, is the main theme in the design of this filter, there is a number of ingenious points that gives this machine the merits it has.

First, no wire winding of the cloth is required; second, a self-seating and self-grounding valve is used; and third, the separate pan construction as the container for the individual leaves is unique.


The leaves have for their basis of construction the same principle as used in the filter leaves of the Sweetland and Kelly filters. In other words, each individual section of the leaf is made up of a drainage member; an outlet nipple with a filter cloth bag enveloping the drainage member; and, secured to the outlet nipple, each filter disc is composed of eight or more individual sector sections and is assembled by dropping the outlet nipple



Courtesy United Filter Corporation

FIG. 84.—American Continuous Filter.

The filter area is divided into discs, each in turn divided into sectors, mounted on a rotatable shaft. The cake is discharged between adjacent leaves into a conveyor or hopper located beneath the filter.



Courtesy United Filter Corporation

FIG. 85.—Filter Disc or Leaf—American Continuous Filter.

Each sector in the leaf has an outlet pipe at its center which fits into openings on the filtrate channels. Each corresponding sector of every leaf functions simultaneously on this account. The leaves must be true planes and therefore the drainage member is best constructed of rigid material, as grooved wood, cast iron, etc. The leaves are assembled, each sector being inserted with its bag clamp, frame clamp and nuts threaded on the radial rods.

into its receiving port located on one of the main collecting conduits. The sector leaves are aligned by clamps secured at each radial aligning rod with a nut.

As many filter discs as are required are distributed along the machine, the individual sectors in each disc in the same arc of rotation feed into the same collecting conduit. Consequently, the one valve registers vacuum or compressed air to each sector in every disc.

By making up the filter cloth as a bag open at the outer curved end and a small hole through which the outlet nipple can slip through, hand sewing of the cloth to the sector shapes is eliminated. After slipping the bag over the drainage member the outer edges are lapped over and held in place by a curved U shape which fits over the periphery. This greatly reduces the labor required in putting on new filter cloth.

The drainage member must be rigid and a true plane. For these specifications corrugated wood drainage boards or cast-iron members are preferable to wire screen. The need of these specifications are apparent if the scrapers dislodging the cake are to function well and not dig into the cloth.

It is equally important that the radial rods be normal to the axis and in true alignment. It is often necessary to slightly bend these arms to obtain this alignment and then spot weld them in place so as to secure them. Apropos of this, it should be noted that only small wrenches should be used to back off the nuts that hold down the peripheral aligning clamps. If a nut rusts to the shaft a long-handled wrench may provide enough leverage to break the weld at the base of the rod. Resetting the rod is a mean job after the machine is installed and working.

When assembling the leaves in the disc the outlet nipple rests on a sealing gasket. This is generally soft rubber and there is no demand that the clamps be made up more than will insure proper seating of the nipple on the gasket.

The filtrate conduits register with a cored casting in which is incorporated the bearing for the shaft at the valve end, and the rotating member of the valve. The latter is fitted with a renewable internal cone sleeve. This is drilled to register with the terminals of the conduits. The stationary member of the valve is a cone to fit the interior of the sleeve of the rotating member. These parts fit in a manner very similar to the standard plug cock. The stationary part is ported with provision to catch filtrate, to separate wash water and to admit compressed air. An additional port to vent the compressed air is very serviceable if the filter cloth is tight and tends to deflate too slowly. The two surfaces of the cones are kept in self-grinding contact by a heavy spring located inside on a central rod. Pressure is thus even all over and any wear is taken up automatically by the tension of the spring. This valve is one of the best and most serviceable features of this filter.

The container in which the discs rotate is unique in its design. Note that cake is built on vertical surfaces and provision must be made to take care of the discharge from the adjacent leaves. The required space between the leaves is obtained by making separate narrow pans for each disc,